

NONMEM Users Guide - Part V

Introductory Guide

Oct 2024

by

Alison J. Boeckmann

Lewis B. Sheiner

Stuart L. Beal

NONMEM Project Group  
University of California at San Francisco

ICON plc, Blue Bell, PA.

Copyright by the Regents of the University of California  
1994, 2009  
Copyright by ICON plc  
2011, 2012, 2013, 2015, 2017, 2020, 2024  
All rights reserved

**Preface**

This edition of "NONMEM Users Guide - Part V Introductory Guide" is distributed with NONMEM 7.6.0. It revises the version of September 2020, which appeared with NONMEM 7.5. Details that have changed since the previous edition have been corrected, and some new features have been added.

Significant changes since the previous version are marked with bars.

With this new edition, examples of NONMEM outputs have been updated to the NONMEM 7.6.0 version as needed.

True to its purpose as an instructional guide for new users of NONMEM, this Guide remains oriented to the classic NONMEM methods and basic features (through NONMEM VI). References to even earlier versions of NONMEM and PREDPP have been deleted.

Chapter 12 (Brief Descriptions of Other Features) has been revised. Sections 1-5 have been expanded to be more complete. Section 6 ("Supplemental List of Features through NONMEM 7.6.0") is a summary of all features of NONMEM not mentioned elsewhere in this guide.

## Table of Contents

|  |    |
|--|----|
| Chapter 1 - Introduction to NONMEM, PREDPP, and NM-TRAN . . . . .      | 1  |
| What This Chapter is About . . . . .                                   | 1  |
| Introducing NONMEM . . . . .   | 1  |
| What is NONMEM? . . . . .  | 1  |
| What is PREDPP? . . . . .  | 1  |
| What is NM-TRAN? . . . . .   | 2  |
| Scope of this Introductory Guide . . . . .                             | 2  |
| Contents of this Introductory Guide . . . . .                          | 3  |
| How to Read this Guide . . . . .                                       | 3  |
| A Brief Technical Overview . . . . .                                   | 4  |
| NONMEM . . . . .   | 4  |
| PREDPP and the PREDPP Library . . . . .                                | 4  |
| Subroutines PK and ERROR . . . . .                                     | 4  |
| Building an Executable Module for NONMEM . . . . .                     | 5  |
| NM-TRAN . . . . .  | 5  |
| Control Language Translation . . . . .                                 | 5  |
| Model Specification via Abbreviated Code . . . . .                     | 5  |
| Partial Differentiation . . . . .                                      | 6  |
| Data Preprocessor . . . . .  | 6  |
| Additional Documentation . . . . .                                     | 6  |
| Chapter 2 - NONMEM Examples . . . . .                                  | 8  |
| What This Chapter is About . . . . .                                   | 8  |
| An Individual's Theophylline Kinetics . . . . .                        | 8  |
| The NM-TRAN Control Records . . . . .                                  | 8  |
| The Model . . . . .  | 9  |
| The Output . . . . .   | 10 |
| A Population Model for Phenobarbital . . . . .                         | 12 |
| The NM-TRAN Control Records . . . . .                                  | 13 |
| The Model . . . . .  | 13 |
| The Output . . . . .   | 14 |
| Overview . . . . .   | 21 |
| Chapter 3 - Models for Individual Data . . . . .                       | 23 |
| What This Chapter is About . . . . .                                   | 23 |
| Pharmacokinetic Structural Models for Individual Data . . . . .        | 23 |
| Alternative Parameterizations . . . . .                                | 24 |
| The Scale Parameter, $S$ . . . . .                                     | 24 |
| $S$ Depends on a Known Constant . . . . .                              | 24 |
| $S$ Depends on a Parameter . . . . .                                   | 25 |
| $S$ Depends on an Element of $\mathbf{x}$ . . . . .                    | 25 |
| Statistical Model for an Individual's Observations . . . . .           | 25 |
| The Additive Error Model . . . . .                                     | 27 |
| The Constant Coefficient of Variation and Exponential Models . . . . . | 27 |
| Combined Additive and CCV Error Model . . . . .                        | 28 |
| The Power Function Model . . . . .                                     | 29 |
| Two Different Types of Measurements . . . . .                          | 29 |
| Use of an Indicator Variable . . . . .                                 | 29 |
| Two Different Types of Observations . . . . .                          | 30 |
| More Than One Indicator Variable . . . . .                             | 30 |

|  |    |
|--|----|
| The General Mixed Effects Model for an Individual . . . . .                            | 31 |
| Chapter 4 - Models for Population Data . . . . .                                       | 32 |
| What This Chapter is About . . . . .   | 32 |
| General . . . . .  | 32 |
| Structural Parameter Models . . . . .  | 33 |
| Linear Models . . . . .  | 33 |
| Multiplicative Models . . . . .  | 34 |
| Saturation Models . . . . .  | 34 |
| Models with Indicator Variables . . . . .  | 35 |
| Combinations . . . . .   | 35 |
| Time Varying $z$ . . . . .   | 35 |
| Structural Kinetic Models . . . . .  | 36 |
| Population Random Effects Models . . . . .   | 36 |
| Models for Interindividual Errors . . . . .  | 36 |
| Additive/Multiplicative Models and the Exponential Model . . . . .                     | 37 |
| Other Models . . . . .   | 37 |
| General Form for the Parameter Model . . . . .   | 38 |
| Statistical Models for an Individual's Observations . . . . .                          | 39 |
| The Population Mixed Effects Model . . . . .   | 39 |
| Chapter 5 - Estimates, Confidence Intervals, and Hypothesis Tests . . . . .            | 41 |
| What This Chapter is About . . . . .   | 41 |
| Model Fitting Criterion . . . . .  | 41 |
| Least Squares for Individual Data with an Additive Error Model . . . . .               | 41 |
| Least Squares for Individual Data with Other Types of Error Models . . . . .           | 41 |
| Least Squares for Population Data . . . . .  | 42 |
| Parameter Estimates . . . . .  | 43 |
| Precision of Parameter Estimates . . . . .   | 43 |
| Distribution of Parameters vs Distribution of Parameter Estimates . . . . .            | 44 |
| Confidence Interval for a Single Parameter . . . . .                                   | 44 |
| Estimating a Parameter's Standard Error . . . . .                                      | 45 |
| Relating the Confidence Interval to the <b>SE</b> . . . . .                            | 45 |
| A Confidence Interval for a Function of a Single Parameter . . . . .                   | 45 |
| Multiple Parameters . . . . .  | 45 |
| Correlation of Parameter Estimates . . . . .   | 45 |
| Confidence Intervals for a Function of Several Parameters . . . . .                    | 46 |
| Hypothesis Testing . . . . .   | 46 |
| Hypothesis Testing Using the <b>SE</b> . . . . .                                       | 47 |
| Hypothesis Testing Using the Likelihood Ratio . . . . .                                | 47 |
| Definition — Full/Reduced Models . . . . .   | 47 |
| Reduced/Full Models Express the Null/Alternative Hypotheses . . . . .                  | 47 |
| The Likelihood Ratio Test . . . . .  | 48 |
| Choosing Among Models . . . . .  | 48 |
| Chapter 6 - Data Sets, \$DATA and \$INPUT Records, and the Data Preprocessor . . . . . | 50 |
| What This Chapter is About . . . . .   | 50 |
| Data Sets for NONMEM . . . . .   | 50 |
| Data Records . . . . .   | 50 |
| Data Items . . . . .   | 50 |
| Clinical Data and Data Conversion . . . . .  | 51 |
| Data Sets for PREDPP . . . . .   | 52 |

|   |    |
|---|----|
| The \$DATA Record . . . . .   | 52 |
| The \$INPUT Record . . . . .  | 54 |
| Data Item Labels . . . . .  | 54 |
| Reserved Labels and Synonyms . . . . .                                  | 54 |
| Dropping Data Items via DROP . . . . .                                  | 55 |
| NONMEM Data Items . . . . .   | 55 |
| DV Data Item . . . . .  | 55 |
| ID Data Item for Population Data . . . . .                              | 55 |
| MDV data item . . . . .   | 55 |
| PREDPP Data Items . . . . .   | 56 |
| TIME Data Item . . . . .  | 56 |
| AMT, RATE, SS, II: Dose-related Data Items . . . . .                    | 56 |
| EVID Data Item . . . . .  | 56 |
| CMT and PCMT Data Items . . . . .                                       | 57 |
| CALL Data Item . . . . .  | 58 |
| Describing Doses to PREDPP . . . . .                                    | 58 |
| Dose-related Data Items . . . . .                                       | 58 |
| Different Kinds of Doses . . . . .                                      | 59 |
| Instantaneous Bolus Doses . . . . .                                     | 59 |
| Infusions . . . . .   | 59 |
| Steady-State Doses . . . . .  | 60 |
| Steady-State with Multiple Bolus Doses . . . . .                        | 60 |
| Steady-State with Multiple Infusions . . . . .                          | 61 |
| Steady-State with Constant Infusion . . . . .                           | 62 |
| Multiple Steady-State Doses . . . . .                                   | 63 |
| Combining Non-Steady-State Doses with Steady-State Doses . . . . .      | 64 |
| The Output Compartment: Urine Collections and Observations . . . . .    | 64 |
| The Data Preprocessor . . . . .   | 65 |
| Day-time Translation . . . . .  | 65 |
| TIME Data Item . . . . .  | 65 |
| DATE Data Item . . . . .  | 66 |
| Calendar Dates . . . . .  | 66 |
| Converting Hours to Days and More General Conversions . . . . .         | 67 |
| The Year 2000 - LAST20 . . . . .  | 68 |
| Leap Year Warning - LYWARN . . . . .                                    | 68 |
| Interdose Interval (II) Conversion . . . . .                            | 69 |
| Data Items Generated by the Data Preprocessor . . . . .                 | 69 |
| When Must a Format Specification be Included or Omitted? . . . . .      | 69 |
| Skipping Data Items . . . . .   | 70 |
| Chapter 7 - \$SUBROUTINE Record and \$PK Record . . . . .               | 71 |
| What This Chapter is About . . . . .                                    | 71 |
| The \$SUBROUTINE Record . . . . .                                       | 71 |
| Choosing an ADVAN Subroutine: Standard Pharmacokinetic Models . . . . . | 71 |
| Choosing a TRANS Subroutine: Alternative Parameterizations . . . . .    | 72 |
| \$PK Abbreviated Code . . . . .   | 73 |
| Syntax . . . . .  | 73 |
| When are \$PK Statements Evaluated? . . . . .                           | 74 |
| Time Varying PK parameters . . . . .                                    | 74 |
| \$PK Statements for Individual Data . . . . .                           | 75 |
| Basic and Additional Parameters . . . . .                               | 75 |

|   |    |
|---|----|
| Alternative Parameterizations using \$PK Statements . . . . .                                     | 76 |
| Scale Parameters . . . . .  | 77 |
| Scaling by a Known Constant . . . . .   | 77 |
| Scaling by a Parameter: Conditional Statements and Indicator Variables . . . . .                  | 77 |
| Scaling by a Data Item . . . . .  | 78 |
| Bioavailability Fraction Parameters . . . . .   | 79 |
| Output Fraction . . . . .   | 79 |
| \$PK Statements for Population Data . . . . .   | 80 |
| Structural Part of Parameter Models . . . . .   | 80 |
| Linear Models . . . . .   | 80 |
| Multiplicative Models . . . . .   | 80 |
| Saturation Models . . . . .   | 80 |
| Models with Indicator Variables . . . . .   | 81 |
| Population Random Effect Models . . . . .   | 81 |
| Models for Interindividual Errors . . . . .   | 82 |
| Additive/Multiplicative Models . . . . .  | 82 |
| Other Models . . . . .  | 82 |
| Restrictions on Random Variables . . . . .  | 82 |
| Chapter 8 - \$ERROR Record . . . . .  | 84 |
| What This Chapter is About . . . . .  | 84 |
| \$error Abbreviated Code . . . . .  | 84 |
| Syntax . . . . .  | 84 |
| When are \$ERROR Statements Evaluated? . . . . .  | 84 |
| Error Models . . . . .  | 85 |
| The Additive Error Model . . . . .  | 85 |
| The Constant Coefficient of Variation and Exponential Models . . . . .                            | 85 |
| Combined Additive and CCV Error Model . . . . .   | 85 |
| The Power Model . . . . .   | 85 |
| Two Different Types of Measurements . . . . .   | 85 |
| Two Different Types of Observations . . . . .   | 86 |
| More than One Indicator Variable . . . . .  | 86 |
| Chapter 9 - Additional NM-TRAN Records . . . . .  | 87 |
| What This Chapter is About . . . . .  | 87 |
| Providing Initial Estimates For $\theta$ : The \$THETA Record . . . . .                           | 87 |
| Providing Initial Estimates For Elements Of $\theta$ . . . . .                                    | 87 |
| Providing Constraints for Elements of $\theta$ . . . . .  | 87 |
| Fixing Elements of $\theta$ . . . . .   | 88 |
| How to Obtain Initial Estimates for $\theta$ . . . . .  | 88 |
| Providing Initial Estimates for $\Omega$ and $\Sigma$ : the \$OMEGA and \$SIGMA Records . . . . . | 88 |
| \$.OMEGA Record With Individual Data . . . . .  | 89 |
| \$.OMEGA Record With Population Data . . . . .  | 89 |
| The \$.SIGMA Record . . . . .   | 89 |
| Fixing Elements of $\Omega$ or $\Sigma$ . . . . .   | 89 |
| How to Obtain Initial Estimates for $\Omega$ and $\Sigma$ . . . . .                               | 90 |
| Specifying Optional Tasks . . . . .   | 91 |
| Requesting the Estimation Step: the \$ESTIMATION Record . . . . .                                 | 91 |
| Requesting the Covariance Step: the \$COVARIANCE Record . . . . .                                 | 92 |
| Specifying Optional Output . . . . .  | 92 |
| Requesting the Table Step: the \$TABLE Record . . . . .   | 93 |

|   |     |
|---|-----|
| Requesting Scatterplots: the \$SCATTERPLOT Record . . . . .                     | 93  |
| Placement and Order of Records . . . . .  | 93  |
| INCLUDE records . . . . .   | 94  |
| Chapter 10 - Reading the Output . . . . .                                       | 95  |
| What This Chapter is About . . . . .  | 95  |
| NONMEM Describes its Inputs . . . . .   | 95  |
| PREDPP Describes Its Inputs . . . . .   | 98  |
| Diagnostic Output from the Estimation Step . . . . .                            | 100 |
| Intermediate Output from the Estimation Step . . . . .                          | 100 |
| Summary Output from the Estimation Step . . . . .                               | 102 |
| Minimum Value of the Objective Function and Final Parameter Estimates . . . . . | 102 |
| Output from the Covariance Step . . . . .                                       | 103 |
| Additional Output: Tables and Scatterplots . . . . .                            | 104 |
| Output from the Table Step . . . . .  | 104 |
| Output from the Scatterplot Step . . . . .                                      | 104 |
| Chapter 11 - Model Building . . . . .   | 106 |
| What This Chapter is About . . . . .  | 106 |
| The Stages of Model Building . . . . .  | 106 |
| Check-out — Index Plots . . . . .   | 108 |
| Building the Structural Part of the Model . . . . .                             | 113 |
| A General Approach . . . . .  | 113 |
| The Minimal Model . . . . .   | 114 |
| Use of Constraints . . . . .  | 115 |
| Diagnostic Tools . . . . .  | 115 |
| Plot of DV vs PRED . . . . .  | 116 |
| Residual Plots . . . . .  | 116 |
| Index Plots of Residuals . . . . .  | 117 |
| Plot of WRES vs Independent Variable . . . . .                                  | 118 |
| Judging Goodness of Fit . . . . .   | 119 |
| A Global Measure — Change in the Objective Function . . . . .                   | 120 |
| Decrease in Unexplained Variability . . . . .                                   | 120 |
| Improvement in Plots . . . . .  | 120 |
| Using the Tools: Further Improvement . . . . .                                  | 122 |
| An Additional Effect of WT . . . . .  | 122 |
| The Effect of APGR . . . . .  | 124 |
| Building the Statistical Model . . . . .  | 126 |
| Judging Among Alternatives . . . . .  | 126 |
| Unexplained Variability . . . . .   | 127 |
| Residual Plots . . . . .  | 127 |
| Refine Model . . . . .  | 129 |
| Use of Standard Errors and Confidence Intervals . . . . .                       | 130 |
| A Model Refinement . . . . .  | 131 |
| Testing the Model . . . . .   | 132 |
| Chapter 12 - Brief Descriptions of Other Features . . . . .                     | 133 |
| What This Chapter is About . . . . .  | 133 |
| Advanced Features of PREDPP . . . . .   | 133 |
| Pharmacodynamic Modeling Using the \$ERROR Record . . . . .                     | 133 |
| Other Pharmacokinetic Models: ADVAN5-9, ADVAN13-ADVAN18 . . . . .               | 134 |
| Zero-Order Bolus Doses . . . . .  | 135 |
| The Additional Dose Data Item: ADDL . . . . .                                   | 136 |

|  |     |
|--|-----|
| Lagged doses: the ALAG Parameter . . . . .   | 136 |
| Model Event Times: MTIME . . . . .   | 136 |
| Controlling Calls to PK and ERROR . . . . .  | 137 |
| Output-Type Compartments . . . . .   | 138 |
| Transgeneration of Input Data: the INFN Subroutine . . . . .                               | 139 |
| User-written PRED Subroutines . . . . .  | 139 |
| Required Data Items . . . . .  | 139 |
| An Example of \$PRED Statements: Pharmacodynamic Modeling . . . . .                        | 140 |
| Advanced Features of NONMEM . . . . .  | 140 |
| Full Covariance Matrices: \$OMEGA BLOCK and \$SIGMA BLOCK . . . . .                        | 140 |
| More About \$OMEGA and \$SIGMA . . . . .   | 141 |
| Grouping Related Observations: The L1 and L2 Data Items . . . . .                          | 142 |
| Continuing a NONMEM Run: MSFO and MSFI . . . . .   | 143 |
| NONMEM Can Obtain Initial Estimates for $\theta$ , $\Omega$ , $\Sigma$ . . . . .           | 144 |
| Improving Parameter Estimates: REPEAT and RESCALE . . . . .                                | 144 |
| The Covariance Step: $\mathbf{R}^{-1}$ , $\mathbf{S}^{-1}$ , Special Computation . . . . . | 144 |
| More About \$COVARIANCE . . . . .  | 145 |
| Multiple Problems in a Single NONMEM Run . . . . .   | 145 |
| Simulation Using NONMEM: The \$SIMULATION Record . . . . .                                 | 145 |
| More About \$SIMULATION . . . . .  | 146 |
| Files for Subsequent Processing: the \$TABLE Record . . . . .                              | 147 |
| More about \$TABLE and \$SCATTER . . . . .   | 147 |
| Data Checkout Mode . . . . .   | 148 |
| Obtaining Individual Parameter Estimates - Conditional Estimates of $\eta$ s . . . . .     | 148 |
| Population Conditional Estimation Methods . . . . .  | 149 |
| Displaying PRED-Defined Variables and Conditional Estimates of $\eta$ s . . . . .          | 149 |
| Mixture Models . . . . .   | 149 |
| PRED Error Return Codes and Error Messages in File PRDERR . . . . .                        | 150 |
| User-Written Subroutines . . . . .   | 150 |
| PRIOR . . . . .  | 151 |
| Observations of Two Different Types . . . . .  | 151 |
| Supplemental List of Features through NONMEM 7.5.2 . . . . .                               | 153 |
| NONMEM Features . . . . .  | 153 |
| Miscellaneous Features . . . . .   | 155 |
| Changes to NONMEM Outputs . . . . .  | 155 |
| PREDPP . . . . .   | 156 |
| NM-TRAN . . . . .  | 158 |
| General Features . . . . .   | 158 |
| Data Preprocessor . . . . .  | 158 |
| Abbreviated Code . . . . .   | 158 |
| Reserved Variables in Abbreviated Code . . . . .   | 159 |
| Utility Routines . . . . .   | 160 |
| All Options for \$ESTIMATION . . . . .   | 161 |
| All Options for \$COVARIANCE . . . . .   | 169 |
| Chapter 13 - Errors in NONMEM Runs . . . . .   | 172 |
| What This Chapter is About . . . . .   | 172 |
| Abnormal Termination of the Estimation Step . . . . .                                      | 172 |
| "DUE TO MAX. NO. OF FUNCTION EVALUATIONS EXCEEDED" . . . . .                               | 172 |
| "DUE TO ROUNDING ERRORS (ERROR=134)" . . . . .   | 173 |
| Abnormal Termination of the Covariance Step . . . . .                                      | 173 |

|   |     |
|---|-----|
| Miscellaneous Problems . . . . .              | 174 |
| Proportional Error Model . . . . .            | 174 |
| Errors in the Pharmacokinetic Model . . . . . | 174 |
| Errors with PREDPP . . . . .                  | 175 |
| Error Messages from a TRANS Routine . . . . . | 175 |
| Error Messages from ADVAN Routines . . . . .  | 175 |
| Numeric difficulties in PREDPP . . . . .      | 175 |
| Index . . . . .                               | 203 |

## Chapter 1 - Introduction to NONMEM, PREDPP, and NM-TRAN

### 1. What This Chapter is About

This chapter introduces a computer program called NONMEM. It also introduces two programs that are distributed with NONMEM and make it easier to use: PREDPP and NM-TRAN. The scope of this text itself is described, and suggestions are made for reading it. A somewhat detailed technical description of the components of NONMEM is then given. The final section is a list of additional references.

### 2. Introducing NONMEM

#### 2.1. What is NONMEM?

NONMEM stands for "Nonlinear Mixed Effects Model." NONMEM is a computer program, written in FORTRAN 90/95, designed to fit general statistical (nonlinear) regression-type models to data.

NONMEM was developed by the NONMEM Project Group at the University of California at San Francisco for analyzing population pharmacokinetic data in particular.<sup>†</sup> These are data typically collected from clinical studies of pharmaceutical agents, involving the administration of a drug to individuals and the subsequent observation of drug levels (most often in the blood plasma). Proper modeling of these data involves accounting for both unexplainable inter- and intra-subject effects (random effects), as well as measured concomitant effects (fixed effects). NONMEM allows this mixed effect modeling. Such modeling is especially useful when there are only a few pharmacokinetic measurements from each individual sampled in the population, or when the data collection design varies considerably between these individuals. However, NONMEM is a general program which can be used to fit models to a wide variety of data.

Like many nonlinear regression programs, NONMEM does not have any "built in" models (such as the linear model) with which it can compute a predicted value given the current values of the regression parameters. Instead, NONMEM calls a subroutine having entry name PRED ("prediction") to obtain a predicted value. PRED also must compute for NONMEM partial derivatives with respect to certain random variables. Depending on the model and the kinds of doses, PRED may be very simple or may be very complicated. A user can write his own PRED subroutine. This can be as simple or complicated as is necessary, and may involve calls to its own subprograms.

#### 2.2. What is PREDPP?

PREDPP stands for "PRED for Population Pharmacokinetics". It is a PRED subroutine for use with NONMEM and is the second major component distributed with NONMEM. Whereas NONMEM is a general nonlinear regression tool, PREDPP is specialized to the kinds of predictions which arise in pharmacokinetic data analysis. It can compute predictions according to many different pharmacokinetic models, according to a great variety of dosing regimens. Almost all the examples in this guide use PREDPP.

---

<sup>†</sup> NONMEM versions up through VI are the property of the Regents of the University of California, but ICON Development Solutions has exclusive rights to license their use. NONMEM 7 is the current version of the software and is the property of ICON Development Solutions.

### 2.3. What is NM-TRAN?

NM-TRAN stands for "NONMEM Translator". It is the third major component distributed with NONMEM. It is a separate, "stand-alone" control language translator and data preprocessor. When NM-TRAN is used, a NONMEM run includes two separate steps: first the NM-TRAN step, in which a file of NM-TRAN records (which begin with "\$") are translated into several NONMEM input files, and second the NONMEM step itself. All the examples in this guide use NM-TRAN. We strongly recommend its use.

Note that neither NM-TRAN nor NONMEM-PREDPP run interactively. Files of commands and data are created by means of (say) the operating system editor. Then NM-TRAN and NONMEM are executed, using these files as input. Figure 1.1 shows the relationship between NONMEM, PREDPP, and NM-TRAN.




Fig 1.1. NONMEM, PREDPP, and NM-TRAN. A user-written PRED subroutine could be included instead of PREDPP.

### 2.4. Scope of this Introductory Guide

This Guide is intended to be read by new users of NONMEM-PREDPP. Typically, such users have pharmacokinetic data, either from a population or from a single individual<sup>†</sup>, to be fit to a standard pharmacokinetic model (e.g., a one or two compartment linear mammillary model). However, new users with nonstandard models, or with pharmacokinetic/pharmacodynamic data, may also find this guide helpful.

It is assumed that NONMEM and its components are already installed on the user's computer and that the user wants to learn to use them as quickly as possible. This guide does not tell how to perform the installation or how to run an installed NONMEM under a particular operating system; the new user will have to ask experienced users what the local commands are. However, someone who is installing NONMEM at a new site may find it useful to review this guide to get a quick overview of NONMEM, its component programs, its inputs, and its outputs.

This guide is not a text book in pharmacokinetics or statistics. Readers should be familiar with basic concepts in pharmacokinetics and statistical data analysis. We also assume a

<sup>†</sup> The terms "population" and "single individual" are used in this guide. NM-TRAN and NONMEM outputs refer to POPULATION and SINGLE-SUBJECT data and analysis.

very basic familiarity with FORTRAN.

## 2.5. Contents of this Introductory Guide

**Chapter 2** contains two examples of the use of NONMEM. The first presents data from a single individual; estimates are obtained of his pharmacokinetic parameters. The second presents data from a group of individuals; estimates are obtained of the pharmacokinetic parameters of the population which this group represents. The examples serve to introduce NONMEM notation, input and output, and to provide an idea of what is possible using the system.

**Chapter 3** presents the notation and definitions we will use to discuss models for individual data. The relationship of these models to data is discussed, and the distinction between so-called fixed effects and random effects is made.

**Chapter 4** extends this discussion to models for population data.

**Chapter 5** discusses NONMEM's fitting criterion, the parameter estimates obtained by using this criterion, and the standard errors of these estimates. It then discusses how to do hypothesis tests with NONMEM.

**Chapter 6** tells how to create data files for NONMEM-PREDPP and how to describe them using the \$DATA and \$INPUT records of NM-TRAN. It also discusses the Data Preprocessor feature of NM-TRAN.

**Chapter 7** tells how to use NM-TRAN to write simple \$SUBROUTINE records for PREDPP, how to write \$PK records for individual data, and how to write \$PK records for population data.

**Chapter 8** tells how to write simple \$ERROR records for PREDPP. Chapters 7 and 8 are meant to be read in parallel with Chapters 3 and 4.

**Chapter 9** tells how to use NM-TRAN to specify the remaining choices for an analysis. It tells how to assign initial values to parameters (\$THETA, \$OMEGA, \$SIGMA records), how to specify what analysis tasks to perform (\$ESTIMATION, \$COVARIANCE records), and how to specify certain additional output (\$TABLE, \$SCATTERPLOT records).

**Chapter 10** describes NONMEM's output in detail.

**Chapter 11** outlines the process of model building, showing how a simple model can be made more complex to better fit the data.

**Chapter 12** briefly describes a variety of features of PREDPP and NONMEM that are somewhat advanced for this text but are of interest to most users of NONMEM. References are given to other documents in which additional information can be found.

**Chapter 13** discusses errors that can occur during a NONMEM run.

**Appendix 1** describes PREDPP's most commonly used pharmacokinetic models (ADVAN subroutines).

**Appendix 2** describes alternative parameterizations (TRANS subroutines) for these models.

**Appendix 3** is a list of NM-TRAN records.

## 2.6. How to Read this Guide

Readers who are completely new to NONMEM should read this guide starting with Chapter 2; the examples presented are used again in the later chapters. Chapters 2-5 are theoretical in nature. Chapters 6-12 describe the details of building the input for

NONMEM-PREDPP and interpreting the output. Readers who have non-pharmacokinetic data to fit can skip (or skim) Chapters 3, 4, 7, and 8. Readers who already have some familiarity with certain topics (e.g., who have used other nonlinear analysis programs to analyze data) can concentrate on the chapters of interest to them. We strongly recommend that all users "graduate" to the more thorough NONMEM documentation listed in Section 4 of this chapter.

Throughout the guide, examples are given of NM-TRAN records. These examples appear in boldface:

**\$THETA .01**

Examples are also given of (fragments) of input data files. They appear as follows:

| <b>ID</b> | <b>AMT</b>  | <b>TIME</b> | <b>DV</b>   |
|-----------|-------------|-------------|-------------|
| <b>2</b>  | <b>320.</b> | <b>0.</b>   | <b>0.</b>   |
| <b>2</b>  | <b>0.</b>   | <b>.27</b>  | <b>1.71</b> |

Alphabetic characters such as ID, AMT, etc., are shown for descriptive purposes. They are *not* part of the actual data file.

### 3. A Brief Technical Overview

In this section we discuss the components of NONMEM in some detail. First-time readers may prefer to skip this section and go directly to Chapter 2, which gives an example of a NONMEM run, and return to this section later (if at all).

#### 3.1. NONMEM

NONMEM is written (almost) entirely in ANSI FORTRAN 90/95. It is distributed on CD-ROM as FORTRAN source code, some of which is encrypted. It can be compiled and run on any computer which has a FORTRAN 90/95 compiler and sufficient memory and speed to run a large, computationally intensive program.

NONMEM consists of a main program and many subroutines, all of which are required for each NONMEM run. As discussed above, one subroutine, PRED, is not included in NONMEM itself.

#### 3.2. PREDPP and the PREDPP Library

PREDPP is not a single subroutine. It is a collection of FORTRAN subroutines. Some of these are always needed but must be supplied by the user himself (see PK and ERROR below). Others are always needed and are supplied; these are called the kernel routines. Others (subroutines ADVAN and TRANS, for example) are also always needed, and are supplied, but are chosen from different versions corresponding to different pharmacokinetic models. The collection of supplied routines constitutes the PREDPP Library.

#### 3.3. Subroutines PK and ERROR

Two very important subroutines of PREDPP are called PK and ERROR. PK computes the values of the population or individual pharmacokinetic parameters (e.g., CL and V) of a given model and accounts for the "differences" between individual and population values. ERROR accounts for the "differences" between predicted and observed values. These two subroutines are where the basic task of modelling is carried out; this task is the user's responsibility. Chapters 7 and 8 are devoted to a description of these subroutines.

Figure 1.2 shows the major components of PREDPP.

|                           |
|---------------------------|
| PREDPP kernal subroutines |
| ADVAN and TRANS           |
| PK                        |
| ERROR                     |

Figure 1.2. Components of PREDPP. ADVAN and TRANS are chosen from the PREDPP library. PK and ERROR are user-supplied.

### 3.4. Building an Executable Module for NONMEM

Whether PREDPP is used or a special purpose PRED subroutine is written, the PRED subroutine must be combined ("linked") with NONMEM; this process (which is sometimes called "link editing" or "loading") must take place before the actual NONMEM run. The NONMEM-PRED combination is generally called a "load module" or "executable module". Compiling and linking are processes which are operating system dependent; each installation must supply its own commands and procedures for these tasks. They may be done before the NM-TRAN step or between it and the NONMEM step. This choice is discussed in Section 3.7 below. For certain platforms, a front-end interface provided by the NONMEM Project Group (nmfe75.bat for MS/DOS; nmfe75 C-shell script for Unix-type) can be used to perform these steps, and can create all both types of load modules described below: generated subroutines and user-written subroutines.

### 3.5. NM-TRAN

NM-TRAN provides the following services: control language translation, model specification via FORTRAN-like statements (called abbreviated code), partial differentiation, and preprocessing of the data. They are discussed separately.

### 3.6. Control Language Translation

NM-TRAN includes a language for communicating control information to NONMEM. NM-TRAN records are free-form (i.e., spacing between options within a record and the order of the records and their options is flexible) and use English words (or their abbreviations) for options. For example, the record name \$ESTIMATION may be abbreviated to \$EST; the option name SIGDIGITS may be abbreviated to SIG. Either spaces or commas may be used to separate options. Defaults are understood for most options, allowing the records to be relatively compact. Considerable error checking is performed by NM-TRAN. This reduces the number and severity of the errors that can occur during the NONMEM run. NM-TRAN also produces messages that warn the user of possible errors in the data and/or control stream.

NM-TRAN translates a file of NM-TRAN control records into NONMEM control records, which use a fixed-field, predominately numerical control language.

### 3.7. Model Specification via Abbreviated Code

With PREDPP, FORTRAN subroutines PK and ERROR are needed to specify parts of the pharmacostatistical model. In most cases, these specifications can be directly expressed within NM-TRAN records \$PK and \$ERROR, using FORTRAN-like assignment and

conditional statements called abbreviated code. These statements are implemented by NM-TRAN as complete FORTRAN subroutines in file FSUBS, incorporating the abbreviated code. An intermediate step between the NM-TRAN and NONMEM steps is needed to compile these subroutines and link them with NONMEM-PREDPP.

The message "Recompiling certain components" will be displayed at the console at this step.

Figure 1.3 shows how the compile and link step relates to the two steps of Figure 1.1.




Figure 1.3. Building a NONMEM load module with generated FORTRAN subroutines. An intermediate step is placed between the two steps of Figure 1.1.

If the user supplies complete PK and ERROR subroutines (i.e., \$PK and \$ERROR records are not used), then the NONMEM load module can be built at any time.

Note that even when PREDPP is not used, the same options exist. For example, if the desired model can be expressed via a \$PRED record, then NM-TRAN will generate a complete PRED subroutine. However, whereas NM-TRAN's FORTRAN-like syntax is sufficient for most purposes of writing PK and ERROR subroutines, it is not sufficient for writing any but the simplest of PRED subroutines.

### 3.8. Partial Differentiation

NONMEM requires that PRED (whether PREDPP or user-written) compute more than just predicted values. It must also compute certain partial derivatives with respect to the random variables  $\eta$  and  $\varepsilon$  described in Chapters 3 and 4. When \$PK, \$ERROR, or \$PRED records are used, NM-TRAN performs symbolic differentiation to generate the code needed to compute these derivatives. This relieves the user of a major burden.

### 3.9. Data Preprocessor

NM-TRAN includes a Data Preprocessor program which allows the user greater flexibility in constructing his data file than is allowed in a data file input directly into NONMEM. This is discussed in Chapter 6.

## 4. Additional Documentation

More information can be found in the other parts of the NONMEM Users Guide, all of which may be found as pdf files on the NONMEM distribution medium.

**Part I - Users Basic Guide**

A thorough, step by step discussion of the various features and some of the statistical concepts involved in using NONMEM, including many examples.

**Part II - Users Supplemental Guide**

A continuation of Part I which includes advanced features of NONMEM.

**Part III - NONMEM Installation Guide**

A guide for installing NONMEM, PREDPP, and NM-TRAN.

**Part IV - NM-TRAN Guide**

A complete reference guide to NM-TRAN and the Data Preprocessor.

**Part V - Introductory Guide**

The present document.

**Part VI - PREDPP Guide**

A complete reference guide to PREDPP.

**Part VII - Conditional Estimation Methods**

A description of these methods and some guidelines for their use.

**Part VIII - Help Guide**

A fast way to locate information on a given word or topic. The content of the Help Guide is also supplied on the NONMEM distribution medium as both text files ("on-line help") and html files for on-line searching.

**NONMEM V Supplemental Guide**

supp.pdf, Describes new features of NONMEM V.

**Introduction to Version VI**

intro.pdf, Describes new features of NONMEM VI.

**Introduction to NONMEM 7.5**

intro7.pdf, Describes new features of NONMEM 7.1, 7.2, 7.3, 7.4, and 7.5

**NONMEM7\_Technical\_Guide**

Technical Guide on the Expectation-Maximization Population Analysis Methods in the NONMEM 7 Program. New with NONMEM 7.2; revised for NONMEM 7.3, NONMEM 7.4, and NONMEM 7.5

**useful\_variables**

New with NONMEM 7.3; revised for NONMEM 7.4, NONMEM 7.5 A description of variables that are available via the NM-TRAN include file util\nonmem\_general\_reserved.

**User Documentation for cvodes v5.1.0 (sundials v5.1.0)**

cv\_s\_guide.pdf, describes additional features of ADVAN14.

**User Documentation for idas v5.1.0 (sundials v5.1.0)**

idas\_guide.pdf, describes additional features of ADVAN15.

**Users Guide for the code RADAR5 - Version 2.1**

man\_radar5-v2.1.pdf, describes additional features for ADVAN16, ADVAN17.

**A Friendly Fortran DDE Solver**

ddes\_f90.pdf, describes additional features of ADVAN18.

## Chapter 2 - NONMEM Examples

### 1. What This Chapter is About

In this chapter, two examples of the use of NONMEM will be given. The first estimates pharmacokinetic parameters of an individual from his data; the second estimates so-called population parameters from data from a group of individuals. The examples serve to introduce NONMEM notation, input and output, and to provide an idea of what is possible using the system. The second example will be discussed again in Chapter 11.

### 2. An Individual's Theophylline Kinetics

Figure 2.1 shows the input used to fit a model to observations of theophylline plasma concentration vs time in a single individual after a single dose of 320 mg.

```
$PROB  SIMPLE NONLINEAR REGRESSION - THEOPHYLLINE
$INPUT  ID AMT TIME DV
$DATA  P2DATA
$SUBROUTINE ADVAN2
$PK
  KA=THETA (1)
  K=THETA (2)
  V=THETA (3)
  S2=V
$ERROR
  Y=F+ERR (1)
$THETA (0, 1.7) (0, .102) (0, 29.)
$OMEGA 1.2
$ESTIMATION PRINT=5
$COVARIANCE
$TABLE ID AMT TIME
$SCATTER PRED VS DV UNIT
```

Figure 2.1. The input (i.e., NM-TRAN control records) for analysis of some individual theophylline data.

The first line (record) gives a name to the problem. The rest of the lines (records) discuss the data, the model, and the desired output. Before going into these in some greater detail, you may want to look right now at figures 2.1 and 2.2, and then 2.4 and 2.5. Figure 2.2 shows the data for this problem, and figures 2.4 and 2.5 show some of NONMEM's output. All you need to know to get a good idea of what this analysis shows is that the one-compartment model with first-order absorption has been used; the observed concentrations and the times of observation after the bolus dose are in columns 4 and 3, respectively, of figure 2.2; and that the symbol DV stands for dependent variable (the observed concentrations, in this case). You should, for example, even at this point, be able to tell that the estimate of Volume of Distribution (V in figure 2.1, and THETA(3) in figure 2.4) is 32 liters (L), with a standard error of  $\pm 1.26$  L. Now consider the figures in greater detail.

#### 2.1. The NM-TRAN Control Records

The second record of figure 2.1 names the data items that appear on each data record, and the third record gives the name of the file containing the data records, P2DATA in this example. Figure 2.2 shows the contents of P2DATA.

|   |      |      |      |
|---|------|------|------|
| 2 | 320. | 0.   | 0.   |
| 2 | 0.   | .27  | 1.71 |
| 2 | 0.   | .52  | 7.91 |
| 2 | 0.   | 1.   | 8.31 |
| 2 | 0.   | 1.92 | 8.33 |
| 2 | 0.   | 3.5  | 6.85 |
| 2 | 0.   | 5.02 | 6.08 |
| 2 | 0.   | 7.03 | 5.4  |
| 2 | 0.   | 9.   | 4.55 |
| 2 | 0.   | 12.  | 3.01 |
| 2 | 0.   | 24.3 | .90  |

Figure 2.2. The contents of the data file containing the data records.

According to the second record of figure 2.1, the third data item (column) of a data record is TIME, the time associated with the event described by that data record. The event at a given time (for this simple data set) can either be the administration of a dose or the acquisition of an observation. The second data item of a data record is AMT, amount (in this case in mg) of the dose given at TIME, the time of the record. Apparently, 320 mg is given at time zero (first record of figure 2.2), and no further doses are given (all zeros in column 2 thereafter). The fourth data item (column) in P2DATA is named DV, for Dependent Variable (the measured plasma theophylline concentration), as already mentioned. So, all of the data records, except the first, give the time after the 320 mg dose, and the concentration of theophylline (in mg/L) measured in a plasma sample drawn at that time. The first data item is labelled ID for the IDentification number of the patient. Here it happens to be 2.

## 2.2. The Model

The fourth record of figure 2.1 identifies the pharmacokinetic model PREDPP is to use: the one-compartment model with first-order absorption. It is implemented by an ADVAN subroutine (see Chapter 1, Section 3.2) which is called ADVAN2 (See Chapter 7). Figure 2.3 shows the part of the output of NONMEM for this problem that verifies the user's choice of model. It also describes the features of the model in terms of its compartments. Of relevance to this problem are the DEPOT compartment (where the dose goes, and from which drug enters the central compartment by a first order process), and the CENTRAL compartment itself. Note, for example, that the default compartment for doses (i.e., where PREDPP will add doses if not otherwise instructed) is the DEPOT compartment, as it should be.

```

ONE COMPARTMENT MODEL WITH FIRST-ORDER ABSORPTION (ADVAN2)

MAXIMUM NO. OF BASIC PK PARAMETERS:    3

BASIC PK PARAMETERS (AFTER TRANSLATION) :
  ELIMINATION RATE (K) IS BASIC PK PARAMETER NO.:  1
  ABSORPTION RATE (KA) IS BASIC PK PARAMETER NO.:  3

COMPARTMENT ATTRIBUTES
COMPT. NO.  FUNCTION  INITIAL  ON/OFF  DOSE  DEFAULT  DEFAULT
              STATUS  ALLOWED  ALLOWED  FOR DOSE  FOR OBS.
  1          DEPOT    OFF      YES     YES     YES      NO
  2          CENTRAL  ON       NO      YES     NO       YES
  3          OUTPUT  OFF      YES     NO      NO       NO

```

Figure 2.3. The PREDPP output that verifies the user's choice of model. Features of the model are discussed, such as the names and numbering of parameters, and the attributes of the various compartments in the model.

The fifth input record (figure 2.1) signals the start of the user's specification of the model for the pharmacokinetic parameters. This specification is given in the next 4 lines of so-called abbreviated code (the \$PK record, along with this abbreviated code is called the \$PK block). Some of the parameters that NONMEM estimates are denoted by  $\theta$  herein, and are labeled THETA in NONMEM input and output. The model specified in figure 2.1 is very simple. It says that a different unknown constant (NONMEM parameter) is to be assigned to each pharmacokinetic parameter: first-order absorption rate, KA (line 1 of the PK block, after the \$PK record - THETA(1)), rate constant of elimination, K (line 2 - THETA(2)), and volume of distribution, V (line 3 - THETA(3)). The S2 parameter (a so-called scale parameter) is discussed in Chapter 3, Section 2.2.

The sixth input record (figure 2.1 - 11<sup>th</sup> line) signals the start of the user's specification of the (statistical) model for the lack of fit of the pharmacokinetic model to the data. This specification is given in the next line of abbreviated code (the \$ERROR record, along with this line of abbreviated code is called the \$ERROR block). The model here says that observations differ from predictions by an additive error (ERR(1)).

Record 7 (\$THETA) gives NONMEM information about possible values of each element of  $\theta$  in the format: lower bound, initial estimate, upper bound. When, as in this particular record, only two numbers are given for an element of  $\theta$ , these are understood to mean the lower bound and initial estimate; the upper bound is unlimited. Record 8 (\$OMEGA) gives NONMEM an initial estimate of the variance of ERR(1). This statistical parameter is often denoted by  $\sigma^2$  in statistical discussions, but with data from a single individual, it is denoted by  $\Omega$  in NONMEM documentation, and by OMEGA in NONMEM input and output. It is understood that a variance parameter is always nonnegative. The \$OMEGA record is further discussed in Chapter 9, Section 3.

### 2.3. The Output

Record 9 (\$ESTIMATION) instructs NONMEM to obtain estimates of the parameters, and the next record (\$COVARIANCE) asks that it also obtain standard errors of the parameter estimates. The output is shown in figure 2.4. It requires little discussion. The first item, the description of the objective function, is marked with a #OBJT: tag. Tags are present in the NONMEM report file in certain key locations, to allow a third party program or the end user to consistently find the appropriate positions in the file without having to search for specific words in the text. The Introduction to NONMEM7 manual describes the various tags. The second item, the minimum value of the objective function,






Figure 2.5. A scatterplot of the observed data (DV) vs the predictions of the best-fitting model parameters (PRED). The line of identity (intercept = 0; slope = 1) is drawn. If all points fell on that line, the fit would be perfect.

### 3. A Population Model for Phenobarbital

About 60 infants were given phenobarbital therapeutically. A plasma concentration was measured in each some hours after the first (loading) dose, followed by multiple maintenance doses. A second, and sometimes a third concentration were measured later. In all, 155 concentrations were observed. Figure 2.6 gives the NM-TRAN control records. The data are too lengthy to show in full, but figure 2.7 shows the data for the first individual<sup>†</sup>. Figures 2.8 - 2.10 have some relevant output. Again, most of the analysis results are apparent from the figures, and you should try to see if you can figure them out before going further. Note that the \$INPUT record now defines a new data item, WT, the patient weight. It's value is given on every data record for an individual, in the column indicated. This is so despite the fact that WT may not change within an individual. This is a bit repetitious, but convenient.

<sup>†</sup> File PHENO of NONMEM distribution medium contains the complete data set.

```

$PROBLEM PHENOBARB
$INPUT  ID TIME AMT WT APGR DV
$DATA   PHENO
$SUBROUTINE ADVAN1
$PK
    TVCL=THETA(1)
    CL=TVCL+ETA(1)
    TVVD=THETA(2)
    V=TVVD+ETA(2)
                                ; THE FOLLOWING ARE REQUIRED BY PREDPP
    K=CL/V
    S1=V
$ERROR
    Y=F+ERR(1)
$THETA  (0, .0047) (0, .99)
$OMEGA  .0000055, .04
$SIGMA  25
$ESTIMATION PRINT=5
$TABLE  ID TIME AMT WT APGR
$COVARIANCE
$SCATTER PRED VS DV UNIT
$SCATTER RES VS WT

```

Figure 2.6. NM-TRAN control records for analysis of some population phenobarbital data.

|   |       |      |     |   |      |
|---|-------|------|-----|---|------|
| 1 | 0.    | 25.0 | 1.4 | 7 | .    |
| 1 | 2.0   | .    | 1.4 | 7 | 17.3 |
| 1 | 12.5  | 3.5  | 1.4 | 7 | .    |
| 1 | 24.5  | 3.5  | 1.4 | 7 | .    |
| 1 | 37.0  | 3.5  | 1.4 | 7 | .    |
| 1 | 48.0  | 3.5  | 1.4 | 7 | .    |
| 1 | 60.5  | 3.5  | 1.4 | 7 | .    |
| 1 | 72.5  | 3.5  | 1.4 | 7 | .    |
| 1 | 85.3  | 3.5  | 1.4 | 7 | .    |
| 1 | 96.5  | 3.5  | 1.4 | 7 | .    |
| 1 | 108.5 | 3.5  | 1.4 | 7 | .    |
| 1 | 112.5 | .    | 1.4 | 7 | 31.0 |

Figure 2.7. The first individual's phenobarbital data.

### 3.1. The NM-TRAN Control Records

The records are very similar to those for the theophylline problem. The new features are that the model has changed (it is implemented by ADVAN1, not ADVAN2), the model for the pharmacokinetic parameters is more complicated, and an additional scatterplot is requested. The data for each infant is similar to those shown in figure 2.7; however, now all of the data records for each infant start with the *same* value for the ID data item (column 1), but this value differs *between* infants.

### 3.2. The Model

ADVAN1 implements the one-compartment (monoexponential) model, without first order absorption. No absorption model was needed for this problem because all concentrations were measured many hours after the last (oral) dose, so absorption could be considered to be complete, and, for the purposes of data analysis, immediate.

The parameters of the one-compartment model are defined by the abbreviated code following the \$PK statement: Clearance (CL) and Volume of Distribution (V). However, here each parameter is not simply equal to one of NONMEM's parameters (an element of THETA). Rather, CL, for example, is equal to a parameter (THETA(1)) plus a new term,








Figure 2.10. A scatterplot of the observed data (DV) vs the predictions with the best fitting model parameters (PRED). The line of identity (intercept = 0; slope = 1) is drawn. If all points fell on that line, the fit would be perfect. Here, in contrast to figure 2.5, the data arise from many different individuals. One cannot tell which data came from which infant.

Although the fit is fairly good, the points far to the right of the line of identity of figure 2.10 indicate that there are many predictions (PRED) that are much higher than their corresponding observations (DV). This is seen from another point of view in the second scatterplot. This scatterplot plots residuals (RES) vs patient weight (from the data item, WT — see figure 2.6). A residual is the difference between an observed concentration and its prediction (the same prediction used in the scatterplot of figure 2.10). The residuals reflect not only lack of fit between observations and predictions for a given individual (the variance SIGMA), but also interindividual variability (the variances comprising OMEGA). They can be thought of as reflecting the part of the data that the model does not explain. As can be seen from figure 2.11, there is a clear relationship between the sign and magnitude of the residuals and patient weight. Here, the patients with the largest weights have the most negative residuals; i.e., their predictions are much larger than their observations. These are the same points that fell on the far right of figure 2.10.




Figure 2.11. A scatterplot of the residuals (RES) vs patient weight (WT). The pattern suggests that observations are underpredicted in infants with low weight, and overpredicted in those with higher weights.

An obvious explanation is that Clearance or Volume, or both, increase with weight, so that without weight being taken into account, too high a prediction is being made for a larger infant and too low a prediction is being made for a smaller infant, all other things (i.e., dose) being equal. To see if accounting for weight improves the fit, the run specified in figure 2.12 can be done.

```

$PROBLEM PHENOBARB WITH WEIGHT IN MODELS FOR CL AND V
$INPUT  ID TIME AMT WT APGR DV
$DATA  INDATA
$SUBROUTINE ADVAN1
$PK
  TVCL=THETA (1) +THETA (3) *WT
  CL=TVCL+ETA (1)
  TVVD=THETA (2) +THETA (4) *WT
  V=TVVD+ETA (2)
                                     ; THE FOLLOWING ARE REQUIRED BY PREDPP
  K=CL/V
  S1=V
$ERROR
  Y=F+ERR (1)
$THETA  (0, .0027) (0, .70) .0018 .5
$OMEGA  .000007, .3
$SIGMA  8
$ESTIMATION PRINT=10
$COVARIANCE UNCONDITIONAL
$TABLE ID TIME AMT WT APGR DV
$SCATTER  PRED VS DV  UNIT
$SCATTER  RES  VS WT

```

Figure 2.12. NM-TRAN control records for fitting a model taking into account the effect of patient weight to the population phenobarbital data.

Now both TVCL and TVVD are linear functions of weight with, in the case of TVCL, for example, intercept THETA(1), and slope THETA(3). Both slope and intercept are "population" parameters since they relate weight to typical population values of the pharmacokinetic parameter. Now we see why WT is given in every data record: the abbreviated PK code may need to be evaluated at each event time. If WT did not change over time within any patient, it could be given only on the first data record for each patient, but then slightly more complicated abbreviated code would be needed. The output from running the input of figure 2.12 is shown in figures 2.13 - 2.16.



model including them.




Figure 2.15. A scatterplot of predictions vs observations for the phenobarbital data, using the model of figure 2.12, which takes into account the effect of patient weight. Compare to figure 2.10.

The scatterplots (figures 2.15 and 2.16) confirm that the new model is an improvement: the group of points far to the right of the line of identity have disappeared from the PRED vs DV plot, and the plot of residuals vs weight no longer shows a pattern.




Figure 2.16. A scatterplot of residuals (RES) vs patient weight (WT) for the phenobarbital data, using the model of figure 2.12, which takes into account the effect of patient weight. Compare to figure 2.11.

#### 4. Overview

The examples in this chapter illustrate some of the most important and useful features of NONMEM.

- NONMEM can fit both individual and population models.
- NONMEM has a menu of pharmacokinetic models from which the one appropriate to the problem at hand can be chosen.
- The user specifies the relationship of pharmacokinetic parameters to independent variables (such as WT in the phenobarbital example), using "population" parameters that will be estimated.
- The user also specifies which parameters vary between individuals, and the form (model) for this variability, as well as the form (model) for the differences between observations from an individual and their predictions for this individual.
- NONMEM estimates parameters describing both kinds of variability.
- NONMEM provides estimates (standard errors) of the precision of its parameter estimates, including those describing variability.
- NONMEM provides a means of deciding whether one model (e.g., that including weight's effect on CL and V) fits the data better than another using the minimum

- objective function value, a goodness-of-fit statistic.
- NONMEM provides (limited) graphics, useful in judging the adequacy of the model currently fit to the data.

## Chapter 3 - Models for Individual Data

### 1. What This Chapter is About

In this chapter, the notation and definitions we will use to discuss models for individual data will be presented. The relationship of these models to data will be discussed, and a distinction between pharmacokinetic structural models (that describe the underlying shape and form of the data) and statistical error models (that describe the "errors" or differences between observations and structural model predictions) will be made. Several error models will be discussed, as will a useful modelling device, the indicator variable.

### 2. Pharmacokinetic Structural Models for Individual Data

By individual data we usually mean data from a single individual (animal or human). One could also be concerned with data comprised of a pharmacokinetic response at just one time point from each of a number of individuals. Call this type of data single-response population data. This name comes from the fact that data such as these can, of course, be regarded as a particular instance of the more general data type, population data; i.e., data comprised of one *or more* pharmacokinetic responses at different time points from a number of individuals sampled from a population. Although one can discuss the treatment of single-response population data as population data, they are often treated just as are individual data.

A simple pharmacokinetic model for data from a single individual is the monoexponential ("one-compartment") model:

$$A_j = De^{-kt_j} \quad (3.1)$$

This model describes the typical time course of amount of drug in the body ( $A$ ), as a function of initial dose ( $D$ ), time ( $t$ ), and a *parameter*,  $k$ . As we may be interested in  $A$  at several possible times, we explicitly note this by the subscript  $j$  which indexes a list of times,  $t_0, t_1, \dots, t_j, \dots, t_n$ .

A way to write a generic form for a structural model, omitting details of its structure, is

$$y_j = f(x_j, \phi) \quad (3.2)$$

where  $y$  stands for some "response" (dependent variable) of interest ( $A$  in (3.1)), the symbol  $f$  stands for the unspecified form of the model (a monoexponential such as in (3.1)), which is a function of known quantities,  $x$  ( $t_j$  and  $D$  in (3.1)), and *parameters*,  $\phi$  ( $k$  in (3.1)). The quantities in  $x$  are *known*, because they are either measured or controlled, and therefore, are called fixed effects, in contrast to effects which are not known and are regarded as random (see below). The parameters in the parameter vector  $\phi$  are called fixed effect parameters because they quantify the influence of the fixed effects on the dependent variable. Each one of an individual's pharmacokinetic parameters is a particular type of fixed effect parameter. With NONMEM, parameters comprising  $\theta$  are (usually) fixed effect parameters, but these may or may not be an individual's pharmacokinetic parameters (contrast figures 2.1 and 2.6). Here we shall use the symbol  $\phi$  for the parameter vector comprised specifically of an individual's pharmacokinetic parameters (although there will be some exception to this).

Aside from the fact that the values given by a structural model are usually not the values observed due to measurement error or model misspecification, an amount of drug ( $A$  of (3.1)) is usually not itself observable. Instead, we may observe a concentration ( $C$ ) of drug. We need an "observation scaling" model to describe the relationship between  $A$

and  $C$ . This might be

$$\tilde{C}_j = \frac{A_j}{V} \quad (3.3)$$

where  $V$  is another parameter, Volume of Distribution. (We denote the concentration in model (3.3) by the symbol  $\tilde{C}$ , to distinguish it, the model-predicted value, from the actually observed value,  $C$ . This will soon be discussed further.) PREDPP assumes that there is always an observation scaling model like (3.3) that relates an amount of drug (in some compartment of the body) to the observation, and therefore always expects a parameter,  $S_n$  that scales (i.e. divides) the predicted amount in the  $n^{\text{th}}$  compartment. In the example above,  $S_1$  is simply  $V$ . In other examples, to be discussed later,  $S_n$  can be more complicated. If a value for  $S_n$  is not specified, it is taken to be 1. For the rest of this discussion, it is convenient to assume that  $\phi$  itself includes a scaling parameter (if such is needed, and even though such a parameter is not usually regarded as one of an individual's pharmacokinetic parameters) and that  $f$  actually includes observational scaling. Note, considering the example of (3.3), that  $x \equiv (D, t)$ , and  $\phi \equiv (k, V)$ . Thus  $x$  and  $\phi$  of (3.1) are in general lists of things (vectors), not single things (scalars).

PREDPP implements a number of pharmacokinetic models, such as the one-compartment model (3.1), (3.3). These will be discussed more fully in Chapter 7. There is no need for further general discussion of kinetic models, as we assume the readers of this document are familiar with pharmacokinetics. However, two modelling features deserve further comment, alternative parameterizations and the special parameter,  $S_n$ .

### 2.1. Alternative Parameterizations

Recall the phenobarbital example of Chapter 2. For the first run, the input contained, among other things, some lines of code defining the variables  $CL$  and  $V$ , and then the line

```
K = CL/V
```

This line was needed because PREDPP expects the one-compartment model to be parameterized using the parameter  $K$ , the rate constant of elimination, not clearance and volume of distribution. However, we chose to estimate typical population values for  $CL$  and  $V$ , so we had to relate these parameters to THETA and then relate  $K$  to  $CL$  and  $V$ . This is an example of reparameterization of a model so that the pharmacokinetic parameters used are those of primary interest to the modeler. In fact, we may use any parameterization we wish, so long as we are willing to include the reparameterization line(s) that translate our parameters into those expected by PREDPP. (Chapter 7 discusses the parameters PREDPP expects for the various models it implements.) However, there is a program called TRANS which automatically does this translation. Different versions of TRANS exist in the PREDPP Library and correspond to translations of different parameterizations into that expected by PREDPP.

### 2.2. The Scale Parameter, $S$

Usually, observations are concentrations. So, as in model (3.3),  $S$  will usually be set identical to  $V$ . However,  $S$  is not always simply  $V$ . Some examples should clarify this point. (In the discussion below, we avoid the notation  $S_n$ , and use  $S$ , to refer to the scale term for the amount in the compartment in which concentrations are being measured.)

#### 2.2.1. $S$ Depends on a Known Constant

This almost trivial case occurs when one wishes to match the units of predicted responses to those of the data. For example, suppose  $D$  is in milligrams, but concentrations are in

ng/ml. If no scaling is done, the units of  $V$  will be kiloliters (i.e.,  $V=1$  corresponds to  $V=1000$  liters). To avoid this, one might choose the model

$$S = V/1000$$

thereby converting the units of  $A$  into micrograms, and since  $\text{mcg/L} \equiv \text{ng/ml}$ , the units of  $V$  become liters. Of course, one could recode one's data, dividing all concentrations by 1000 (or multiplying the dose by 1000) and avoid this, but that may not be convenient.

### 2.2.2. $S$ Depends on a Parameter

Later in this chapter we will discuss a model used when the data arise from two different assays (call them assay 1 and assay 2). In such a case, there may be a systematic (multiplicative) bias of one assay relative to the other. If we wish to allow for this possibility, we might need a model such as

$$S = \begin{cases} V, & \text{if assay is 1} \\ hV, & \text{if assay is 2} \end{cases}$$

where  $h$  is a new parameter that measures the proportional bias of the assays (i.e., bias causes the apparent volume of distribution to be different for data from the two assays). The parameter  $h$  is not really a pharmacokinetic parameter, but for the purpose of this discussion it can be included in  $\phi$ .

### 2.2.3. $S$ Depends on an Element of $x$

Later in this chapter we will describe a model useful when two kinds of responses are measured, plasma and urine concentrations. In the case of urine concentrations, the predicted total drug in the urine during a time period (available from an "output" compartment present in all models implemented by PREDPP; see Chapter 7) would have to be scaled by the actual urine volume during that time period. This volume would be an element of  $x$ , and  $S$  would be set equal to it.

## 3. Statistical Model for an Individual's Observations

One does not, in fact, ever observe the predicted plasma concentration (or any other predicted response). What one observes is a measured value which differs from the predicted value by some (usually small) amount called a residual error (also called intra-individual error). We regard this error as a random quantity (see below). We will want NONMEM to fit our model to our data, and in so doing, provide us with estimates of the model parameters. The way NONMEM's fit follows the data is determined largely by what we tell it about the nature of the errors (see Chapter 5). We must therefore provide NONMEM with another model, an error model.

There are many reasons that the actual observation may not correspond to the predicted value (e.g.  $\tilde{C}$  as given by the right side of (3.3)) The structural model may only be approximate, or the quantities in  $x$  may have been measured with error, or, as is always true, pharmacokinetic responses may be measured with some error (assay error). It is too difficult to model all these sources of error separately, so we usually make the simplifying assumption that each difference between an observation and its *prediction* (i.e. each error) is a randomly occurring number. When the data are from a single individual, and the error model is the Additive error model (see Section 3.1, below), the error is denoted by  $\eta$  herein, by ETA in NONMEM output, and by ETA or ERR in NM-TRAN input. (When data are from a population, and the same error model is used, this error will be denoted  $\varepsilon$ ; see Chapter 4.) Therefore a model for the  $j$ th observation,  $y_j$ , could be written

$$y_j = f(x_j, \phi) + \eta_j \quad (3.4)$$

Implicit in using the symbol  $\eta$  in this way is the assumption that all residual errors come from probability distributions with mean zero and the same (usually unknown) variance. (The error variance is the mean *squared* error.) More complicated error models involving  $\eta$  can be written (see below). A schematic of model (3.4) is shown for the structural model of (3.1), (3.3) in figure 3.1. Because this model describes the influence of both fixed effects ( $x_j$ ) and random effects ( $\eta_j$ ), it is called a Mixed Effects Model (hence the name, NONMEM: *NON*linear *M*ixed *E*ffects *M*odel). Mixed effects models, in general, may have more than one random effect, and more than one type of random effect (Chapter 4); (3.4) is only a particularly simple example.




Figure 3.1.  $C$  vs  $t$  for a monoexponential model. The solid line is  $f(x, \phi)$ ; the circles are the observed data points. An error is indicated.

Even though errors are unpredictable random quantities, some information about them is usually assumed, and some can be estimated. First, it is assumed that the mean error is zero. This simply means that were the true values for the parameters in  $\phi$  known, the model would have no systematic overall bias (e.g., be systematically below or above the data points, on average).

A second aspect of the error, one that can be estimated by NONMEM, is its typical size. Since errors may be positive or negative, their typical size is not given by their mean (which is zero), but by their standard deviation, the square root of their variance. One can always simply convert the variance into the standard deviation, and conversely. NONMEM output gives estimates of the error variance. With individual data this variance is denoted in this text by  $\omega^2$ , and by OMEGA in NONMEM input and output. The standard deviation (SD) of the error is denoted  $\omega$  herein. The reason that OMEGA, rather than, for example, OMEGA SQ stands for  $\omega^2$  in NONMEM input and output will be discussed in Section 3.8. (We will see, in Chapter 4, that when the error is symbolized by  $\varepsilon$ , not  $\eta$ , its variance will be denoted  $\sigma^2$  in this text, and SIGMA, not OMEGA, in NONMEM input and output.) Here, the parameter  $\omega^2$  quantifies the influence of the random effect,  $\eta$  on the observations,  $y$ . It is therefore called a random effects parameter.

### 3.1. The Additive Error Model

The symbol  $\eta$  is always used to denote a random quantity whose probability distribution has mean zero and variance  $\omega^2$ . Model (3.4) says that the errors themselves can be so regarded, and since an observation equals its prediction (under the structural model) plus an error, model (3.4) is called the Additive error model. This model is illustrated in figure 3.2.




Figure 3.2.  $C$  vs  $t$  for a monoexponential model. The middle line is  $f(x, \phi)$ ; the outer lines give the approximate "envelope" for additive errors. Don't be fooled by the apparent widening of the gap between the upper and lower curves as time increases: the vertical distance from the middle line to either outer line is everywhere the same.

### 3.2. The Constant Coefficient of Variation and Exponential Models

NONMEM allows an error model which can be more complicated than that of (3.4). One such more complicated, but useful model is the Constant Coefficient of Variation (CCV), or Proportional error model,

$$y_j = f(x_j, \phi) + f(x_j, \phi)\eta_j = f(x_j, \phi)(1 + \eta_j) \quad (3.5)$$

A fractional error is an error expressed as a fraction of the corresponding prediction. The CCV model says that a fractional error can be written as an  $\eta$ , i.e. as a random quantity with mean zero and variance  $\omega^2$ . Under this model, the variance of an error itself is proportional to the squared prediction, with  $\omega^2$  being the proportionality factor, and so is not constant over observations. Since, under this model, the standard deviation of the error, and also of  $y$ , is  $\omega f(x, \phi)$ , and since the mean of  $y$  is  $f(x, \phi)$  (when  $\phi$  assumes its true value), the coefficient of variation of  $y$  is just the constant  $\omega$  (the coefficient of variation of a random quantity is defined as its standard deviation divided by its mean). This is the

reason the CCV error model is so named. Also for this reason,  $\omega^2$  is dimensionless, in contrast to having units equal to those of the squared observation as with the Additive model. This error model is illustrated in figure 3.3.




Figure 3.3.  $C$  vs  $t$  for a monoexponential model. The middle line is  $f(x, \phi)$ ; the outer lines give the approximate "envelope" for constant coefficient of variation errors.

The exponential error model is

$$y_j = f(x_j, \phi) \exp(\eta_j) \quad (3.5a)$$

This model is sometimes referred to as the log-normal model, because it is additive if logs are taken (and because  $\eta_j$  is assumed to be normally distributed):

$$\log y_j = \log f(x_j, \phi) + \eta_j \quad (3.5b)$$

See Chapter 8, Section 3.2 for a discussion of this model.

### 3.3. Combined Additive and CCV Error Model

When most observations obey the CCV model but some observations may be near the lower limit of detection of an assay, a model which may be useful is one which is a combination of both the Additive and CCV error models:

$$y_j = f(x_j, \phi) + f(x_j, \phi)\eta_{1j} + \eta_{2j}. \quad (3.6)$$

Here there are two types of  $\eta$ 's,  $\eta_1$  and  $\eta_2$ . The first has variance  $\omega_1^2$ ; the second has a possibly different variance,  $\omega_2^2$ . NONMEM permits several types of  $\eta$ 's. Under this model, the variance of the error portion of the model is  $\omega_1^2 f(x_j, \phi)^2 + \omega_2^2$ . When the prediction is near zero, the variance is approximately constant, namely  $\omega_2^2$ . This is the

smallest variance possible and corresponds, perhaps, to the limit of assay precision. When the prediction is considerably greater than zero, the variance is approximately proportional to the squared prediction.

### 3.4. The Power Function Model

A model that has both the additive and the CCV error models as special cases, and smoothly interpolates between them in other cases is the Power Function model:

$$y_j = f(x_j, \phi) + f(x_j, \phi)^p \eta_j. \quad (3.7)$$

Here  $f(x, \phi)$  is raised to the  $p^{\text{th}}$  power in the error model, rather than the  $0^{\text{th}}$  power (Additive error model; note  $a^0 = 1$  for any number,  $a$ ) or the first power (CCV model). The parameter  $p$  is a fixed effects parameter, even though its role in the overall model is to modify the variance model, not the structural model. With NONMEM all fixed effect parameters must be elements of the general parameter vector  $\theta$ . If we want the Power Function Model to interpolate between the additive and CCV models,  $p$  must be constrained to lie between 0 and 1. NONMEM allows this (see Chapter 9). While one might be tempted to combine the Power Function model with the Additive model, much as the CCV and Additive model were combined above, such a combination model can lead to identifiability difficulties, and for this reason such a combination should be avoided.

### 3.5. Two Different Types of Measurements

Another more complicated error model can arise when more than one type of measurement is made. Suppose, for sake of illustration, that the observations are drug concentrations, but that they are measured with two different assays. If one assay may be more precise than the other, then this is equivalent to saying that one assay has a smaller  $\omega^2$  than the other. We would like to be able to take this into account in the analysis (i.e., not pay as much attention to the less precise observations), and perhaps (if we have enough data) estimate the relative precision of the assays as well. To do this in the notation we have introduced, an independent variable indicating which observations are obtained with which assay is needed: we call such an independent variable an indicator variable.

#### 3.5.1. Use of an Indicator Variable

Let one of the data items (an element of  $x$ ) be labeled  $ASY$ , and let  $ASY_j$  take the value 1 if the assay used for  $y_j$  was of the first type, and the value 0, if it was of the 2nd type. The variable,  $ASY$  is an indicator variable, and it allows us to write an additive type error model, say, as

$$y_j = f(x_j, \phi) + ASY_j \eta_1 + (1 - ASY_j) \eta_2 \quad (3.8)$$

Here there are two types of  $\eta$ 's,  $\eta_1$  and  $\eta_2$ . The first applies to the first type of assay, and has variance  $\omega_1^2$ ; the second applies to the second type of assay, and has a possibly different variance,  $\omega_2^2$ . NONMEM permits several types of  $\eta$ 's. Different types of  $\eta$ 's can be correlated, and NONMEM can allow this. However, this is something we would only need to consider in the example at hand if the same blood sample were measured by both assays. We will not emphasize this possibility in this introductory guide. (This possibility also applies to random variables describing unexplained interindividual differences with population data; see Chapter 4)

When the assay is done by the first method,  $ASY$  will be unity, and (3.8) becomes

$$y_j = f(x_j, \phi) + \eta_1 \quad (3.8a)$$

so that the variance of the error is  $\omega_1^2$ . When the assay is done by the second method,  $ASY$  will be zero, and (3.7) becomes

$$y_j = f(x_j, \phi) + \eta 2_j \quad (3.8b)$$

so that the variance of the error is now  $\omega_2^2$ . Both  $\omega_1^2$  and  $\omega_2^2$  are random effect parameters. An equivalent form of the model that can be implemented easily is

$$y_j = \begin{cases} f(x_j, \phi) + \eta 1_j, & \text{if } ASY_j \text{ is } 1 \\ f(x_j, \phi) + \eta 2_j, & \text{if } ASY_j \text{ is } 0 \end{cases} \quad (3.8c)$$

### 3.6. Two Different Types of Observations

The same need for separate scales for different measurements can arise when more than one type of observation is made. Suppose both plasma concentrations ( $C$ ) and urine concentrations ( $Cu$ ) are measured. The structural model for  $C_j$  might be (3.1), (3.3). If we assume that urine is collected between each observation of  $C$ , then the structural model for  $Cu_j$ , the drug concentration in the urine collected between time  $t_{j-1}$  and time  $t_j$  might be

$$\tilde{C}u_j = f_o \frac{D}{Vu_j} (e^{-kt_{j-1}} - e^{-kt_j}) \quad (3.9)$$

where  $f_o$  is the fraction of drug excreted unchanged (a parameter), and  $Vu_j$  is the urine volume collected between time  $t_{j-1}$  and  $t_j$  (a data item)<sup>†</sup>. Assuming again, for sake of the example, that we want to use an additive type error model for the observations, the problem is that urine concentrations can be orders of magnitude larger than plasma concentrations, so that, while an additive error model might be appropriate for either type of observation alone, the two types of observations must have different typical error magnitudes; i.e., different variances ( $\omega^2$ 's).

An indicator variable can again be used. Let the indicator variable  $TYP$  be unity if the  $j^{\text{th}}$  observation is a  $C$ , and 0 if it is a  $Cu$ . We now need to use it for both the structural and error models, so that:

$$y = TYP_j \tilde{C}_j + (1 - TYP_j) \tilde{C}u_j + TYP_j \eta 1_j + (1 - TYP_j) \eta 2_j \quad (3.10)$$

A little thought shows that the indicator variable selects the correct prediction ( $\tilde{C}$  or  $\tilde{C}u$ ) and the correct error term for each observation ( $y$ ).

An equivalent form of the model that can be implemented easily is

$$y = \begin{cases} \tilde{C}_j + \eta 1_j, & \text{if } TYP_j \text{ is } 1 \\ \tilde{C}u_j + \eta 2_j, & \text{if } TYP_j \text{ is } 0 \end{cases} \quad (3.10a)$$

### 3.7. More Than One Indicator Variable

Of course, there could be three types of assays, or more, and similarly, more than two types of observations. One usually needs one less indicator variable than types of things to be distinguished. So, if there were three assays, one would define  $ASY1$  and  $ASY2$ .  $ASY1$  would be 1 if the assay were of the first type, and zero otherwise;  $ASY2$  would be 1 if the assay were of the second type, and zero otherwise. The error model for the data

<sup>†</sup> With all PREDPP pharmacokinetic models there is an output compartment for which the total amount of drug leaving the system is computed automatically. The concentration in the urine is then obtained by setting the scaling parameter for the output compartment to  $Vu$ .

would require three types of  $\eta$ 's,  $\eta_1$ ,  $\eta_2$ , and  $\eta_3$ .

$$y_j = f(x_j, \phi) + ASY1_j \eta_1 + ASY2_j \eta_2 + (1 - ASY1_j)(1 - ASY2_j) \eta_3 \quad (3.11)$$

Equation (3.11) results in the following:

| Assay | ASY1 | ASY2 | Type of $\eta$ | var( $y_j$ ) |
|-------|------|------|----------------|--------------|
| 1     | 1    | 0    | $\eta_1$       | $\omega_1^2$ |
| 2     | 0    | 1    | $\eta_2$       | $\omega_2^2$ |
| 3     | 0    | 0    | $\eta_3$       | $\omega_3^2$ |

An equivalent form of the model that can be implemented easily is

$$y_j = \begin{cases} f(x_j, \phi) + \eta_1, & \text{if } ASY1_j \text{ is } 1 \\ f(x_j, \phi) + \eta_2, & \text{if } ASY2_j \text{ is } 1 \\ f(x_j, \phi) + \eta_3, & \text{if } ASY1_j \text{ is } 0 \text{ and } ASY2_j \text{ is } 0 \end{cases} \quad (3.10a)$$

### 3.8. The General Mixed Effects Model for an Individual

We have just seen examples of more complicated error models than the simple Additive model. We here give a mathematical form for the most general mixed effects model that is considered within the scope of this document:

$$y_j = f(x_j, \phi) + h'(x_j, \phi) \eta_j \quad (3.12)$$

where  $h$  is a vector valued function of  $x$  and parameters  $\phi$  (where the latter is interpreted broadly to contain parameters such as  $p$  of (3.7)), and  $\eta$  is a vector of different different  $\eta$  types. The notation  $h'$  denotes vector transpose. When there is more than one  $\eta$  type, there will be several  $\omega^2$ 's, one for each type. The collection of these is denoted  $\Omega$  and is labeled OMEGA in NONMEM input and output. This collection is regarded as a diagonal matrix (diagonal for now; but see Chapter 4), rather than as a vector. We will use the symbol  $\omega_k^2$  and  $\omega_{kk}$  interchangeably in this text to denote the (diagonal) element of this matrix found in position  $k, k$ .

## Chapter 4 - Models for Population Data

### 1. What This Chapter is About

In this chapter, models for data from (animal or human) populations will be discussed. These models describe observations from a number of individuals sampled from the population. The distinguishing feature of the data to which such models apply is that there is *more than one* observation from some (usually most) individuals. A population model includes the structural model of Chapter 3, but also a new model, which shall be called the parameter model, for each individual's kinetic parameters. The parameter model can have both fixed and random effects. A population model also includes the error model of Chapter 3.

### 2. General

Individuals differ, and the types, degrees and causes of these differences are often what we want to learn. NONMEM was designed to help us learn these things. These individual differences can be due to fixed and/or random effects, but they all manifest themselves by affecting the value of an individual's parameters,  $\phi$ . That is, first, each individual is regarded as having his own particular value of  $\phi$ . If the data come from  $i = 1, \dots, N$  individuals, then we may rewrite the (not completely) general mixed effects model, (3.4) for  $y_{ij}$ , the  $j^{\text{th}}$  observation from the  $i^{\text{th}}$  individual, as

$$y_{ij} = f(x_{ij}, \phi_i) + \varepsilon_{ij} \quad (4.1)$$

Eq (4.1) is now (part of) a population model because it explicitly recognizes, through the subscript,  $i$ , that the data come from distinct individuals. Note too that we have written  $\varepsilon$ , rather than  $\eta$ . According to NONMEM conventions, when modeling data from a *population*, the random effects in the residual errors are denoted by  $\varepsilon$ , their individual variances by  $\sigma^2$ , and the collection of the variances by the matrix  $\Sigma$ , denoted SIGMA in NONMEM input and output. We also adopt the same convention here as we did for  $\Omega$ : the  $k^{\text{th}}$  diagonal element of  $\Sigma$  is interchangeably denoted  $\sigma_k^2$  or  $\sigma_{kk}$ .

When dealing with population data, the symbol  $\eta$  is reserved for random effects influencing the vectors  $\phi_i$ , as is now explained. We can write a general model (but not yet as general a model as we will present later) for  $\phi_i$ :

$$\phi_i = g(z_i, \theta) + \eta_i \quad (4.2)$$

It is called the parameter model. Here,  $g$  is a structural (though non-kinetic) type model (of which examples will be given shortly), which is a function of fixed effects,  $z_i$ , and fixed effects parameters,  $\theta$ . Note that since, in general,  $\phi$  is a vector,  $g$  must be a vector-valued function, and for the same reason,  $\eta$  is usually a vector. This will be discussed further later. All fixed effects, whether they are part of the kinetic structural model, or are part of the parameter model, are input to NONMEM in a uniform way. For the purposes of this discussion, the symbol  $z$  is used for the particular fixed effects in  $g$ , such as the individual's height, weight, and so forth (this will be discussed further in a moment). Even though most often  $\phi$  is regarded as time invariant, as is done in most of the discussion in this document, fixed effects can change with time, and thus kinetic parameters within  $\phi$  can change with time. This will be discussed further in Section 3.4.2.

### 3. Structural Parameter Models

The symbol in (4.2) for the fixed effects parameter vector is  $\theta$ , not  $\phi$ . As mentioned in Chapter 3, we reserve the symbol  $\phi$ , in this document, for an individual's fixed effect parameters and use the symbol  $\theta$  for a vector of *population* (fixed effects and possibly random effects) parameters.

Recall the phenobarbital example of Chapter 2. For the second run, the input contained the line of code

```
TVCL = THETA(1) + THETA(3)*WT
```

Translated into the symbols we are using here, this is

$$\tilde{C}l_i = \theta_1 + \theta_3 WT_i \quad (4.3)$$

In (4.3),  $\theta_1$  and  $\theta_3$  are the first and third elements of the parameter vector  $\theta$ , and  $WT_i$  is an element of  $z_i$  (recall that this value of weight appears as a data item). The tilde over  $CL$  is meant to distinguish this typical population value of clearance from the  $i^{\text{th}}$  individual's actual value of clearance. According to this model,  $\tilde{C}L_i$  will be the same for any two individuals both of whom have the same value of weight. Equation (4.3) defines an element (the one associated with clearance) of the vector-valued function  $g$ . Note that in (4.3), we use the subscript  $i$  to stress that this equation applies to the  $i^{\text{th}}$  individual, but there is no confusion when, as in the NM-TRAN input, and in the following, the subscript is omitted. It should always be understood that all variables and data items used in the parameter model definition refer to the same individual. Many different models are possible to describe the dependence of individual parameters on fixed effects. However, certain model forms are simple, easy to use, and cover most cases. An assortment of these will be discussed briefly next.

#### 3.1. Linear Models

The simplest form that  $g$  can take, and the most common, is one that is linear in  $\theta$ . An example is (4.3): all elements of  $\theta$  appear as linear coefficients of terms involving data items. The data items themselves can appear nonlinearly, without affecting the linearity with respect to  $\theta$ . For example, if clearance is the sum of renal and non-renal components, and renal clearance is believed to be proportional to renal function as described according to a standard formula involving the elements of  $z$ : age ( $AGE$ ), serum creatinine ( $SECR$ ), and weight ( $WT$ ), then one might write

$$\tilde{C}L_{met} = \theta_1 WT \quad (4.4)$$

$$RF = WT \frac{1.66 - .011 AGE}{SECR} \quad (4.5a)$$

$$\tilde{C}L_{ren} = \theta_4 RF \quad (4.5b)$$

$$\tilde{C}l = \tilde{C}L_{met} + \tilde{C}L_{ren} \quad (4.6)$$

Clearly,  $RF$  is a nonlinear function of  $SECR$ , for example, and so, therefore, is  $\tilde{C}l$ , but  $\tilde{C}l$  is linear in  $\theta$ , and (4.4 - 4.6) is still considered a linear model. (Do not worry about the non-consecutive numbering of the elements of  $\theta$ ; a model for  $\tilde{C}L$  is being developed (an alternative to 4.3), and the missing elements  $\theta_2$  and  $\theta_3$  will appear presently.)

### 3.2. Multiplicative Models

Multiplicative models are linear models, but on a logarithmic scale. For example, if patients covering a very wide range of weights are studied, metabolic clearance might vary with weight, but not linearly, and a substitute for (4.4) might be

$$L\tilde{C}l_{met} = \theta_1 + \theta_2 \log(WT) \quad (4.4.1)$$

$$\tilde{C}l_{met} = \exp(L\tilde{C}l_{met})$$

Note that the logarithm of  $\tilde{C}l_{met}$  ( $L\tilde{C}l_{met}$ ) is linear in  $\theta$ , but  $\tilde{C}l_{met}$  itself is not. Of course, (4.4.1) can also be written

$$\tilde{C}l_{met} = \theta_1 WT^{\theta_2} \quad (4.4.2)$$

Models (4.4.1) and (4.4.2) are equivalent so far as  $\tilde{C}l$  is concerned, but  $\theta_1$  of (4.4.2) corresponds to  $\exp(\theta_1)$  of (4.4.1).

### 3.3. Saturation Models

A useful model for processes reaching a maximum is a hyperbolic model. For example, if a second drug, (whose steady-state plasma concentration,  $C_{pss_2}$  is known and available in the data set), is present in some individuals and it is believed that this second drug is an inhibitor of the metabolism of the study drug, one might wish to use

$$\tilde{C}l_{met} = WT \left( \theta_1 - \frac{\theta_2 C_{pss_2}}{\theta_3 + C_{pss_2}} \right) \quad (4.4.3)$$

This model is shown in figure 4.1. The inhibition is expressed by the ratio occurring within the brackets and is a concave hyperbola, asymptoting to a maximum value equal to  $\theta_2$ . It is identical in form to the familiar Michaelis-Menten model.




Figure 4.1. A hyperbolic model for metabolic clearance of drug on the ordinate, as inhibited by another drug at steady-state concentration  $C_{pss_2}$  on the abscissa.

### 3.4. Models with Indicator Variables

Indicator variables were discussed in Chapter 3 in connection with the error model. They can be quite useful when modelling individual parameters. They are usually used in a linear model. For example, if the clinical condition, heart failure, is noted as "present" or "absent", one can define an indicator variable,  $HF$  which equals 0 if heart failure is absent, and 1 if it is present. If metabolic clearance is thought to be affected by heart failure, one might choose

$$\tilde{Cl}_{met} = (\theta_1 - \theta_2 HF)WT \quad (4.4.4)$$

Here, the non-heart-failure cases will have  $\tilde{Cl}_{met} = \theta_1 WT$ , while the heart-failure cases will have  $\tilde{Cl}_{met} = (\theta_1 - \theta_2)WT$ †.

#### 3.4.1. Combinations

Given the basic building blocks of linear, multiplicative and saturation models, these can be combined in the usual algebraic ways (usually by addition) to make more complex models. For example, one could use (4.4.3), (4.5), and (4.6) as a model for  $\tilde{Cl}$ . A non-additive example arises if plasma and urine concentrations are both observed and (kinetic) model (3.6) is to be used for the latter. The parameter  $f_o$ , the fraction of drug excreted unchanged into the urine might be modeled as

$$f_o = \frac{\tilde{Cl}_{ren}}{\tilde{Cl}} \quad (4.7)$$

where  $\tilde{Cl}_{ren}$  is given by (4.5) and  $\tilde{Cl}$  by (4.6) (using any of the (4.4) variants).

#### 3.4.2. Time Varying $z$

As mentioned in Section 2, although most of the time the data items affecting an individual's  $\phi$  do not change over the course of his data, they occasionally do, and PREDPP can handle this. For example, if an individual had heart failure for part of his observation period, but not the rest,  $\tilde{Cl}_{met}$ , according to (4.4.4) should change. Or, if acute renal failure occurred during a patient's observation period,  $\tilde{Cl}_{ren}$  would change, according to model (4.5).

PREDPP implements its kinetic model recursively: given the state of the system at time  $t_j$  (by state we mean the amounts of drug in all the compartments), it updates (i.e. advances) the state to that at time  $t_{j+1}$ , using the value of  $z$  (and in general, the value of  $x$ ) at time  $t_{j+1}$  to compute a value of  $\phi$  holding between times  $t_j$  and  $t_{j+1}$ . The value of  $z$  used to compute this  $\phi$  is that value found on the data record with time  $t_{j+1}$ . So, in order to have  $\phi$  change appropriately as  $z$  does, one places a value of  $z$  which is typical for the time period  $t_j$  to  $t_{j+1}$  on the data record associated with the time point  $t_{j+1}$ . This will not always be easy since the relevant element(s) of  $z$  may not be measured at, for example, the midpoint of the time interval (the value at the *midpoint* of the time interval is a good choice for the *typical* value for the interval). If not, one will have to use some interpolation method to arrive at the typical value. The important point is that the values of the independent variables at time  $t_{j+1}$  determine the values of the individual's parameters applying to the entire period  $t_j$  to  $t_{j+1}$ .

† Heart failure is expected to decrease metabolic clearance. If it does, using a minus sign in (4.4.4) allows the more pleasing result that  $\theta_2$  will be estimated as positive. The model is identical to one with a positive sign, but then  $\theta_2$  would probably be negative. If  $\theta_2$  were constrained to be non-negative, then the sign chosen in the model statement would, of course, be important.

### 3.5. Structural Kinetic Models

The kinetic models (i.e., the models for responses such as drug concentrations) used when performing a population analysis do not differ at all from those used for an individual analysis. One still needs a model for the relationship of  $y$  to  $\phi$  and  $x$ , and this relationship does not depend on whether  $\phi$  changes from individual to individual or with time within an individual.

## 4. Population Random Effects Models

Under NONMEM conventions, there are two levels of random effects, and  $\eta$  and  $\varepsilon$  are the symbols used for the vectors of first and second level random effects, respectively. With data from a single individual, only first-level random effects are needed. However, with data from a population of individuals, both first- and second-level random effects are needed. First-level effects are needed in the parameter model to help model unexplainable interindividual differences in  $\phi$ , and second-level effects are needed in the (intraindividual) error model. For example, in (4.2) there is an element of  $\eta_i$ ,  $\eta_i^V$ , that is the difference between the individual value  $V_i$  (an element of  $\phi$ ) and  $\tilde{V}_i$ , the typical value of  $V_i$ . This is a first-level random effect. In (4.1)  $\varepsilon_{ij}$  is the error between  $y_{ij}$  and  $f(x_{ij}, \phi_i)$ . This is a second-level random effect.

### 4.1. Models for Interindividual Errors

The difference between  $\phi_i$  and  $g(z_i, \theta)$  is called an interindividual error. It arises from a few sources: the function  $g$  may be only approximate, and/or  $z$  may be measured with error. It is regarded as a random quantity, and it may be modeled in terms of  $\eta$  variables. As usual, each of these variables is assumed to have mean 0 and a variance denoted by  $\omega^2$  which may be estimated. This variance describes biological population variability.

The difference between  $y_{ij}$  and  $f(x_{ij}, \phi_i)$  is called an intraindividual error. It has been discussed at some length in Chapter 3. Although in that discussion about individual data, this difference was modeled in terms of  $\eta$  variables, in this discussion about population data, it is modeled in terms of  $\varepsilon$  variables. Each  $\varepsilon$  variable is assumed to have mean 0 and a variance denoted by  $\sigma^2$  which also may be estimated.

Each pair of elements in  $\eta$  has a covariance, and NONMEM can also estimate this, although often we choose to assume that the covariance is zero (we made this same assumption for the different elements of  $\eta$  in Chapter 3, Section 3.5.1).

A covariance between two elements of  $\eta$ ,  $\eta_k$  and  $\eta_m$ , say, is a measure of statistical association between these two random variables. Their covariance is related to their correlation,  $\rho_{km}$  ( $\rho_{km} \equiv \rho_{mk}$ ) by

$$\text{cov}(\eta_k, \eta_m) = \rho_{km} \omega_k \omega_m \quad (4.8)$$

(Note that now that we are suppressing the subscript  $i$  on  $\eta$ , we may, without confusion, use the subscript position to designate elements of  $\eta$ .)

The variances and covariances among the elements of  $\eta$  are laid out in a covariance matrix, called  $\Omega$ , and labeled OMEGA in NONMEM input and output. This matrix was defined in Chapter 3, Section 3.8, but some additional comment here may be helpful. If  $\eta$  has, for example, 3 elements,  $\Omega$  has the following form:

$$\begin{array}{ccc} \omega_{11} & \omega_{12} & \omega_{13} \\ \omega_{21} & \omega_{22} & \omega_{23} \\ \omega_{31} & \omega_{32} & \omega_{33} \end{array}$$

Here, as previously,  $\omega_{kk}$  is another way of writing the variance  $\omega_k^2$ , and  $\omega_{km}$  ( $k \neq m$ ) is the covariance between  $\eta_k$  and  $\eta_m$ .

The elements  $\omega_{11}$ ,  $\omega_{22}$ ,  $\omega_{33}$  are called the diagonal elements of the matrix. If the nondiagonal elements (the covariances) are all zero, i.e. the correlation among all pairs of  $\eta$  elements is zero, the matrix is called a diagonal matrix. The lower triangular elements of the matrix are the elements

$$\begin{array}{ccc} \omega_{11} & & \\ \omega_{21} & \omega_{22} & \\ \omega_{31} & \omega_{32} & \omega_{33} \end{array}$$

To specify the matrix only its lower triangular elements need be given (and these are all NONMEM does give), since from (4.8) it is clear that for all  $k, m$ ,  $\omega_{km} = \omega_{mk}$ .

#### 4.1.1. Additive/Multiplicative Models and the Exponential Model

Frequently, the model for an interindividual error is the simple additive one (as in (4.2)), such as

$$V = \tilde{V} + \eta_2 \quad (4.9)$$

A feature of (4.9) is that the resulting units for  $\omega^2$  depend on the units of the parameter ( $V$  in this case). For example, this model was used in the theophylline problem of Chapter 2 (Figure 2.6). The final estimate of  $\omega_2^2$  is .286 (Figure 2.8). Assuming that the units of  $V$  are liters, we interpret this to mean that the standard deviation of  $V$  between individuals is .53 Liters ( $.53 = \sqrt{.286}$ ).

Perhaps even more often, a multiplicative model equivalent to the Constant Coefficient of Variation (CCV) error model (3.5) is used, such as

$$V = \tilde{V}(1 + \eta_2) \quad (4.10)$$

This model is also referred to as the proportional error model.

A feature of (4.10) is that the resulting units for  $\omega^2$  are independent of the units of the parameter ( $V$  in this case). When this model is used in the theophylline problem instead of the additive model, so that Figure 2.6 contains the code `V=TVVD*(1+ETA(2))` instead of `V=TVVD+ETA(2)`, then NONMEM estimates  $\omega_2^2$  to be .146. We interpret this to mean that the coefficient of variation of  $V$  in the population is 38% ( $.38 = \sqrt{.146}$ ).

The exponential model is

$$V = \tilde{V} \exp(\eta_2) \quad (4.10a)$$

During simulation, (Chapter 12, Section 4.8), the exponential and proportional models give different results. During estimation by the first-order method, the exponential model and proportional models give identical results, i.e., NONMEM cannot distinguish between them. During estimation by a conditional estimation method, the exponential and proportional models for inter-individual variability give different results. The exponential model is preferred for conditional estimation methods. (See NONMEM User's Guide Part VII, Conditional Estimation Methods.)

#### 4.1.2. Other Models

Occasionally, a model for an individual's pharmacokinetic parameter might involve scaling an  $\eta$ , as in (3.6), or two or more  $\eta$ 's as in (3.10). For example, a study might involve patients in the intensive care unit (ICU) and others on non-acute care units. It might be

reasonable to suppose that some aspects of the kinetics of ICU patients (e.g., metabolic clearance of drug) are more variable, due to unmeasured factors (e.g., hepatic function) that vary greatly among acutely ill patients. Even though the variation is, in reality, due to a potentially measurable fixed effect (hepatic function), if information on this fixed effect is not available, differences caused by it must be assigned to random factors ( $\eta$ ). In this case, one might wish to use an indicator variable,  $ICU$  (which equals 1 if the patient is in the ICU, and 0, otherwise), and a model such as

$$Cl_{met} = \tilde{Cl}_{met} + (1 - ICU)\eta_1 + ICU\eta_2 \quad (4.11)$$

In addition to model (4.11) we might have, for example,

$$Cl_{ren} = \tilde{Cl}_{ren} + \tilde{Cl}_{ren}\eta_3 \quad (4.12a)$$

$$Cl = Cl_{ren} + Cl_{met}. \quad (4.12b)$$

Models (4.11) and (4.12) together, along with suitable models for  $\tilde{Cl}_{ren}$  and  $\tilde{Cl}_{met}$ , form a complete model for an individual's  $Cl$  parameter, and involve 3  $\eta$ 's.

#### 4.1.3. General Form for the Parameter Model

As we have just seen in (4.10) and in (4.11)-(4.12), an element of  $\eta$  need not act in a simple additive way and may act solely on an intermediate variable (e.g.  $Cl_{met}$ ). Indeed, there may be more or fewer elements in  $\eta$  than in  $\phi$ , the elements in  $\eta$  may act in nonlinear ways to influence  $\phi$ , and one element of  $\eta$  may influence more than a single element of  $\phi$ . We now give a more general form for the parameter model than (4.2) and then an example illustrating it.

The general form of the parameter model is

$$\phi_i = g(z_i, \theta, \eta_i) \quad (4.13)$$

Here,  $g$  is a very general function of fixed effects,  $z_i$ , fixed effects parameters,  $\theta$ , and a vector of  $\eta$ 's,  $\eta_i$ . The dimensions of the vectors  $\phi_i$  and  $\eta_i$  need not be the same. An individual's kinetic parameter may change with time. As explained in Section 1.6, with NONMEM-PREDPP changes can occur only at discrete time points. Therefore, the parameter actually can be regarded as being a number of parameters, each one applying to a different time period. The parameter  $\phi_i$  in (4.13), being a vector of all the kinetic parameters for the  $i^{th}$  individual, can be regarded as encompassing these time-interval-specific parameters.

An example utilizing this generality is provided by a model for observations of both plasma and urine drug concentrations, similar to the one presented previously. Ignoring the details of the structural part of the model, consider the following model

$$\begin{aligned} Cl_{met} &= \tilde{Cl}_{met} + \eta_1 \\ Cl_{ren} &= \tilde{Cl}_{ren} + \eta_2 \\ Cl &= Cl_{met} + Cl_{ren} \end{aligned} \quad (4.14)$$

$$f_o = \frac{Cl_{ren}}{Cl}$$

$$V = \tilde{V} + \eta_3$$

In this model,  $\phi = (V, Cl, f_o)$ ; the parameters  $Cl_{met}$  and  $Cl_{ren}$  are regarded as intermediate parameters. We have  $\eta = (\eta_1, \eta_2, \eta_3)$ , where both  $\eta_1$  and  $\eta_2$  influence both  $Cl$  (linearly) and  $f_o$  (nonlinearly).

#### 4.2. Statistical Models for an Individual's Observations

Model (4.1) can be generalized by incorporating a model like those given in Chapter 3 for the residual errors, i.e. for the differences between the  $y_{ij}$  and  $f(x_{ij}, \phi_i)$ , rather than using just the simple Additive model. A particular instance of such a model may have several types of  $\varepsilon$ 's, and as mentioned in Section 2, the variances of these  $\varepsilon$ 's are denoted by  $\sigma^2$ 's. With a population model these variances could change from individual to individual. With NONMEM, they are considered as constants over individuals. The  $\varepsilon$ 's can covary. A covariance matrix  $\Sigma$ , like the  $\Omega$  matrix given in Section 4.1, gives the variances and covariances of the  $\varepsilon$ 's, as already discussed at the end of Chapter 3. This does not preclude the magnitudes of the errors from being affected by fixed effects. A model such as (3.8) can still be used. This is shown explicitly by the general model given in the next section.

#### 5. The Population Mixed Effects Model

We have now presented all of the parts needed to fully define a population model. It may be useful to recap this information by stating the entire general model here:

$$y_{ij} = f(x_{ij}, \phi_i) + h'(x_{ij}, \phi_i)\varepsilon_{ij} \quad (4.15a)$$

$$\phi_i = g(x_{ij}, \theta, \eta_i) \quad (4.15b)$$

$$cov(\varepsilon_{ij}) = \Sigma; \quad cov(\eta_i) = \Omega$$

$$\varepsilon_{ij}, \varepsilon_{kl} \text{ independent for } (i, j) \neq (k, l)$$

$$\eta_i, \eta_k \text{ independent for } i \neq k$$

$$\varepsilon_{ij}, \eta_k \text{ independent for all } i, j, k,$$

where here,  $\varepsilon_{ij}$  is a vector, along with  $x_{ij}$ ,  $\phi_i$ ,  $\theta$  and  $\eta_i$ , and  $\Sigma$  and  $\Omega$  are square matrices with dimensions equal to those of  $\varepsilon_{ij}$  and  $\eta_i$ .

To try to represent the relationship between all the fixed and random effects of a population model graphically, consider figure 4.2. The model corresponding to this figure is

$$y_{ij} = \frac{D}{V_i} \exp[-(Cl_i/V_i)t_{ij}] + \varepsilon_{ij}$$

$$Cl_i = \theta_1 + \theta_2 RF_i + \eta_i^{Cl} \quad (4.16)$$

$$V_i = V$$

$$var(\varepsilon_{ij}) = \sigma^2; \quad var(\eta_i^{Cl}) = \omega_{Cl}^2$$

where the  $V_i$  are all equal to a constant  $V$ , i.e. there is no random interindividual variability in the volume of distribution, so that for the sake of this example,  $\eta_i$  is just a scalar.




Figure 4.2. Random and fixed effects influence observation,  $C_{ij}$ , from the population point of view. Open circle, lower left, is population parameter predicted clearance, closed circle is true clearance for  $i^{th}$  individual which differs from population prediction by  $\eta_i^{Cl}$ , chosen randomly from a distribution (upper left) with mean 0 and SD  $\omega_{Cl}$ . Similarly, lower right, the observed  $C$  at time  $t_{ij}$  (open square) differs by  $\varepsilon_{ij}$  from the true value (closed circle) by an error  $\varepsilon_{ij}$ , chosen independently from a distribution with mean 0 and SD  $\sigma_\varepsilon$ . The  $C$  corresponding to the population-based prediction is also shown (upper curve, open circle).

## Chapter 5 - Estimates, Confidence Intervals, and Hypothesis Tests

### 1. What This Chapter is About

In this chapter, we discuss the fitting criterion that NONMEM uses, parameter estimates, and standard error estimates. We then discuss how to form confidence intervals for parameters and do hypothesis tests with NONMEM.

### 2. Model Fitting Criterion

In principle, all fitting procedures attempt to adjust the values of the parameters of the model to give a "best fit" of the predictions to the actual observations. The set of parameters that accomplish this are called the parameter estimates, and are denoted here as  $\hat{\theta}$ ,  $\hat{\Omega}$ , and  $\hat{\Sigma}$ . Methods differ in how they define "best". The criterion that NONMEM uses is a Least Squares (LS) type criterion. The form of this criterion varies as the error model varies, and as population models with multiple random effects must be considered. We briefly discuss these various criteria next, to give the reader a feel for what NONMEM is doing. A detailed knowledge of the statistical basis for the choice of fitting criterion is not necessary either to use or interpret NONMEM fits. In this chapter, a fixed effects parameter will be denoted by a  $\theta$ ; the distinction between individual fixed effects parameters ( $\phi$ ) and population fixed effects parameters will not be important here.

#### 2.1. Least Squares for Individual Data with an Additive Error Model

For the Additive error model (3.4), the Ordinary Least Squares criterion (OLS) chooses the estimate  $\hat{\theta}$  so as to make the sum of squared (estimated) errors as small as possible. These estimates cause the prediction, here denoted  $\tilde{y}$ , to be an estimate of the mean value of  $y$ , which is intuitively appealing. The prediction is obtained by computing the value for  $y$  under the model with parameters set to their estimated values and  $\eta$  set to zero<sup>†</sup>.

#### 2.2. Least Squares for Individual Data with Other Types of Error Models

The simple OLS criterion just defined becomes inefficient and is no longer the "best" one to use when the error model is other than the Additive error model. It treats all estimated errors as equally important (i.e. a reduction in the magnitude of either of two estimated errors that are of the same magnitude is equally valuable in that either reduction decreases the sum of squared errors by the same amount), and this results in parameter estimates that cause all errors to have about the same typical magnitude, as assumed under the Additive model. The CCV error model, though, says that the typical magnitude of an error varies monotonically with the magnitude of the (true) prediction of  $y$ . In principle, Weighted Least Squares (WLS) gives a fit more commensurate with the CCV or other non-Additive error model. WLS chooses  $\hat{\theta}$  as that value of  $\theta$  minimizing

$$O_{WLS}(\theta) = \sum_j w_j (y_j - \tilde{y}_j)^2 \quad (5.1)$$

Each  $w_j$  is a weight which, ideally, is set proportional to the inverse of the variance of  $y_j$ . In the CCV model this variance is proportional to  $\tilde{y}_j^2$  (evaluated at the true value of  $\theta$ ). Use of such weights will down-weight the importance of estimated squared errors associated with large values of  $\tilde{y}$  and promote the relative contribution of those associated with small values of  $\tilde{y}$ .

<sup>†</sup>  $\eta$ , not  $\varepsilon$ , since we follow the NONMEM convention and, when discussing individual type data as here, use  $\eta$  to denote the random effects of a single level that appear in the model, those in the residual error model.

In many cases, users can supply approximate weights, and the WLS objective function can be used as stated in (5.1). When, as with the CCV model for example, the ideal weights depend on the true values of parameters, these true values can be replaced by initial estimates, and then the WLS objective function as given in (5.1) can be minimized. Alternatively, instead of viewing  $O_{WLS}$  as a function of  $\theta$  only through the estimated error's dependence on  $\theta$ , it can be viewed as a function of  $\theta$  through both that dependence and *also* through the ideal weights' dependence on  $\theta$ . The entire function can then be minimized with respect to  $\theta$ . That this creates a problem is most easily seen when the error model contains a parameter which is not itself a parameter of the structural model, but which, nonetheless, must be regarded as an element of  $\theta$ . Such an error model is the Power Function model of (3.7), and the "extra" parameter is  $p$ . The WLS objective function with the reciprocal variance of  $y_j$  substituted for  $w_j$  is<sup>†</sup>

$$O_{WLS}^*(\theta) = \sum_j \left[ \frac{(y_j - \tilde{y}_j)^2}{\omega^2 \tilde{y}_j^p} \right] \quad (5.2)$$

In this case if  $p$  were set to a very large number, while the other parameters in  $\theta$  were only such as to make all  $\tilde{y}_j > 1$ , then all  $\tilde{y}_j^p$  would be very large, and the summation would attain a very small value. (The value of  $\omega^2$  is irrelevant to the minimization with respect to  $\theta$ .) Thus, all elements in  $\theta$  other than  $p$  would be indeterminate (as long as they were such that all  $\tilde{y}$  were greater than 1); a most unsatisfactory state of affairs.

There is a way to deal with this problem that preserves the spirit of least-squares fitting, and NONMEM uses it. In essence, it adds to the WLS objective function a term proportional to the sum of the logarithms of the error variances. Thus a penalty is paid for increasing the error variances without a concomitant decrease in the estimated errors themselves. This modified objective function is called the Extended Least Squares (ELS) objective function. It is minimized with respect to all parameters of the structural and error models simultaneously (in the current example,  $\theta$  and  $\omega^2$ , as  $p$  can be considered an element of  $\theta$ ). Note that the objective function may be negative. This has no particular significance.

### 2.3. Least Squares for Population Data

The complications arising from a population model are due entirely to the random interindividual effects occurring in the parameter model. To deal with this, NONMEM uses an approximation to the true model. The approximate model is linear in all the random effects. For this linearized model, the vector of mean values for the observations from the  $i^{th}$  individual is the vector of true predictions for these observations. These predictions are obtained from the model by setting the parameters to their true values and by setting all the elements of both  $\varepsilon$  and  $\eta$  to zero. In other words, these are the true predictions for the mean individual with fixed effects equal to those of the  $i^{th}$  individual. For this linearized model it is also possible to write a formula for the variance-covariance matrix of the observations from the  $i^{th}$  individual. This matrix is a function of the individual's fixed effects and the population parameters  $\theta$ ,  $\Omega$ , and  $\Sigma$ . Finally, the ELS objective function discussed above is generalized to be a sum over individuals, rather than observations, and where the  $i^{th}$  term of the sum involves a squared error between a vector of observations and an associated vector of predictions, weighted by the reciprocal of the associated variance-covariance matrix for the  $i^{th}$  individual.

<sup>†</sup> Again, we call attention to the symbols used for the random effects parameter: the term  $\omega^2$  appears in the objective function, (5.2), not  $\sigma^2$ , because we are discussing individual type data, not population type data.

### 3. Parameter Estimates

It is useful to consider how to estimate parameters that do not appear in the model we use to fit the data, but are, instead, functions of them (e.g. the half-life parameter  $t_{\frac{1}{2}} = .693/k$ , when the rate constant of elimination  $k$  is the model parameter).

It is always possible, of course, to parameterize the model in the function of interest. For example, we have already seen (Chapters 2 & 3) that we may use the function (parameter)  $Cl$  in the one-compartment model instead of  $k$ . However, we may be interested in the values of several alternative parameterizations (e.g., we may want to know  $k$ , clearance, and half-life). Rather than rerun the same problem with several alternative parameterizations, we can use the fact that the LS estimate of a function of the parameters is given by the same function of the LS parameter estimates. Formally, if  $\theta' = q(\theta)$  is the function of interest, then  $\hat{\theta}'_{LS} = q(\hat{\theta}_{LS})$ . E.g. Letting  $\theta' = t_{\frac{1}{2}}$ ,  $\theta = k$ , and  $q(\theta) = .693/\theta$ , then  $\hat{t}_{\frac{1}{2}} = .693/\hat{k}$ .

### 4. Precision of Parameter Estimates

Clearly, it is almost impossible for the estimates to actually be the true values. The question is: how far are the true values from the estimates? To discuss this question, imagine replicating the entire experiment (gathering new data, but keeping  $x$  fixed) multiple times. Also, for simplicity, imagine that the model has only one scalar parameter,  $\theta$ , and that its true value,  $\theta_T$  is known. If, after each replication, the estimate of  $\theta$  is recorded, and a histogram of these values is plotted, one might see something like figure 5.1A or 5.1B.




Figure 5.1. Two hypothetical histograms of estimates of a single parameter upon replication of a given experiment. Left panel (A): The estimates have small variance (spread) but are biased (the mean of the estimates differs from the true value,  $\theta_T$ ); Right panel: The estimates have large variance but are relatively unbiased.

The difference between the estimate and the true value,  $\theta_T$ , obviously differs from replication to replication. Let this difference be called the estimation error. We cannot know the estimation error of any particular estimate (if we could, we could know the true value itself, by subtraction), but we can hope to estimate the mean error magnitude. Since errors can be positive or negative, a measure of magnitude that is unaffected by sign is desirable. This is traditionally the Mean Squared Error (*MSE*). The MSE can be factored into two parts:

$$MSE = B^2 + SE^2 \quad (5.2)$$

where  $B$  is the bias of the estimates (mean (signed) difference between the estimates and

the true value) and  $SE$  is the standard error of the estimates ( $SE^2$  is the variance of the estimates). As illustrated in figure 5.1, the  $MSE$  can be about the same for two types of estimates while both their bias and  $SE$  differ. It is very hard to estimate the bias of an estimator unless the true parameter value is, in fact, known. This is not true of the  $SE$ : the standard deviation of the distribution of estimates of a parameter on replication is the  $SE$ ; no knowledge of the true value of the parameter is required. In many situations, LS estimators of fixed effects parameters are unbiased, although in nonlinear problems, such as most pharmacokinetic ones, this cannot be assured.

#### 4.1. Distribution of Parameters vs Distribution of Parameter Estimates

Figure 5.1 illustrates the distribution of parameter estimates that might result if an experiment were replicated. The bias and spread depend on the estimation method, the design of the experiment ( $x$ , which implicitly includes  $n$ ) and on the true parameter values, including the variances (and covariances) of the random effects influencing  $y$ . If, for example, more observations were obtained in each experiment (more individuals in a population study), the spread of the estimates (one from each experiment) would decrease until, in the limit, if an infinite number of observations were obtained in each experiment, every estimate would be the same (equal to the true value plus the bias of the estimator). Thus, the distribution of the estimate tells us nothing about biology or measurement error, but only about the *precision* of the estimate itself.

In contrast,  $\Omega$  and  $\Sigma$  tell us about unexplained (or random) interindividual variability (biology) or error magnitude (biology plus measurement error), not about how precisely we know these things. No matter how many observations we make, interindividual variability will remain the same size (but the variability of our estimate of its size will decrease), as will the measurement error variability of a particular instrument.

It is very important not to confuse variability (e.g., between individuals) in a model parameter with variability in the estimate of that parameter, despite the fact that the terms we use to describe both variabilities are similar. Thus an element of  $\eta$ , say  $\eta_1$  has a variance  $\omega_{11}$ , while the estimate of  $\omega_{11}$ ,  $\hat{\omega}_{11}$ , also has a variance given by the square of the standard error for  $\hat{\omega}_{11}$ . Indeed, the use of the term "standard error" rather than "standard deviation" to name a measure of the spread in the distribution of the parameter estimate rather than in the parameter helps call attention to the distinction between these two types of things.

#### 4.2. Confidence Interval for a Single Parameter

Acknowledging that any particular estimate from any particular experiment is unlikely to equal the true parameter value implies that we should be interested in "interval" estimates of parameters as well as (instead of?) point estimates. An interval estimate of a parameter is usually a range of values for the parameter, often centered at the point estimate, such that the range contains the true parameter value with a specified probability. The probability chosen is often 95%, in which case the interval estimate is called the 95% Confidence Interval (CI).

A CI is often based only on the parameter estimate and its  $SE$ . In the next sections we discuss three questions about such CIs a little further. (i) How to estimate the  $SE$  from a single set of data (we cannot replicate our experiment many times and construct a histogram as in figure 5.1). (ii) Given an estimate of  $SE$ , how to use that number to compute a (95% confidence) interval with 95% chance of containing the true parameter value. (iii) Given an estimate of  $SE$ , how to compute a confidence interval for a function of the parameter.

#### 4.2.1. Estimating a Parameter's Standard Error

Remarkably, the  $SE$  of a parameter estimate can be estimated using only the data from a single experiment. The idea is that the data give us estimates of the variances of all random effects in our model, from which we can estimate the variability in future data (if we were to replicate the experiment). That is, the  $SE$  of the estimates on replication depends only on quantities we either know or have estimates of: the  $x$ , the number of  $y$  observed ( $n$ ), and the variances of all random effects.

It is a little beyond the scope of this discussion to give the method by which NONMEM actually estimates the  $SE$  of a parameter estimate; however, examples of how this can be done are found in any statistical textbook on regression. NONMEM presents the estimated standard error for each parameter of the model (including the random effects parameters,  $\Omega$  and  $\Sigma$ ) as part of its output.

#### 4.2.2. Relating the Confidence Interval to the SE

Statistical theory tells us not only how to compute the  $SE$  of a parameter estimate, but also that for a LS estimate (and many other kinds of estimates), the shape of the distribution of the estimates is approximately Normal if the data set is large enough. This means that we may use percentiles of the Normal distribution, to compute confidence interval bounds (when  $n$  is small, the  $t$  distribution is often used instead; this is discussed in statistics texts). In general, a  $100(1-\alpha)\%$  confidence interval for a single parameter,  $\theta$  say, is computed as  $\hat{\theta} \pm Z_{1-\alpha/2}SE$ . Here  $Z_{1-\alpha/2}$  denotes the  $1 - \alpha/2$  percentile of the Normal distribution. As previously noted,  $\alpha$  is often chosen to be .05, in which case  $Z$  is approximately 2.

#### 4.2.3. A Confidence Interval for a Function of a Single Parameter

As discussed above, one can reparameterize the model in terms of the new parameter, and NONMEM will then estimate its standard error. If re-running the fit presents a problem, there is a simple way to compute a confidence interval for a function  $q$  of a single parameter. If the lower and upper bounds of a  $100(1-\alpha)\%$  confidence interval for  $\hat{\theta}$  are denoted  $b_l$  and  $b_u$ , respectively, then a  $100(1-\alpha)\%$  confidence interval for  $q(\hat{\theta})$  has lower and upper bounds  $q(b_l)$  and  $q(b_u)$ , respectively. This confidence interval, however, is not necessarily centered at  $q(\hat{\theta})$ .

### 4.3. Multiple Parameters

#### 4.3.1. Correlation of Parameter Estimates

A truly new feature introduced by multiple parameters is the phenomenon of correlation among parameter estimates. NONMEM outputs a correlation matrix for the parameter estimates. The  $(i, j)$  element of the matrix is the correlation between the  $i$ th and  $j$ th parameter estimates. A large correlation (e.g.  $\geq .95$ ) means that the conditional distribution of the  $i$ th estimate, given a fixed value of the  $j$ th estimate, depends considerably on this fixed value. Sometimes each parameter estimate of a pair that is highly correlated has a large standard error, meaning that neither parameter can be well-estimated. This problem may be caused by data that do not distinguish among the parameters very well, while a simpler model, or a different design, or more data might permit more precise estimates of each.

As a simple example, imagine a straight line fit to just two points, both at the same value of  $x$ : neither slope nor intercept can be estimated at all as long as the other is unknown, but fixing either one (simplifying the model) determines the other. Both parameters could

be estimated by observing another point at some other value of  $x$  (more data), or, still using just 2 points, by placing these points at two different values of  $x$  (modifying the design). Thus, when standard errors are large, it is useful to examine the correlation matrix of parameter estimates to see, in particular, if some simplification of the model may help.

#### 4.3.2. Confidence Intervals for a Function of Several Parameters

There is an approximate formula for computing a standard error, and hence a confidence interval for a function of several parameters (e.g., a confidence interval for half-life when the estimated parameters are  $Cl$  and  $V$ ). It uses the standard errors of the parameter estimates and the correlations between the parameter estimates. However, discussion of this formula is beyond the scope of this introduction. If a confidence interval for a function of several parameters is desired, it is often more convenient to re-fit the data with the model reparameterized to include the function as an explicit parameter.

### 5. Hypothesis Testing

Before going into details, a note of caution is in order about hypothesis testing in general. The logic of hypothesis testing is that one sets up a hypothesis about a parameter's value, called the null hypothesis, and asks if the data are sufficiently in conflict with it to call it into question. If they are, one rejects the null hypothesis. However, logically, if they are not, one has simply failed to reject the null hypothesis; one does not necessarily have sufficient data to accept it. An extreme example will make this clear. Let the null hypothesis be any assertion at all about the state of nature. Gather no evidence bearing on the question. Clearly, the evidence (which is void) is insufficient to reject the null hypothesis, but just as clearly, in this case the evidence provides no support for it either.

In less extreme cases there is a way to view failure to reject as lending some support to the null hypothesis, but the matter is problematic. It is somewhat less problematic to use a confidence interval to quantify support for a null hypothesis. A null hypothesis is an assertion that a parameter's true value is found among a set of null values. A confidence interval puts reasonable bounds on the possible values of a parameter. One can then say that the evidence (the data from which the parameter estimate is derived) *does* support a null hypothesis (about the value of the parameter) if the null values are included in the interval and that the evidence fully support the null hypothesis if all nonnull values lie outside. An example will help make this clear.

Consider that mean drug clearance in adults varies linearly with the weight of the individual to a *clinically* significant degree. Formally, this can be put as a statement about a regression coefficient in a model such as

$$Cl = \theta_1 + \theta_2(WT - 70), \quad (5.3)$$

The null hypothesis might be that  $\theta_2$  is close to zero, i.e. that it is not so different from zero as to be clinically significant. To make this precise, suppose that we know that mean clearance for a 70 kg person (i.e.,  $\theta_1$ ) is about 100 ml/min. If  $\theta_2$  were .20 ml/min/kg or less, a 50 kg increment (decrement) in weight from 70 kg would be associated with less than a 10% change in total clearance. This is clinically insignificant, so the appropriate null values for  $\theta_2$  might be 0.0 to .20, assuming, of course, that a physical lower bound for the parameter is zero. (More usually in statistical discussions a set of null values consists of a single number, e.g. 0.) If the confidence interval for  $\theta_2$  only includes null values (e.g., it is .10 to .15), one might then safely conclude that weight, if it has any effect at all, has no *clinically* significant effect, and that the data fully support the null hypothesis. If

the confidence interval includes null values and others (e.g., it is 0.0 to .60), one would conclude that there is some support for the null hypothesis, but that there is also some support for rejecting it. In this case the data are insufficient to allow outright acceptance or rejection. If the confidence interval includes no null values (e.g., it is .80 to 1.3), one would reject the null hypothesis and conclude that weight has a clinically significant (linear) effect on clearance.

For these reasons, we urge caution when performing hypothesis tests and suggest that confidence intervals are often more useful. None the less, the popularity of hypothesis tests requires that they be done, and we now describe two methods for so doing, the first somewhat more approximate and less general than the second, but easier to do.

### 5.1. Hypothesis Testing Using the SE

A straight-forward way to test a null hypothesis about the value of a parameter is to use a confidence interval for this purpose. In other words, if the confidence interval excludes the null values, then the null hypothesis is rejected. As described in Section 4.2.2, such a confidence interval is based on the estimated standard error. This method generalizes to a hypothesis about the values of several parameters simultaneously, but this is beyond the scope of this introduction.

### 5.2. Hypothesis Testing Using the Likelihood Ratio

An approach that involves the extra effort of re-fitting the data has the advantage of being less approximate than the one that uses a confidence interval based on the SE. This method is the so-called Likelihood Ratio Test.

The basic idea is to compare directly the goodness of fit (as indicated by the minimum value of the extended least squares objective function) obtained between using a model in which the parameter is fixed to the hypothesized value (the *reduced* model) and a model in which the parameter must be estimated (the *full* model).

#### 5.2.1. Definition — Full/Reduced Models

A model is a reduced model of a full model if it is identical to the full model except that one or more parameters of the latter have been fixed to hypothesized values (usually 0). Consider the examples:

E.g. #1. Valid Full/Reduced Pair:

$$\text{Full model: } \tilde{Cl} = \theta_1 + \theta_2 WT$$

$$\text{Reduced model: } \tilde{Cl} = \theta_1$$

E.g. #2. Invalid Full/Reduced Pair:

$$\text{Full model: } \tilde{Cl} = \theta_1 WT$$

$$\text{Reduced model: } \tilde{Cl} = \theta_1$$

In example #1, fixing  $\theta_2$  to 0 produces the reduced model, while in example #2, no parameter of the full model can be fixed to a particular value to yield the "reduced" model. It will always be true that if the models are set up correctly, the number of parameters that must be estimated will be greater in the full model than in the reduced model. Note that this is not so for example #2.

#### 5.2.2. Reduced/Full Models Express the Null/Alternative Hypotheses

The reduced model expresses the *null hypothesis*; the full model expresses an *alternative hypothesis*. In example #1 above, the null hypothesis is "typical value of clearance is

independent of weight", and the alternative is "typical value of clearance depends linearly on weight."

Note an important point here: the alternative hypothesis represents a *particular* alternative, and the likelihood ratio test using it will most sensitively reject the null hypothesis *only when* this particular alternative holds. If the full model were that "the typical value of clearance is inversely proportional to weight" (so that as weight increases, the typical value of clearance decreases, a situation which rarely holds), the likelihood ratio test using the alternative we have stated would not be particularly sensitive to rejecting the null hypothesis, and we might fail to do so. In contrast, we might succeed in rejecting the null hypothesis if we used some other alternative model closer to the truth.

### 5.2.3. The Likelihood Ratio Test

Part of the NONMEM output is the "Minimum Value of the Objective Function" (see Chapter 2). Denote this by  $l$ . If NONMEM's approximate model were the true model, then  $l$  would be minus twice the maximum logarithm of the likelihood of the data (for those readers unfamiliar with likelihoods, and curious as to what they are, we suggest consulting a statistics textbook). Statistical theory tells us that the difference in minus twice the maximum log likelihoods between a full and reduced model can be referenced to a known distribution. Thus, to perform the Likelihood Ratio Test, one proceeds as follows.

Let  $l_f$  be the minimum value of the objective function from the fit to the full model, and let  $l_r$  be the corresponding quantity from the fit to the reduced model. Fit both models separately yielding  $l_f$  and  $l_r$ , and form the statistic,

$$C^2 = l_r - l_f$$

This statistic is approximately distributed chi-square ( $\chi^2$ ) with  $q$  degree of freedom, where  $q$  is the number of parameters whose values are fixed in the reduced model. For an  $\alpha$ -level test, compare  $C^2$  to  $\chi^2_{1-\alpha}(q)$ , the 100(1- $\alpha$ ) percentile of the  $\chi^2$  distribution.

In particular, when exactly one parameter of the full model is fixed in the reduced model, a decrease of 3.84 in the minimum value of the objective function is significant at  $p < .05$ .

If NONMEM's approximate model (linear in the random effects) were the true model, and in addition,  $f$  were linear in the fixed effects, then  $C^2/q$  would be (approximately) distributed according to the  $F$  distribution with  $q$ , and  $n - p$  degrees of freedom ( $F(q, n - p)$ ). Since  $qF(q, n - p)$  is equal to  $\chi^2(q)$  only when  $n$  is "large", and is greater otherwise, it is more conservative to reference  $C^2$  to  $qF(q, n - p)$  in all instances, even when  $f$  is nonlinear.

## 6. Choosing Among Models

An idea related to hypothesis testing is this: when faced with alternative explanations (models) for some data, how does one use the data to determine which model(s) is (are) most plausible? When one of the models is a reduced sub-model of the other, and there is some *a priori* reason to prefer the reduced model to the alternative, then the Likelihood Ratio test can be used to test whether this *a priori* preference must be rejected (at the  $\alpha$  level). However, when one gives the matter some thought, there is usually little *objective* reason to prefer one model over another on *a priori* grounds. For example, although possibly more convenient, a monoexponential model is, if anything, less likely on biological grounds than a biexponential.

Not only may there not be a clear *a priori* probability favoring one contending model over another, but the two models may not form a full and reduced model pair. In such circumstances, one must rely on some goodness-of-fit criterion to distinguish between the models. Consider choosing between just two models (the ideas to be discussed readily generalize to more than two), denoted model  $A$  and model  $B$ . If the number of free parameters in model  $A$  ( $p_A$ ) is the same as that of  $B$  ( $p_B$ ), then here is a reasonable criterion: favor the model with the better fit. Note that there is no  $p$  value associated with this statement; no hypothesis is being tested.

Unfortunately, if  $p_A \neq p_B$  one cannot simply compare  $l_A$  and  $l_B$  and choose the one with the smaller value. The reason is best understood when  $A$  and  $B$  are a full and reduced model pair. The full model will *always* fit the data better (i.e., have a smaller  $l$ ) as it has more free parameters to adjust its shape to the data. While the same is not always true for any pair of non-linear models with different numbers of parameters, it is often true: the model with the greater number of parameters will fit a given data set better than the model with fewer parameters. Yet the larger (more parameters) model may not really be better; it may, in fact, fit an entirely new data set worse than the simpler model if its better fit to the original data was simply because it exploited the flexibility of its extra parameter(s) to better fit some random aspect of that data.

Based on the above intuitive argument, it seems that one should penalize the larger model in some way before comparing the likelihoods. This intuition is formally realized in the Akaike Information Criterion (AIC) which says that one should compute  $AIC = l_A - l_B + 2(p_A - p_B)$ , and choose model  $B$  if  $AIC$  is  $>0$ , and model  $A$  if  $AIC$  is  $<0$ . The second term penalizes model  $A$  if  $p_A > p_B$ , and vice versa. When  $p_A = p_B$ , the  $AIC$  reduces to the comparison of  $l_A$  and  $l_B$  described previously.

## Chapter 6 - Data Sets, \$DATA and \$INPUT Records, and the Data Preprocessor

### 1. What This Chapter is About

This chapter tells how to create data for analysis by NONMEM-PREDPP. It tells how to describe the data using \$DATA and \$INPUT records. The requirements for formatting the data for NONMEM-PREDPP are somewhat more stringent than are the requirements for formatting the data for NM-TRAN. The Data Preprocessor is a component of NM-TRAN which modifies the data so that it becomes formatted appropriately for NONMEM-PREDPP.

### 2. Data Sets for NONMEM

#### 2.1. Data Records

A data set for NONMEM analysis consists of a series of records ("lines" in the terminology of editing programs). Each record must consist of a fixed number of data items and each must have the same format. Figure 6.1 shows how such a data set may be pictured. In data base terminology, this is a "flat" structure.

|           | Data<br>item<br>#1 | Data<br>item<br>#2 | Data<br>item<br>#3 | ... | Data<br>item<br>#n |
|-----------|--------------------|--------------------|--------------------|-----|--------------------|
| Record #1 |                    |                    |                    |     |                    |
| Record #2 |                    |                    |                    |     |                    |
| Record #3 |                    |                    |                    |     |                    |
| .         |                    |                    |                    |     |                    |
| .         |                    |                    |                    |     |                    |

Figure 6.1. A NONMEM input data set. Each data record is a row; each type of data item is in a different column.

NONMEM imposes no limit on the number of records in the data set. It does not (nor does PREDPP or NM-TRAN) sort the data records before processing them, so the data records must already be in the correct sequence.

NM-TRAN may be instructed to omit records. See the DROP and IGNORE options of the \$DATA record, below,

With NONMEM 7.5, PRED may also instruct NONMEM to omit records. See PRED\_IGNORE\_DATA in Chapter 12, Section 6.1.

#### 2.2. Data Items

NONMEM reads records from the data set with a FORTRAN FORMAT specification, and so each data item must occupy a fixed number of character positions. Data items are always numbers. However, if no particular number is appropriate for a given data item on a given record, the data item is called a null data item; it may be given the numerical value 0 or the nonnumerical value ".", or left blank. Zero's were used in the first two lines of the Theophylline example of Chapter 2, which appeared as follows:

```

2      320.      0.      0.
2      0.      .27     1.71

```

The Data Preprocessor allows each value in the data set to occupy only as many character positions as it needs, so long as the data items are separated by blanks (spaces) or commas. Tab characters may also be used as separators if they are stored as explicit characters, e.g., ASCII 011, although this is platform-dependent and should be tested carefully. When there are no commas or tabs, the value "." or 0 *must* be used to hold the place of a null data item. The two lines above could have been entered as follows:

```

2 320. 0. 0.
2, , .27, 1.71

```

(Note the use in the second line of adjacent commas ",", to denote a null data item.)

The contents of the data items must be purely numeric; i.e., character values such as Y, N, M or F may not be recorded. Instead, numeric codes such as 0 or 1 must be used.

With NONMEM VI, the number of data items per data record is given by constant PD in file SIZES. The default value is 20. With NONMEM 7.1, the default value is 50. With NONMEM 7.2, there is no limit on the number of data items per data record. If the value in SIZES is not sufficient, a larger value may be specified on the \$SIZES record.

### 2.3. Clinical Data and Data Conversion

Clinical data often has a "hierarchical" file structure, with (say) two record formats: a patient record, containing fixed information about a patient (ID number, sex, age, prior history of smoking or drug use, etc), followed by one or more visit records, containing doses and physical observations during the course of the study. Visit records may not even contain the same number of items as patient records, nor have the same format. The hierarchy is shown schematically in figure 6.2.

```

Patient record
  Visit record
  Visit record
  ...
Patient record
  Visit record
  Visit record
  ...

```

Figure 6.2. A hierarchical data file. Patient and visit records have different formats.

NONMEM cannot accept such data. For NONMEM, the (fixed) information on the "patient" record must be copied onto every "visit" record, and the "patient" records must be eliminated. This is the user's responsibility and is typically done in a one-time data conversion step using the system editor and/or a specially written computer program. If an individual's data is to be deleted because he did not complete the study or had an adverse outcome, it should be done at this time. In addition, numeric codes should be substituted for alphabetic codes. Clinical data sometimes includes multi-digit, non-consecutive patient identification numbers drawn from some patient identification system. Such patient identification numbers can be used with NONMEM as the identification data item described in Section 6.2. However, it is preferable to append to each patient's data records numbers from the sequence 1, 2, 3, ..., for use as the ID data item. This will make it easier to read a scatterplot which includes ID along one of the axes (e.g., residual vs ID).

When there is a large amount of data, we strongly suggest that a small amount of data (from one or two individuals) be prepared for NONMEM-PREDPP analysis and a run in which only tables and scatterplots are output be made to check that the data is correctly prepared before a great deal of labor is expended on the remainder.

### 3. Data Sets for PREDPP

When PREDPP is used with NONMEM, the data must meet additional requirements. First, PREDPP is concerned with time-ordered events such as dose events, which introduce drug into the system at particular times, and observation events, which report observations taken at particular times. PREDPP insists that these events be recorded on separate records. That is, dosing information cannot be recorded on the same record as an observed value. Second, PREDPP requires that the time of each event be recorded on each data record, and that the physical sequence of the data records be the same as their sequence in time. (E.g., if a dose event immediately precedes an observation event in time, then the dose event record must immediately precede the observation event record.) Again, neither PREDPP nor the Data Preprocessor will physically sort or resequence the data records.

### 4. The \$DATA Record

The \$DATA record describes the characteristics of the external data file to be processed by NONMEM. NONMEM is not a data base management system and does not store a data set between runs; once a file has been prepared for NONMEM, it must be re-read each time it is to be analyzed. The first character string appearing after \$DATA is the name of the file containing the data. Since it is to be used in a FORTRAN OPEN statement, this name may not include embedded special characters such as slashes (/ or \), commas, semi-colons, parentheses, equal signs or spaces unless it is surrounded by single quotes ' or double quotes ". The filename may contain 80 characters. (If a file is to be opened by NONMEM rather than by NM-TRAN, the filename may not contain embedded spaces, and may contain at most 71 characters.) A FORTRAN format specification suitable to read the data may follow the file name; this is optional and can be supplied by the Data Preprocessor. The choice is discussed more fully in Section 10.4 of this chapter.

Certain options may be specified if desired. Among these are:

**RECORDS=n**

This tells the number of records to be read from the data file. If omitted, the records are read to the end-of-file or to a NONMEM FINISH record (Users Guide II). The RECORDS option may be used to limit NONMEM processing to the initial portion of the file and is useful during the early stages of debugging.

**RECORDS=label**

"Label" is a data item label. The data records for the problem will start at the place where the file is positioned before data records are read and include all contiguous data records having the same value for the data item. In particular, the ID label may be used (or alternatively, the option may be coded RECORDS=IR, RECORDS=INDREC, or RECORDS=INDIVIDUALRECORD) to obtain the data for a single individual.

**IR,INDREC,INDIVIDUALRECORD.**

**NOREWIND|REWIND**

With the first problem specification in a control stream, the file is positioned at its

initial point so that the first record in the file is used. The options REWIND and NOREWIND apply only with a \$DATA record in a subsequent problem specification.

REWIND: Reposition the file at the start.

NOREWIND: Leave the file at its current position so that the next record in the file is read. Used when the \$DATA record with the previous problem specification included the RECORDS option so that NM-TRAN did not read to a physical end-of-file. This is the default.

#### LRECL=n

This tells the length of the physical data records. It is required if the operating system associates a fixed physical record length with every disk file *and* considers it a fatal I/O error if a READ command requests more characters than the records contain. If this is true of your operating system, the operating system will issue an error message when you first run NM-TRAN without the LRECL option in the \$DATA record.

#### WIDE

This requests that the NONMEM data set produced by NM-TRAN always contain single-line records, and that these records always include at least one space between data items. Such a data set can be further processed by other programs. (The default is NOWIDE, in which case NM-TRAN limits the records to 80 characters by creating multi-line records and/or eliminating spaces between data items if necessary.) It may not be used if a FORTRAN format specification is present. It also provides an extra character for relative times computed by the Data Preprocessor.

#### NULL=c

This requests that the NONMEM data set produced by NM-TRAN contain the character c in place of null data items. For example, NULL=0 requests that all null data items be replaced by 0. The syntax NULL='c' and NULL="c" is also permitted. The default is NULL=' '. It may not be used if a FORTRAN format specification is present.

#### IGNORE=c

This instructs NM-TRAN to ignore data records having character c in the first character position ("column 1") of the record. This allows the use of "comment" records in the NM-TRAN data set. The syntax IGNORE='c' and IGNORE="c" is also permitted. It may be used even if a FORTRAN format specification is present. The character @ has a special meaning. It signifies that any data record containing an alphabetic character (or special characters @ or #) as its first non-blank character (not just in column 1) should be ignored. Alphabetic characters are the letters A-Z and a-z. Thus, a table file produced by NONMEM in an earlier run can be used as an NM-TRAN data set. Any header lines included in this table can be dropped by specifying IGNORE=@.

When the IGNORE option is omitted, any records containing the character # in column 1 are ignored.

#### IGNORE=(list), ACCEPT=(list)

This form of the IGNORE option allows records to be dropped based on the values of data items. For example,

**IGNORE= (GEN . EQ . 1 , AGE . GT . 60) .**

Records having GEN equal to 1 or AGE greater than 60 are dropped. All others are accepted. The ACCEPT option allows records to be accepted based on the values

of data items. FORTRAN logical operators .EQ., .NE., .GT., .GE., .LT., .LE. may be used, as well as FORTRAN 90 logical operators ==, /=, >, >=, <, <=.

Special operators .NEN. and .EQN. request that character strings be converted to numeric prior to being compared (nm73). See Guide VIII for more information.

LAST20=nn

"nn" is a 2 digit number that specifies the highest 2-digit year that is assumed to be in the 21st. century, i.e., that represents 20nn rather than 19nn. See Section 10.1.5 below.

TRANSLATE

The translate option must be followed by parentheses enclosing a list of one or more translate specifications. For example,

```
$DATA filename TRANSLATE (TIME/24, II/24)
```

Translate specification TIME/24 causes the value of TIME to be divided by 24, whether or not day-time translation occurs (i.e., whether or not relative times are being computed). This has the effect of changing the unit of TIME from hours to days. Similarly, translate specification II/24 causes the value of II (interdose interval) to be divided by 24 whether or not ":" appears in any II value. With NONMEM 7.3, any value may be given for dividing time and II values, and any precision may be requested. See Section 10.1.4 below.

## 5. The \$INPUT Record

This record describes how many data items there are on each data record, the order of the data items, and tells what the labels of the data items are.

### 5.1. Data Item Labels

A data item label is one to four letters (A-Z) or numerals (0-9). With NONMEM 7 a label consists of 1-24 letters (A-Z), numerals (0-9), and the character '\_'. (The length 24 is specified by constant SD in SIZES)

The first character must be a letter. These labels are the ones which will be used in other records (such as \$PK or \$SCATTERPLOT), and will appear in NONMEM's output. The order of the data items on the data records is not important, but must be the same on all data records in the data set. In both the examples of Chapter 2, the ID data items happened to be the first ones in the data records, and the DV data items happened to be the last ones. This order was arbitrary.

### 5.2. Reserved Labels and Synonyms

Certain data item labels are reserved in that they identify data items which are recognized specifically by NONMEM, PREDPP, or NM-TRAN. The data items they label are themselves called NONMEM, PREDPP, or NM-TRAN data items, respectively.

- Reserved NONMEM data item labels are: ID, L2, DV, and MDV. They are discussed in Section 6 of this chapter and in Section 4.2 of Chapter 12. Additional reserved NONMEM data item labels are: MRG\_, RAW\_, and RPT\_. See Guide VIII for a discussion of these items.
- Reserved PREDPP data item labels are: TIME, EVID, AMT, RATE, SS, II, ADDL, CMT, PCMT, CALL, and CONT. They are discussed in Section 7 of this chapter and in Section 2.4 of Chapter 12. With NONMEM 7.2, additional reserved PREDPP data items are the extra EVID labels, XVID1, XVID2, XVID3, XVID4,

and XVID5. See Guide VIII for a discussion of these items.

- Reserved NM-TRAN data item labels are: DATE, DAT1, DAT2, DAT3, and L1. DATE, DAT1, DAT2, and DAT3 are discussed in Section 10.1 of this chapter; L1 is discussed in Section 4.2 of Chapter 12.

If you do not want to use the reserved label, you can supply two labels: the reserved label and a "synonym". Either label can be used in subsequent records, but only the synonym will appear in NONMEM output. For example,

```
$INPUT PNO=ID, CONC=DV, DOSE=AMT, WT, . . . .
```

The first three data items are given the labels PNO, CONC, and DOSE. These labels are synonyms for the NONMEM data items ID and DV and for the PREDPP data item AMT. The last data item is given the label WT and is not a reserved data item; it is an example of fixed effect ("concomitant") data  $x$

When \$PK and \$ERROR records are present, certain labels may not be used at all as data item labels. These are: the labels for the basic and additional PK parameters for the pharmacokinetic model, as listed in Appendices 1 and 2 (e.g., for ADVAN1 and TRANS2: CL, V, S1, S2, F1, F0), and specific labels for the arguments of the PK and ERROR sub-routines: IDEF, IREV, N, GG, IRGG, HH, and G.

### 5.3. Dropping Data Items via DROP

If no format specification is included on the \$INPUT record, then another synonym, DROP, may be used with any data item. DROP may be used as a synonym more than once. It identifies data items to be dropped (i.e. eliminated) from the NM-TRAN data set by the Data Preprocessor while constructing the NONMEM data set. This provides a way to limit the number of data items in the NONMEM data set and to eliminate non-numeric data items.

## 6. NONMEM Data Items

### 6.1. DV Data Item

There must always be a Dependent Variable data item labeled DV. This is a value of an observation. There can be only one DV data item per data record. The position of the DV data item (and the ones described below) is not important. However, its position must be the same on all records.

### 6.2. ID Data Item for Population Data

When the data is from a population, NONMEM expects the Identification data item, labeled ID, and expects the data to be organized into two or more "individual records". An individual record is a group of contiguous data records having the same value for the ID data item and presumably containing data from the same individual. ID data item values need not be consecutive, increasing, unique, nor begin with 1. E.g., 3, 5, 6, 10, 3, etc. is a possible sequence of ID values. Note the two instances of 3 as ID data item values. As long as these two instances are separated by different ID data item values (e.g. 5, 6, 10), they represent different individuals.

### 6.3. MDV data item

If there are records in an input data set which do not contain values of observations, then NONMEM needs to be informed of this fact. This is done using the Missing Dependent Variable data item labeled MDV. The values of MDV are:

0 The DV data item of the data record contains a value of an observation. The record is referred to as an observation record.

1 The DV data item of the data record does *not* contain a value of an observation.

NONMEM 7 limits the number of observation records per individual record to 250. To change this limit, see Users Guide III. With NONMEM 7.3, there is no limit on the number of observation records.

When PREDPP is used, the Data Preprocessor is able to recognize which records contain observed values and which do not, and it can supply the MDV data item if it is not already present in the data set, i.e. if the label MDV does not occur in the \$INPUT record. (When PREDPP is not used, the Data Preprocessor cannot do this.)

## 7. PREDPP Data Items

### 7.1. TIME Data Item

PREDPP will in general need the

Time data item, labeled TIME. With NONMEM 7.4, the value of TIME may be negative. With earlier versions of NONMEM, the value of TIME must be non-negative. Within an individual record, values of TIME may not decrease. (Exceptions exist for reset and reset-dose events; see Section 7.3.) The units are optional (e.g., minutes or hours), but should be consistent with other units used in the problem. The TIME of the first event record may be zero or non-zero. (If non-zero, then PREDPP in effect subtracts this value from all other TIME values within the same individual record, so that PREDPP always works with relative time values.) The Data Preprocessor permits TIME to be expressed as clock time (e.g., 8:30, representing the time, half-past 8 o'clock). Such times are converted by the Data Preprocessor into relative times. Details are given in Section 10.1 below.

### 7.2. AMT, RATE, SS, II: Dose-related Data Items

Doses are described using one or more of these four data items, depending on the kind of dose. A detailed discussion of these data items and of dose records in general is deferred to Section 8 below.

### 7.3. EVID Data Item

When PREDPP is used, all data records are also called event records. Every event record must contain an Event Identification data item identifying the kind of event described by the record, and labeled EVID. The values of EVID and the five kinds of event records are:

0 Observation event. This record contains an observed value (in the DV data item). Dose-related data items such as RATE and AMT must be 0.

1 Dose event. This record describes a dose. The contents of the DV data item are ignored.

2 Other event. This record is used for a variety of purposes. It can be used to obtain a predicted value at a point in time at which no actual observation or dose event took place; it can be used to turn a compartment off or on at a point in time; it can be used to mark a time at which a change in a physiological data item (e.g. weight) occurs (as well as give the new value of the data item). Dose-related data items must be 0. The contents of the DV data item are ignored.

- 3 Reset event. This record is used to reset the kinetic system at some point in time, without actually starting a new individual record: time is set to *whatever* time appears in the event record, the amounts in each compartment are set to zero, prior doses are cancelled, and the on/off status of each compartment is set to its initial status. It is in all other respects identical to an other event type record. It is typically used within an individual record, when the individual had a course of drug treatment, followed by a wash-out period, followed by another course of drug treatment. It should appear prior to the start of the second course.
- 4 Reset-dose event. This record combines EVID types 3 (reset) and 1 (dose). First the system is reset, and then a dose is introduced. It is in all other respects identical to an ordinary dose event type record.

If only dose and observation event records are present in the NM-TRAN data set, and if EVID is not already present in the data set (i.e. EVID does not appear in the INPUT record), then EVID will be supplied automatically by the Data Preprocessor. This is what was done in the examples of Chapter 2. If other or reset type event records are present in the data set, then the \$INPUT record must include the EVID data item, and the data set must include the appropriate values for EVID on *all* the data records.

#### 7.4. CMT and PCMT Data Items

The Compartment data item (CMT) and Prediction Compartment data item (PCMT) are similar. Both contain the number of a compartment in the model. (Compartments and compartment numbers are discussed in Chapter 7 and Appendix 1, as are default compartments. It may help to look at Chapter 7 and Appendix 1 at this time.) If CMT or PCMT is not defined in the data set (i.e., not listed in the \$INPUT record), or has the value 0 on a given event record, the appropriate default compartment is used, except as noted below. This is what was done in the examples of Chapter 2. The meaning of the two data items depends on the particular kind of event record.

- Observation event: CMT specifies the compartment from which the predicted value of the observation is obtained. PCMT is ignored. When CMT specifies the output compartment, it is allowed to have a negative sign (e.g., with the One-compartment model, CMT may be -2). This signals that *after* the prediction is computed the output compartment is to be turned off, i.e. the amount in the compartment is to be set to zero. The amount remains zero until the compartment is subsequently turned on. This is quite useful with urine observations; see Section 9 below.†
- Dose event: CMT specifies the compartment into which the dose is introduced. The compartment is turned on if it was previously off. PCMT specifies the compartment for which a predicted observation is computed. This predicted value is not associated with an observation, but it can be useful because it will appear in tables or scatterplots.
- Other event: A positive value of CMT specifies that the compartment is to be turned on if it is off. A negative value of CMT specifies that the compartment is to be turned off if it is on. (If CMT is 0, no compartment is turned on or off.) PCMT is the same as for dose events.
- Reset event: CMT is ignored. PCMT is the same as for dose events.
- Reset-dose event: CMT and PCMT are the same as for dose events.

---

† This is also permitted with output-type compartments; see Chapter 12, Section 2.8.

### 7.5. CALL Data Item

The Call data item (CALL) is used to force a call to either or both of the PK and ERROR subroutines with the event record when such a call would not normally occur. A call to the PK or ERROR subroutine causes the code specified by the \$PK or \$ERROR records, respectively, to be executed with the event record. This is discussed in Chapters 7 (\$PK) and 8 (\$ERROR.) When not defined in the data set, CALL is assumed to be 0 always. The values are:

- 0 No forced call; PREDPP takes its normal action.
- 1 Force a call to ERROR.
- 2 Force a call to PK.
- 3 Force a call to both PK and ERROR.
- 10 Force a call to ADVAN9. May be combined with other values. E.g., the value 12 means "Force a call to PK and to ADVAN9".

## 8. Describing Doses to PREDPP

Doses are described using one or more of the data items discussed below. A detailed discussion of the actual kinds of doses that PREDPP recognizes follows in Section 8.2, including a precise definition of what is meant by the term "steady-state dose" (Section 8.2.3). A data item that is not needed to describe the kinds of doses used in the study need not be defined in the data set; it will in effect always have the value 0. Only AMT (Dose amount) was used in the examples of Chapter 2, for example. The values of dose-related data items should be 0 for non-dose events and for those dose events to which they are not relevant.

### 8.1. Dose-related Data Items

#### AMT data item

The Amount data item (AMT) gives the amount of a bolus dose or of an infusion of finite duration. This amount should be a positive number.

#### RATE data item

The Rate data item (RATE) gives the rate of an infusion. This rate should be a positive number. (Negative values are discussed in Chapter 12, Section 2.3.)

#### SS data item

The Steady-state data item (SS) can take four values.

- 0 This record does not describe a steady-state dose.
- 1 This record describes a steady-state dose. If this is not the first event record for the individual, then the system is first reset as if by a reset event record (except that the on/off status of the compartments is unchanged from what it was prior to the event record and the time on the event record must not be less than the time on the previous event record). The compartment amounts are then computed using steady-state kinetic formulas.
- 2 This record describes a steady-state dose. No reset of the kinetic system occurs. Compartment amounts are computed using steady-state kinetic formulas and are then added to the amounts already present at the event time. The use of SS=2 will be discussed further in Section 8.2.7, below.
- 3 This record describes a steady-state dose. It is exactly like a steady-state dose with SS data item = 1, except that existing compartment amounts and derivatives are

retained and used as initial estimates. The computed steady-state levels replace these compartment amounts and derivatives. This value of SS may be specified only with SS6 and SS9 (the General Nonlinear Models).

## II data item

The Interdose Interval data item labeled II gives the time between implied doses (see Section 8.2.3 and Chapter 12, Section 2.4). For a steady-state infusion, it should be 0. For other steady-state doses, it should be a positive number whose units are the same as the TIME data item.

## 8.2. Different Kinds of Doses

Any of the doses described here may be introduced into any compartment of the model except the output compartment. Examples are given below that are fragments of data records, identifying the data items of interest and showing their contents on the dose record. The units of various data items are presumed to be appropriate for some actual data.

### 8.2.1. Instantaneous Bolus Doses

All the examples in Chapter 2 involve instantaneous bolus doses, which we shall refer to simply as bolus doses. (There is also such a thing as a "zero-order bolus dose", see Chapter 12, Section 2.3.) These are dose records having  $AMT > 0$ ,  $RATE = 0$  and  $SS = 0$ . (Recall that if  $RATE$  and  $SS$  are not defined on the \$INPUT record, they are effectively 0.) If the \$PK record computes a bioavailability fraction parameter for the compartment into which the dose is introduced, then the contents of the  $AMT$  data item is multiplied by the current value of this parameter before the amount is added to the compartment. A bolus dose enters the dose compartment immediately; the predicted (scaled) amount in the dose compartment, if displayed in a table or scatterplot, will include the dose.

Example:

```

TIME AMT
4 . 10 .

```

This is a dose of 10 to be added to the default dose compartment at time 4.

A bolus dose to the central compartment might be interpreted as an IV bolus dose; to the depot it might be an oral tablet; to a peripheral compartment it might be an intra-muscular injection.

### 8.2.2. Infusions

Infusions are doses having  $AMT > 0$  and  $RATE > 0$ . The duration of the infusion is computed by PREDPP by dividing the  $AMT$  by the  $RATE$ . As with bolus doses,  $AMT$  is first multiplied by the bioavailability parameter for the dose compartment, if any. There is no explicit "end of infusion" record. Drug amounts in the system cannot be affected in a detectable way at the time an infusion begins by any drug introduced by the infusion; the predicted (scaled) amount in the dose compartment, if displayed in a table or scatterplot, will not include the dose. Infusions may overlap. That is, subsequent dose records may start new infusions before old ones have finished. It is not an error if an infusion's duration is so large as to extend beyond the time of the last event record for the individual; the remainder of the drug is ignored. A reset or reset-dose event, or a steady-state dose event with  $SS = 1$ , will also terminate any infusions in progress.

Example:

```

TIME AMT RATE
4 . 10 . 2 .

```

The duration of the infusion will be computed as  $10./2.$ , and so the infusion, which begins at time 4, will terminate at time 9. ( $=4.+5.$ ).

An infusion to the central compartment might be interpreted as an IV infusion; to the depot it might be a sustained release tablet; to a peripheral compartment it might be an implant or skin patch which releases drug at a known constant rate. It is possible for NONMEM-PREDPP to estimate the input rate of a constant-rate drug delivery system (see Chapter 12, Section 2.3).

### 8.2.3. Steady-State Doses

A steady-state dose can be regarded as the last one of a series of doses just like the one specified in the dose event record, which have been given at a regular interdose interval since time  $-\infty$ , and such that they have led to a steady-state periodic pattern of drug amounts in the system by the time this last dose has been administered. The doses of similar kind that precede it are called implied doses, because their existence is not described by separate dose records in the data set, but rather is implied by the description of the single steady-state dose. By stipulating that a dose is a steady-state dose, the user instructs PREDPP to update the drug amounts in the system at the time the dose is given by using steady-state kinetic formulas. This can take less computational time than using separate dose records to describe the implied doses and using transient kinetic formulas to advance the system from one dose time to the next (as well as requiring fewer dose records). The formulas used to compute the steady-state amounts at the time the steady-state dose is introduced use the values of the basic and additional pharmacokinetic parameters in effect at this time; any values in effect at earlier times are ignored. Moreover, when using a steady-state dose, the user is assuming that under reasonable values of the pharmacokinetic parameters, steady-state is in fact effectively reached by the time the dose is introduced; PREDPP does not check this assumption. The output compartment must be off when a steady state dose record is encountered in the data set.

(The Model Event Time (MTIME) feature described in Chapter 12 does not apply during steady-state computations. The Absorption lag (ALAG) feature described in Chapter 12 does apply. See Guide VI, Chapter V, Notes 3 and 4.)

### 8.2.4. Steady-State with Multiple Bolus Doses

These are dose events having  $AMT>0$ ,  $RATE=0$ ,  $SS=1$ , and  $II>0$ . The II data item (interdose interval) tells how many time units apart the doses were given. As with non-steady-state bolus doses, AMT is first multiplied by the bioavailability parameter for the dose compartment, if any.

Figure 6.3 shows how drug levels vary with time. The concentration-time profiles over each interdose interval look the same since, in principle, there is an *infinite* number of implied doses.




Figure 6.3. Steady-state with multiple bolus doses. The dose is given at time  $t$ . The interdose interval is  $I$ . Steady-state levels can be predicted between times  $t$  and  $t+I$ .

Example:

```

TIME AMT SS II
8 10. 1 12
    
```

Here, an infinite number of bolus doses, 10 units each, are assumed to have been given 12 hours apart, with the last of these given at time 8AM, at which time steady-state is reached. The fact that TIME is 8 has no effect on the computed amounts, but is important in relation to the records that follow. Steady-state levels can be predicted at any time between the time on the dose record (8) and the end of the succeeding interdose interval (12) (provided there are no further doses introduced *during* this interval). If another (steady-state or *non-steady-state*) dose just like the steady-state one is introduced at time 20, then predictions in the interdose interval following this time will also be steady-state levels.

### 8.2.5. Steady-State with Multiple Infusions

These are dose events having  $AMT > 0$ ,  $RATE > 0$ ,  $SS = 1$ , and  $II > 0$ . Each such event describes the last of a series of regularly spaced infusions, all of the same amount and rate. As with a non-steady-state infusion, the duration of each infusion is given by  $AMT/RATE$ . The bioavailability fraction applies to each infusion of the series.

Figure 6.4 shows how drug levels vary with time. The concentration-time profiles over each interdose interval look the same since, in principle, there is an *infinite* number of implied doses.




Figure 6.4. Steady-state with multiple infusions. The dose is given at time  $t$ . The interdose interval is  $I$ . Steady-state levels can be predicted between times  $t$  and  $t+I$ .

Example:

```

TIME AMT RATE SS II
16 10. 5. 1 6
    
```

Here, infusions, each 10 units and of duration 2 ( $=10/5$ ), are assumed to have been given 6 hours apart, with the last of these started at time 4PM, at which time steady-state is reached. The daily dose times were 4 AM, 10 AM, 4 PM, and 10 PM. Again, the value of TIME has no effect on the computed amounts but is important in relation to the records that follow. Steady-state levels can be predicted between times 16 (4 PM) and 22 (10 PM) (provided there are no further doses introduced *during* this interval).

### 8.2.6. Steady-State with Constant Infusion

These are dose events having  $AMT=0$ ,  $RATE>0$ ,  $SS=1$ , and  $II=0$ . Such an event consists of infusion with the stated rate, starting at time  $-\infty$ , and *ending* at the time on the dose event record. Bioavailability fractions do not apply to these doses.

Figure 6.5 shows how drug levels vary with time.




Figure 6.5. Steady-state with constant infusion. Steady-state level can be predicted only at time  $t$ .

Example:

```

TIME RATE SS
16 2. 1
    
```

Here, a steady-state infusion at rate 2 is specified as ending at 4 PM. A steady-state level can be predicted only at this time.

### 8.2.7. Multiple Steady-State Doses

Doses with SS=2 are exactly like doses with SS=1. Doses with SS=2 are similar to non-steady-state doses in that compartment amounts are computed in two steps. First, compartment amounts are computed at the time on the dose event record based on the prior dosing history of the system. Second, steady-state amounts are computed from the dosing information on the record and added to the existing compartment amounts. Thus, if the kinetics are linear, this results in an application of the superposition principle wherein the amounts in the system resulting from doses described by dose event records preceding the time of the steady-state dose are superposed on the (steady-state) amounts in the system resulting from the steady-state dose and the implied doses.

As with any steady-state dose, the steady-state amounts are obtained using the values of the pharmacokinetic parameters computed from the information on the steady-state dose record. In the case that SS=2, though, if these values differ from those computed from the information on the previous dose record(s), then the compartment amounts at the time in the steady-state dose record are not truly steady-state amounts, and the computed steady-state levels are not valid predictions. PREDPP will not detect this error. We emphasize that superposition is only valid with linear kinetic systems; all the kinetic systems (ADVANS) discussed in this text are linear.

SS=2 records can be used to achieve the specification of complicated dosing regimens. For example, Figure 6.6 shows how drug levels vary with time when two different doses are alternated. In this illustration, two steady-state doses are specified, each with interdose interval  $I$  and with time between the two steady-state doses equal to  $I/2$ . Even more complex patterns are possible.




Figure 6.6. Multiple steady-state doses. Two separate steady-state doses are given. As pictured, they are each bolus doses, but they do not have to be. The first dose event record is at time  $t$ . The second dose event record is at time  $t+I/2$ . They each have interdose interval  $I$ . Steady-state levels can be predicted between times  $t+I/2$  and  $t+I$ .

Example:

| TIME | AMT | SS | II |
|------|-----|----|----|
| 8    | 10. | 1  | 24 |
| 20   | 15. | 2  | 24 |

This describes the following dosing regimen: a dose of 10 units every morning at 8 AM and a dose of 15 units every evening at 8 PM (20 hours is 12 hours past 8). Note that steady-state is not truly established until *after* the second dose record; any observation

events interposed between the two dose records will reflect only the first steady-state dosage (i.e., 10 units every 8 AM). Another way to achieve the same steady-state is by the following:

Example:

| TIME | AMT | SS | II |
|------|-----|----|----|
| 20   | 10. | 1  | 12 |
| 20   | 5.  | 2  | 24 |

This describes doses of 10 units every 12 hours, the last of which is given at 8 PM (i.e. at 8 AM and 8 PM daily), plus additional doses of 5 units at 8 PM daily. In both examples, the steady-state levels can be predicted from time 20 hours to time 32 hours.

### 8.2.8. Combining Non-Steady-State Doses with Steady-State Doses

Non-steady-state dose records may appear before, among, or after steady-state dose records. Such a dose record may occur *before* a steady-state dose record to reflect a transient dose given among a series of regular doses leading to steady-state, but which is not a part of this series. E.g., a patient who has been maintained at steady-state takes an extra dose by mistake shortly before his appointment. A non-steady-state dose record may occur *after* a steady-state dose record in order to continue the pattern of doses beyond the steady-state dose. Ordinarily, steady-state levels can only be predicted between  $t_1$ , the time on the steady-state dose record, and  $t_2$ , the sum of  $t_1$  and the interdose interval. If it is not only necessary to compute a steady-state prediction between  $t_1$  and  $t_2$ , but also after  $t_2$ , then there must also occur one or more non-steady-state dose records at  $t_2$ ,  $t_2 + I$ , etc. with doses just like the steady-state dose. (The "additional doses" data item, labeled ADDL, is especially useful for this purpose; see Chapter 12, Section 2.4.)

Example:

| TIME | AMT | SS | II |
|------|-----|----|----|
| 8    | 10. | 1  | 24 |
| 20   | 15. | 2  | 24 |
| 32   | 10. | 0  | 0  |
| 44   | 15. | 0  | 0  |

Here, the last two records continue the steady-state pattern of the first two. Steady-state levels may be predicted between times 20 and 56.

Similarly, a steady-state constant infusion may be extended with a non-steady-state infusion. In the example below, steady-state levels can be predicted from time 0 to time 100.

| TIME | RATE | AMT   | SS |
|------|------|-------|----|
| 0    | 30   | 0.    | 1  |
| 0    | 30   | 3000. | 0  |

## 9. The Output Compartment: Urine Collections and Observations

In this section we show how urine collections and observations of urine concentration,  $C_u$ , can be described. The first-time reader may prefer to return to this section after reading Section 4.3.3 of Chapter 7. As an example, consider the one-compartment model with first-order absorption (ADVAN2). The sequence of events is:

6:00 AM A bolus dose of 100 is given.

8:00 AM A urine collection is started.

9:30 AM  $C_u$  and urine volume (UVOL) are measured and a new collection is started.

11:45 AM  $C_p$ ,  $C_u$ , and urine volume are measured.

The \$INPUT record is:

```
$INPUT ID TIME EVID UVOL DV CMT AMT
```

The data records appear as follows:

| ID | TIME  | EVID | UVOL | DV   | CMT | AMT |
|----|-------|------|------|------|-----|-----|
| 1  | 6.00  | 1    | 0    | 0    | 1   | 100 |
| 1  | 8.00  | 2    | 0    | 0    | 3   | 0   |
| 1  | 9.50  | 0    | 75   | .058 | -3  | 0   |
| 1  | 9.50  | 2    | 0    | 0    | 3   | 0   |
| 1  | 11.75 | 0    | 100  | .067 | -3  | 0   |
| 1  | 11.75 | 0    | 100  | 5.80 | 2   | 0   |

Notice that urine collections start with an other type event record (EVID=2) whose CMT contains the number of the output compartment, the effect of which is to turn this compartment on at 8AM, i.e. to begin accounting for the amount of drug appearing in this compartment from 8AM. Because other type event records are included, the EVID data item *must* be present in the data. The CMT data item must be present in all event records since it is needed to refer to the output compartment in at least one record. Care must be taken to use correct values for the CMT data item; default values used when this data item is not present are not relevant in this case. The DV value on the observation record at 9:30 is the measured  $C_u$ . Because the value of CMT is negative, the output compartment is also turned off at 9:30. Since the collection is to continue, the compartment must be explicitly turned on again (the fourth record). Note that UVOL is recorded on both observation records at time 11:45. Strictly speaking, it need only be recorded on the second ( $C_u$  observation). This point is discussed further in Chapter 7, Section 4.3.3. See also Chapter 12, Section 7, for a modification to this data file for output-type compartments.

## 10. The Data Preprocessor

This section discusses in more detail the ways in which the Data Preprocessor can modify data, and discusses when a format specification should be included in the \$DATA record.

### 10.1. Day-time Translation

#### 10.1.1. TIME Data Item

Sometimes the data contains clock times hh:mm (e.g., the time 1:30 PM is recorded as 13:30). With NONMEM 7.3, clock times may also include the seconds hh:mm:ss. These times must be converted to decimal-valued times (e.g., 13.5). The Data Preprocessor can perform this task when it is processing unformatted data. Within an individual record, the Data Preprocessor replaces the TIME value in the first data record with 0, and then replaces subsequent records' TIME values with the relative time (i.e., the number of hours elapsed since the first record). (The TIME value is also reset to 0 on a reset (EVID=3) or reset-dose (EVID=4) record.) Here is an example of relative time calculation:

| Contents of original file: |       | Contents of new file: |       |
|----------------------------|-------|-----------------------|-------|
| ID                         | TIME  | ID                    | TIME  |
| 1                          | 9:15  | 1                     | 0.00  |
| 1                          | 9:30  | 1                     | 0.25  |
| 1                          | 10    | 1                     | 0.75  |
| 1                          | 14:40 | 1                     | 5.42  |
| 1                          | 32.5  | 1                     | 23.25 |
| 2                          | 8     | 2                     | 0.00  |
| 2                          | 8.0   | 2                     | 0.00  |
| 2                          | 44:50 | 2                     | 36.83 |
| 2                          | 58    | 2                     | 50.00 |

The presence of the colon ":" in the TIME data item of at least one record of the data causes the Data Preprocessor to convert all the TIME values to elapsed values. Elapsed times are also called relative times. Note that recorded data (lines 5, 8, and 9 of the original file) spanned more than one day. The user had to add 24 to the TIME values on each day subsequent to the first to communicate the correct times to the Data Preprocessor.

### 10.1.2. DATE Data Item

Here is another way the above data could have been recorded, using a data item called DATE whose value is 1 for the first day, 2 for the second day, and so on. This allows TIME values to be recorded more naturally using values in the range 0-24.

| Contents of original file: |      |       | Contents of new file: |      |       |
|----------------------------|------|-------|-----------------------|------|-------|
| ID                         | DATE | TIME  | ID                    | DATE | TIME  |
| 1                          | 1    | 9:15  | 1                     | 1    | 0.00  |
| 1                          | 1    | 9:30  | 1                     | 1    | 0.25  |
| 1                          | 1    | 10    | 1                     | 1    | 0.75  |
| 1                          | 1    | 14:40 | 1                     | 1    | 5.42  |
| 1                          | 2    | 8.5   | 1                     | 2    | 23.25 |
| 2                          | 1    | 8     | 2                     | 1    | 0.00  |
| 2                          | 1    | 8.0   | 2                     | 1    | 0.00  |
| 2                          | 2    | 20:50 | 2                     | 2    | 36.83 |
| 2                          | 3    | 10    | 2                     | 3    | 50.00 |

The DATE data item is of significance only to the Data Preprocessor; NONMEM-PREDPP will not make use of it. Even if there are no ":" characters among the TIME values, the existence of a DATE data item will cause the Data Preprocessor to replace TIME values by relative times.

### 10.1.3. Calendar Dates

The Date data item (DATE) can also be used to record calendar dates in month-day-year format. Any alphabetic character (e.g., / or -) can be used to separate the components. Here is a third way the same example could be recorded:

| Contents of original file: |           |       | Contents of new file: |       |
|----------------------------|-----------|-------|-----------------------|-------|
| ID                         | DATE=DROP | TIME  | ID                    | TIME  |
| 1                          | 10-1-86   | 9:15  | 1                     | 0.00  |
| 1                          | 10-1-86   | 9:30  | 1                     | 0.25  |
| 1                          | 10-1-86   | 10    | 1                     | 0.75  |
| 1                          | 10-1-86   | 14:40 | 1                     | 5.42  |
| 1                          | 10-2-86   | 8.5   | 1                     | 23.25 |
| 2                          | 10-12     | 8     | 2                     | 0.00  |
| 2                          | 10-12     | 8.0   | 2                     | 0.00  |
| 2                          | 10-13     | 20:50 | 2                     | 36.83 |
| 2                          | 10-14     | 10    | 2                     | 50.00 |

This example illustrates two features. First, when calendar dates are used, the DATE item should be specified as "DATE=DROP", so that the data item is omitted from the new data file (see Section 5.3). Otherwise, the alphabetic characters which separate the components will cause read errors when NONMEM reads the data. Second, the year value is optional; only month and date were actually needed. (Within a single individual record, however, either all dates should specify a year, or none should.)

Data labels DAT1, DAT2, and DAT3 are also recognized by the Data Preprocessor and can be used instead of DATE. The label given to the Date data item describes its format:

```
DATE  month day year
DAT1  day month year
DAT2  year month day
DAT3  year day month
```

If only one of the three components is present, it is assumed to be the day<sup>†</sup>. If only two components are present, they are assumed to be month and day (with DATE and DAT2) or day and month (with DAT1 and DAT3). The year may be omitted or given as 1, 2, 3, or 4 digits.

#### 10.1.4. Converting Hours to Days and More General Conversions

The units of the relative TIME values resulting from the Data Preprocessor's day-time translation are hours. If the correct units for relative time should be days, then the TRANSLATE option of the \$DATA record may be used to request that hours to be converted to days. For example,

```
$DATA filename TRANSLATE(TIME/24)
or
$DATA filename TRANSLATE(TIME/24.000)
```

With the former, values of TIME have two significant digits, e.g., xxxx.xx. With the latter, they have three significant digits, e.g., xxxx.xxx.

With NONMEM 7.3, more general conversions are possible. Any value may be given for dividing time and II values, and any precision may be requested. Examples are:

```
$DATA filename TRANSLATE(TIME/1.0000)
or
$DATA filename TRANSLATE(TIME/1/4)
```

for formatting times in FDATA with 4 digits to the right of the decimal. Another example is

<sup>†</sup> In this case *only*, the Date data item may be zero or negative. Day -1 means one day prior to day 0.

**\$DATA filename TRANSLATE(II/0.01/6)**  
 which divides II values by 0.01, and writes 6 digits to the right of the decimal for the II data item. See Guide VIII for more information.

### 10.1.5. The Year 2000 - LAST20

The user may supply 4 digit years starting (e.g.) "19" and "20", and such dates are processed correctly. (Three digit years "000"- "999" are permitted, but would represent exactly those years, and should not normally be used.) If the year is omitted, it is assumed to be a non-leap year. A problem arises when the year supplied, but has only 1 or 2 digits. Such years are assumed by default to be in the 1900's. If this is not a correct assumption, two errors may be made by the Data Preprocessor when computing relative times. First, 1900 was not a leap year, but 2000 is a leap year. Hence, if consecutive dates in a data file are 02-28-00 and 03-01-00 (signifying February 28 and March 1, 2000), an elapsed time of 24 hours, rather than 48 hours, is computed. Second, if consecutive dates have years 99 and 00, the computed elapsed time is negative and an error message is generated.

With NONMEM V and later versions there is a constant LAST20. The value of LAST20 is a 2 digit number nn that specifies the highest 2-digit year that is assumed to be in the 21st. century, i.e., to represent 20nn rather than 19nn. For example, with LAST20=50, then 1 and 2 digit years are interpreted as follows:

00-50 represents 2000-2050  
 51-99 represents 1951-1999

The elapsed time between 02-28-00 and 03-01-00 is calculated to be 48 hours, and the elapsed time calculated between the years 99 (1999) and 00 (2000) is positive.

There are two ways that a value for LAST20 can be specified.

First, when NM-TRAN is installed, a value is given to constant LAST20 in TrGlobal.f90 (in the resource directory): `DATA LAST20`

The default value of this constant in the distribution medium is 50. Please ask your system support department if they modified the LAST20 constant when NM-TRAN was installed.

Regardless of what value was assigned to the LAST20 constant in TrGlobal.f90, there is an option LAST20 of the \$DATA record that may be used to specify the value of the constant for the current run. For example:

**\$DATA filename LAST20=50**

This insures that all 1 and 2 digit years are interpreted as above (2000-2050; 1951-1999).

### 10.1.6. Leap Year Warning - LYWARN

There may be two circumstances such that 1 or 2 digit years are recorded as 00, 01, ... (equivalently, 0, 1, ...). First, these may represent the years 2000, 2001, etc. Or, they may represent years 0, 1, etc., of a study. Suppose the latter is the case, and that none of the years of the study was a leap year. Then if LAST20 is set to a value greater than -1, the year 0 is assumed incorrectly to be the leap year 2000, and elapsed times may be computed incorrectly. The Data Preprocessor issues a warning message under the following circumstances:

- 1) The year is recorded as "00" or "0",
- 2) The value of LAST20 is greater than -1 by default (so that the year is understood to be 2000), and

- 3) The LAST20 option of the \$DATA record was not used to modify LAST20 for this run.

The warning message is as follows:

```
(DATA WARNING 3) RECORD      3, DATA ITEM 3: 01-01-00
THE YEAR IS ASSUMED TO BE 2000 (A LEAP YEAR). IF THIS IS INCORRECT, USE
$DATA'S LAST20 OPTION TO OVERRIDE THE DEFAULT VALUE OF LAST20 IN NMTRAN'S
ABLOCK, OR CHANGE THE DEFAULT: 50
```

Suppose these warning messages are appropriate, that is, year "00" (or "0") should not be a leap year. The LAST20 option of the \$DATA record may be used to specify that such years are in the 1900's for the current data set:

```
$DATA filename LAST20=-1
```

A constant LYWARN is defined in NM-TRAN's ABLOCK module. The default value of LYWARN is 1 ("data warning message 3 enabled"). If the value of LYWARN is set to 0 ("data warning message 3 disabled") and NM-TRAN is recompiled, then the warning message is suppressed for all runs.

## 10.2. Interdose Interval (II) Conversion

When the input data is unformatted and PREDPP is being used, the Interdose Interval (II) data item is checked for values containing a colon (:). Any such value is assumed to signal a clock time hh:mm. The minutes portion is converted to a decimal number containing as many decimal places as digits in the original. E.g., the value ":30" is replaced by ".50". This conversion is performed whether or not day-time translation is also being done.

## 10.3. Data Items Generated by the Data Preprocessor

When the data is from a single individual, the Data Preprocessor will almost always generate an ID data item<sup>‡</sup>. It does this whether or not PREDPP is used. This is done because, when the data is from a single individual, the ID data item must take on very special non-constant values for NONMEM. The generated ID data item is given the label ".ID." (i.e., ID surrounded by dots). If this data item is to be shown in any NONMEM output (e.g., in a table), it must be referred to on subsequent NM-TRAN records by this label.

When PREDPP is used, the Data Preprocessor will always generate the required EVID data item if it is not already listed on the \$INPUT record. (This was discussed in Section 7.3 above.)

When PREDPP is used, the Data Preprocessor will always generate the MDV (Missing Dependent Variable) data item if it is not already listed on the \$INPUT record.

These data items are generated by the Data Preprocessor whether or not a format specification was coded on the \$INPUT record. They are appended to the end of each data record.

## 10.4. When Must a Format Specification be Included or Omitted?

When coding the \$DATA record, you will need to decide whether to include a FORTRAN format specification describing the data file or to omit it and let the Data Preprocessor construct it. Here are some guidelines in making this decision.

<sup>‡</sup> Section 4.2 of Chapter 12 discusses the L1 data item, which is used to prevent NM-TRAN from generating an Identification data item for individual data.

A format specification is *required* when:

Some data values are left blank on some data records, without having the value 0 or . (or a pair of commas) to hold the place of the missing value.

Some data values are adjacent on some data records; they are not separated by a space or a comma.

The data records span multiple physical records; that is, the character / is needed in the format specification. (The Data Preprocessor may generate such a format specification for the NONMEM data set; we are speaking here of the NM-TRAN data set.) The NOOPEN option of \$DATA is used.

A format specification should *not* be present when:

The \$INPUT record includes DROP as a data item label or synonym.

Day-time translation is desired.

II conversion is desired.

Commas are used to separate the data items.

The data values are not lined up into columns with uniform width, so that no format specification can be written to describe the file.

The IGNORE/ACCEPT option of \$DATA is used to drop records from the data set.

Many data files do not fall in either category. A format specification is optional for such files.

NM-TRAN performs more checks on the data file when there is no format specification. Some features of NM-TRAN are the same with or without a format specification.

Comment records may be used.

NM-TRAN appends EVID, MDV, .ID., as needed.

NM-TRAN checks for blank records, and the BLANKOK option of \$DATA may be used.

NM-TRAN gives a warning for unusual characters in the data file.

NM-TRAN counts records and supplies the count in FCON.

### **10.5. Skipping Data Items**

It is always possible to omit (skip) data items that are not of interest for a given NONMEM run. When a format specification is coded, two things must be done: first, replace the data item's specification by an "X" specification (e.g., replace F8.0 by 8X) and second, delete the data item's label from the \$INPUT record. When no format specification is coded, all that need be done is to replace the data item's label in the \$INPUT record by DROP (or include DROP as a synonym).

## Chapter 7 - \$SUBROUTINE Record and \$PK Record

### 1. What This Chapter is About

This chapter tells how to write a \$SUBROUTINE record and how to write a simple \$PK record for both individual and population data. This chapter is meant to be read in parallel with Chapters 3 and 4.

### 2. The \$SUBROUTINE Record

The \$SUBROUTINE record describes which pharmacokinetic model is to be used. Recall that NONMEM calls a subroutine named PRED to compute the predicted value. The user must choose to use his own PRED subroutine or to use the PREDPP package. In this text it is assumed that the PREDPP package is chosen.

#### 2.1. Choosing an ADVAN Subroutine: Standard Pharmacokinetic Models

The PREDPP Library includes subroutines which are pre-preprogrammed, each for a specific pharmacokinetic model. They are:

ADVAN1 (One Compartment Linear Model)

ADVAN2 (One Compartment Linear Model with First Order Absorption)

ADVAN3 (Two Compartment Linear Model)

ADVAN4 (Two Compartment Linear Model with First Order Absorption)

ADVAN10 (One Compartment Model with Michaelis-Menten Elimination)

ADVAN11 (Three Compartment Linear Model)

ADVAN12 (Three Compartment Linear Model with First Order Absorption)

PREDPP calls only one subroutine, ADVAN; the different names above are external names distinguishing different instances of the ADVAN routine in the PREDPP Library. The name 'ADVAN' is used because the routine advances (i.e. updates the state of) the kinetic system from one point in time to the next. There are additional ADVAN routines in the Library which implement more general types of pharmacokinetic models; see Chapter 12, Section 2.2. Each of the ADVAN's can be used for either individual or population data. The (external) name of the ADVAN to be used is coded on the \$SUBROUTINE record; this also implies that PREDPP is to be used. As an example, the following record specifies the One Compartment Linear Model:

```
$SUBROUTINE ADVAN1
```

The ADVAN's are described in Appendix 1. They share certain features.

1. The compartments are numbered. These numbers are used in two places. First, they are used in the CMT and PCMT data items to describe specific compartments. Second, the compartment number  $n$  is part of the name of PK parameters such as compartment scale ( $S_n$ ), as discussed below.
2. Each model has a default observation compartment, which for each of the above ADVAN's happens to be the central compartment. If an event record contains an observation (i.e. is an observation event record), the prediction associated with that record will be the scaled drug amount in this compartment, unless the CMT data item on the record specifies differently. The prediction associated with a non-observational event record will again be the scaled drug amount in this compartment, unless the PCMT data item on the record specifies differently.
3. Each model has a default dose compartment. Unless specified differently by the CMT data item, it is understood that a dose is input into this compartment. With

ADVAN1, ADVAN3, and ADVAN10, this is the central compartment. With ADVAN2 and ADVAN4, a drug depot compartment is part of the model and is the default dose compartment. In these cases, if a dose is to go directly into the central compartment, its compartment number (2) must be present in the CMT data item of the dose record. Note that it is never *required* that there be doses into the depot compartment. In a study involving mixed oral and IV doses, for example, some patients may receive only IV doses. All dose event records for such patients will have the value 2 in the CMT data item.

4. Each model has an output compartment. The amount of drug in this compartment is the accumulated amount of drug eliminated from the system and typically represents the amount of drug which accumulates in the urine. This compartment is special. It may not receive a dose. It is initially off, and it remains off (so that the amount therein remains zero) until it is explicitly turned on by an other type event record which has the output compartment's number in the CMT data item. It is computed by "mass balance", as follows. Between any two points in time, it increases by an amount equal to the amount of drug in the other compartments at the first point in time, plus the amount added via doses between the two time points, less the amount remaining in the other compartments at the second point in time. (This difference is multiplied by an output fraction (F0) parameter, if F0 is computed by the PK routine.) The output compartment can be turned off (i.e. its amount reset to zero). If the compartment is interpreted as a urine compartment, this is equivalent to "emptying" the compartment. This is done by putting the *negative* of its number in the CMT data item of an other type or observation event record.†

On event records, the output compartment is referred to by the compartment number given in Appendix 1. A PK parameter which refers to the output compartment may use either this number or 0 (zero). Thus, F0 and F2 both denote the output fraction for ADVAN1; similarly, S0 and S4 both denote the scale for ADVAN4's output compartment. SC denotes the scale for any ADVAN's central compartment.

5. Each model has a set of basic (required) pharmacokinetic (PK) parameters, which are the microconstants used to compute the amounts of drug via the kinetic equations for the model. Each one also has a set of additional (optional) PK parameters, including compartment scales (Sn), bioavailability fractions (Fn), and output fraction (F0). Compartment scales are typically used to convert amounts to concentrations, but they also can be used for other purposes. Bioavailability fractions multiply dose amounts. The output fraction is described above.
6. Each model's basic and additional pharmacokinetic parameters must be computed for it by a subroutine named PK. The error model must be described by a subroutine named ERROR. \$PK and \$ERROR abbreviated code provide an easy way to specify the essential computations that must occur in these subroutines.

## 2.2. Choosing a TRANS Subroutine: Alternative Parameterizations

As discussed in Chapter 3, we may prefer to use pharmacokinetic parameters in our PK routine other than the microconstants used by PREDPP. Appendix 2 shows several commonly-used parameterizations. The PREDPP package includes a family of subroutines called TRANS routines which are pre-programmed to translate (reparameterize) from these commonly used parameterizations to the ones expected by PREDPP. Appendix 2

† This is also permitted with output-type compartments; see Chapter 12, Section 2.8.

also gives the TRANS routine for each alternative parameterization. As with ADVAN, TRANS is the name of the routine. The names given in Appendix 2 are instances of external subroutine names used in the PREDPP Library. The first member of the family, TRANS1, simply translates a set of microconstants into these same microconstants and must be included in the NONMEM load module in lieu of the others when the \$PK abbreviated code computes the microconstants.

The user must describe on the \$SUBROUTINE record which TRANS routine is to be used. For example, the following record requests the One Compartment Linear Model parameterized (in the PK routine) in terms of clearance and volume.

```
$SUBROUTINE ADVAN1, TRANS2
```

When a TRANS other than TRANS1 is used, only the alternative parameters listed in column 1 need be assigned values in the \$PK abbreviated code. In this example, these are CL, V, and KA.

Note that TRANS1 is the default. That is, if no TRANS routine is listed on the \$SUBROUTINE record, it is assumed that TRANS1 is intended. This is the case in the examples of Chapter 2. Alternative parameterizations using TRANS1 are discussed later in this chapter in Section 4.2.

### 3. \$PK Abbreviated Code

\$PK abbreviated code consists of a block of \$PK statements, one per line, which look much like FORTRAN statements. In fact, they are a subset of FORTRAN: simple assignment statements, certain kinds of conditional (IF) statements, and certain kinds of CALL, WRITE, PRINT, RETURN, OPEN, CLOSE, REWIND statements. The \$PK abbreviated code must be preceded by a record containing the characters "\$PK". This record and the abbreviated code constitute the \$PK record.

\$PK statements must include assignment statements giving a value to every basic PK parameter for the given ADVAN and TRANS combination, as listed in Appendix 1 (when TRANS1 is used) or column 1 of Appendix 2 (when a different TRANS is used). They may also include assignment statements giving values to one or more of the additional PK parameters.

#### 3.1. Syntax

We assume the readers of this document are familiar with writing FORTRAN assignment and conditional statements. If not, the examples in this and the following chapter should give adequate guidance. FORTRAN statement numbers are not used, and the statements may start in any column. As with all NM-TRAN records, blank lines are permitted, and all text following a semi-colon (;) is ignored and may be used for comments. FORTRAN 95 continuation lines are permitted. An ampersand (&) is used at the end of a line to be continued.

The statements are built using the following: elements of the THETA array (e.g., THETA(1)); constants; names of input data items appearing on the \$INPUT record; names of previously-assigned variables; FORTRAN library functions SQRT, LOG, LOG10, EXP, SIN, COS, ABS, TAN, ASIN, ACOS, ATAN, INT, MIN, MAX, and MOD; NONMEM functions GAMLN and PHI<sup>†</sup>; arithmetic operators +, -, \*, /, \*\*; and arithmetical and logical expressions using all of the above. In addition, statements may include representations for random variables such as ETA(1) and EPS(3). Input data

<sup>†</sup> PHI gives the value of the cumulative distribution function. GAMLN gives an accurate evaluation of the logarithm of the gamma function.

items have the values appearing on the current event record, and thus these values may change from one event record to the next. A user-defined variable name follows the usual FORTRAN rules (1-6 letters and digits, starting with a letter) and may not be subscripted. It is defined ("declared") by being assigned a value (i.e., by appearing to the left of = in an assignment statement).

Nested parentheses and nested IF statements are allowed. A pair of parentheses enclosing a subscript may be nested within another pair of parentheses. All subscripts must be constants (e.g. THETA(1)). The statements are evaluated sequentially, in the order in which they appear.

All variables, constants, and expressions are evaluated using floating-point (not integer) arithmetic. Single or double precision function names and constants may be used interchangeably.

### 3.2. When are \$PK Statements Evaluated?

\$PK statements are normally evaluated with every event record for both population and individual data. This enables the amounts in the compartments to be updated from event time to event time using current values of the data items. This may be more frequent than is necessary. In the theophylline example of Chapter 2, no data item is used in the \$PK statements. In the phenobarbital example, the data item used, WT, is constant within any individual's data. In these cases, it is sufficient, and it can save noticeable amounts of run time, to evaluate the \$PK statements once per individual record. PREDPP can be instructed that the set of event records with which the \$PK statements are evaluated are to be limited in some way (see Chapter 12, Section 2.7). The CALL data item can be used to force the statements to be evaluated with any event records.

Certain advanced forms of dosing (additional and lagged doses; see Chapter 12, Sections 2.4 and 2.5) introduce doses at times which do not necessarily coincide with any event record. PREDPP does not normally evaluate the \$PK statements at such times, but can be instructed to do so (See Chapter 12, Section 2.6). Model event time parameters can be used to instruct PREDPP to evaluate the \$PK statements at specified times (See Chapter 12, Section 2.7).

### 3.3. Time Varying PK parameters

The state of the kinetic system at a given event time is obtained using PK parameter values computed with the data items on the event record. Using these parameter values the system is advanced to the event time from the last event time. Population models sometimes use data items which change value within individual records and thus give rise to PK parameters whose values change within individual records. In Chapter 4, Section 3.1.6, it is pointed out that it is desirable for the value of such a data item on the event record to be that value holding at the midpoint of the interval between the current event time and the last previous event time, since the system is advanced over this interval using the PK parameters determined with this value.

If the data item changes too rapidly for this value to fairly represent the data item over the entire time period, it is possible to subdivide the interval into smaller intervals. Event records with EVID=2 (other type event records) can be introduced for this purpose. For example, between two consecutive event records  $r_j$  and  $r_{j+1}$ , with event times  $t_j$  and  $t_{j+1}$ , one might introduce two new other type event records  $R_1$  and  $R_2$ , with event times  $T_1$  and  $T_2$ , into the data set. The value of the data item in  $R_1$  will be used to compute the PK parameters used to advance the system over the interval  $t_j$  to  $T_1$  and should be the value of the data item holding at the midpoint of this interval. Similarly, the value of the data

item in  $R_2$  will be used to compute the PK parameters used to advance the system over the interval  $T_1$  to  $T_2$  and should be the value of the data item holding at the midpoint of this interval, and so on.

#### 4. \$PK Statements for Individual Data

##### 4.1. Basic and Additional Parameters

With individual data, the parameters to be estimated are (usually) the individual's PK parameters, and therefore, elements of  $\theta$  should be associated with these PK parameters. (NONMEM estimates the elements of the  $\theta$  vector.) By an individual's PK parameters, we mean here the basic PK parameters and, possibly, some additional PK parameters (e.g. a bioavailability fraction, or volume of distribution when the latter is not a basic PK parameter). To illustrate, in the theophylline example of Chapter 1 there occur these \$PK statements

```
$PK
KA=THETA (1)
K=THETA (2)
```

The parameters KA and K are the basic PK parameters for ADVAN2 and TRANS1 (the default TRANS routine). They are used to compute the amounts in the compartments. Typically, however, the observations are concentrations. A scale parameter is used to convert the amount into a concentration. Thus, in the theophylline example we see two additional \$PK statements:

```
V=THETA (3)
S2=V
```

Here, V is a user-defined variable standing for the volume of distribution of the central compartment. It is neither a basic nor additional parameter. The parameter S2 is the scale parameter for the central compartment; upon dividing the amount in that compartment by S2, the concentration results. (An observation is usually predicted by an amount for a compartment divided by that compartment's scale parameter). In fact, these two statements could be replaced by the single statement

```
S2=THETA (3)
```

However, it may be helpful to the user to distinguish in his code between the calculation of the central volume itself and the calculation of the scale parameter.

There is no particular need for certain elements of  $\theta$  to be associated with certain PK parameters. In the above example, the roles of  $\theta_1$  and  $\theta_2$  could have been reversed. NONMEM's  $\theta$  vector may contain more or fewer elements than there are PK parameters, depending on how these parameters are modeled.

PK parameters must be explicitly modeled, usually in terms of parameters to be estimated and user-defined data items; the user communicates this model with the \$PK statements. If a certain parameter's value is known a priori (say, S2 has the known value 500), there are several ways the value can be incorporated into the \$PK statements. The following examples show how it can be done via a constant, via a fixed element of  $\theta$ , and via a (differently-named) data item:

1. **S2=500**
2. **\$THETA .6 9. (500 FIXED)**  
**\$PK**  
**S2=THETA (3)**

Here, rather than be estimated,  $\theta_3$  is constrained to the value 500. This is discussed in Chapter 9.

```

3.  $INPUT ... VOL ...
    $PK
    S2=VOL

```

Here, VOL is assumed to have the value 500 on the data records. When the data is from a population, this third technique allows a unique value of VOL to be supplied for each individual.

#### 4.2. Alternative Parameterizations using \$PK Statements

It is possible to use an alternative parameterization while still using TRANS1. The reparameterization is performed within the \$PK statements by explicitly computing the microconstants from the alternative parameters. Such "reparameterization" statements are given in column 2 of Appendix 2. They must follow the assignment statements that give the alternative parameters their values, as in the phenobarbital example of Chapter 2.

The advantage of using \$PK statements to reparameterize, rather than using a TRANS subroutine, is that the NONMEM-PREDPP load module will then always consist of the same set of subroutines for a given choice of ADVAN, which simplifies the job of creating and running it. It will also run slightly faster. We assume in this document that this approach is taken.

Other parameterizations are possible besides the ones in Appendix 2. For example, with ADVAN1 and TRANS1, one might code:

```

CL=THETA (1)
K=THETA (2)
V=CL/K
S1=V

```

The ability to express a large variety of modeling possibilities with NONMEM-PREDPP provides great freedom and flexibility, but as always with flexible modeling capability, certain pitfalls arise. Suppose, for example, that with a one compartment system the compartment amount, rather than the concentration is observed. With ADVAN1 and TRANS1 the statements

```

CL=THETA (1)
V=THETA (2)
K=CL/V

```

will lead to difficulty because only the ratio of  $\theta_1$  to  $\theta_2$  affects the amount in the compartment, and therefore, the data do not allow  $\theta_1$  and  $\theta_2$  to be separately estimated. The statements should read:

```

K=THETA (1)

```

It is important to remember that only those elements of  $\theta$  which affect the predictions of observations will be estimated by NONMEM. Here is some problematic code using ADVAN1 with TRANS1:

```

K=THETA (1)
V=THETA (2)
CL=THETA (3)
S1=V

```

Once again, NONMEM will be unable to produce separate estimates of all elements of  $\theta$ . The kinetics of a simple one compartment system cannot be determined by three independent parameters. With TRANS1, PREDPP itself does not "know" about the relationship  $K=CL/V$  which defines a dependency among the parameters. Indeed, the parameters CL and V are both regarded as user-defined variables. The value of  $\theta_3$  has no effect on the prediction. Were it not for the fact that S1 is set equal to V, the value of  $\theta_2$  would have no

effect on the prediction either. With TRANS2 this code is also incorrect for essentially the same reason. Here, K is regarded as a user-defined variable, and the relationship  $CL=K*V$  is not "known" to PREDPP. (PREDPP does know that  $CL/V$  is the rate constant of elimination, but it does not recognize the variable K as denoting this rate constant, and  $\theta_1$  has no effect on the prediction.)

### 4.3. Scale Parameters

Scale parameters are mentioned in Section 2.1. Predicted compartment amounts are divided by them and are thus converted to predicted concentrations. They are only needed for those compartments whose concentrations are directly observed. With ADVAN3, for example, the peripheral compartment's scale S2 does not need to be computed explicitly if there are no observation events giving measured values of concentrations in the peripheral compartment. Predicted values for this compartment may still be plotted against time, for example, but these values need not be scaled drug amounts; the (unscaled) amount alone is sufficient to show the shape of the curve. (The various volume parameters shown in Appendix 2 must be modeled when they are used as basic parameters, but they need not be assigned as values to compartment scale parameters.) Any scale parameter which is not modeled by \$PK statements is assumed to be 1 (i.e., predicted values are always amounts).

#### 4.3.1. Scaling by a Known Constant

In Chapter 3, Section 2.2.1, the units of V were changed from kiloliters to liters using the model:

$$S = V/1000$$

This can be coded in a \$PK statement similar to the way it appears here, except that the compartment number must be specified:

```
S1=V/1000
```

Basic PK parameters may also be rescaled in this manner.

#### 4.3.2. Scaling by a Parameter: Conditional Statements and Indicator Variables

In Chapter 3, Section 2.2.2, the following model appeared:

$$S = \begin{cases} V, & \text{if assay is 1} \\ hV, & \text{if assay is 2} \end{cases}$$

There are two ways this can be coded in \$PK statements. The *assay* data item can be tested directly, or an indicator variable can be used. An indicator variable is a variable whose value is 0 or 1. It may be identified with an input data item, or it may be a user-defined variable in the \$PK statements. For example, suppose variable ASY is to be used as an indicator variable. If some input data item is given value 1 when assay 1 was used and value 0 when assay 2 was used, then this data item could simply be named ASY on the \$INPUT record. Suppose, however, that the assay number itself (1 or 2) was recorded in the data and that we have named the data item ANUM on the \$INPUT record. We must compute the user-defined variable ASY for use as an indicator variable. There are two ways this can be done: using a logical IF and using a block IF.

1. **ASY=1**

```
IF (ANUM.EQ.2) ASY=0
```

Here, ASY is "provisionally" given the value 1. The value is changed to 0 if the data indicates assay 2.

```

2.  IF (ANUM.EQ.1) THEN
      ASY=1
    ELSE
      ASY=0
    ENDIF

```

The choice between these forms of IF is purely a matter of style. Now let us assume that the compartment to be scaled is compartment 2, and that  $h$  is to be identified with  $\theta_5$ . The parameter S2 can now be coded unconditionally:

```
S2=ASY*V+(1-ASY)*THETA(5)*V
```

Alternatively, ANUM can be tested and ASY avoided altogether:

```

1.  S2=V
      IF (ANUM.EQ.2) S2=THETA(5)*V
2.  IF (ANUM.EQ.1) THEN
      S2=V
    ELSE
      S2=THETA(5)*V
    ENDIF

```

#### 4.3.3. Scaling by a Data Item

If observations of urine concentration  $C_u$  are included in the data (see e.g. Chapter 6, Section 9), it is necessary to provide urine volume as a scale for the output compartment. Presumably, this volume varies between urine observations and is recorded in the data records. Suppose this data item is called UVOL in the \$INPUT record. (The name given to the data item has no special significance; any name could be chosen.) An additional \$PK statement is necessary:

```
S0=UVOL
```

UVOL need be recorded on only those observation events to which it applies, although it does no harm to record it on other event records. For example, it may well happen that both plasma and urine responses are measured at the same time, so that there are two observation event records with the same value of TIME, one for each compartment observed at that time. As described in Section 3.2 above, \$PK statements are normally evaluated with every event record. Consider, for example, the sample data below. Assume that the Central compartment is compartment 2 and the output compartment is compartment 3. (Note the use of -3 to signify that compartment 3 is to be turned off after the observation time. The compartment will remain off until the time another urine collection begins, as indicated with an other type record; see Chapter 6, Section 7.4). Either 1. or 2. will produce the correct value of S0:

- Record UVOL on the event record to which it applies. The order of the records does not matter.

| TIME | UVOL | DV   | CMT |
|------|------|------|-----|
| 10.  | 0    | 5.80 | 2   |
| 10.  | 100  | .067 | -3  |

- Record UVOL on all event records having the same value of TIME. The order of the records does not matter.

| TIME | UVOL | DV   | CMT |
|------|------|------|-----|
| 10.  | 100  | 5.80 | 2   |
| 10.  | 100  | .067 | -3  |

The following will not produce the correct value of S0 unless PREDPP is instructed to evaluate the \$PK statements only once for each distinct value of TIME:

| TIME | UVOL | DV   | CMT |
|------|------|------|-----|
| 10.  | 100  | 5.80 | 2   |
| 10.  | 0    | .067 | -3  |

#### 4.4. Bioavailability Fraction Parameters

PK parameters of the form  $F_n$ , where  $n$  is the number of a compartment into which a dose may be introduced, are bioavailability fractions. If a dose record specifies a dose for compartment  $n$ , the dose amount given on the event record is multiplied by the value of  $F_n$  computed from the \$PK statements evaluated with this record, and this product is the dose amount introduced into the system. For example,  $F_1$  multiplies the amount of dose which is to be added to compartment 1. Any  $F_n$  which is not computed by \$PK statements is assumed to be 1 (i.e., the dose is 100% available).

As an example, suppose two different preparations of the same drug are administered, and it is assumed that they differ only in their bioavailability. The indicator variable (or data item) PREP has value 1 for the first preparation and 0 for the second. The ratio of the bioavailability of the second preparation to that of the first preparation is identified with  $\theta_6$ . Usually, the method of drug administration permits this ratio to be estimated, but not the separate bioavailabilities. Without loss of generality, the bioavailability of the first preparation can be taken to be 1. Assuming the drug enters compartment 1 of the model, there are three ways this can be coded:

1. `F1=PREP+(1-PREP)*THETA(6)`
2. `F1=1`  
`IF (PREP.EQ.0) F1=THETA(6)`
3. `IF (PREP.EQ.0) THEN`  
`F1=THETA(6)`  
`ELSE`  
`F1=1`  
`ENDIF`

Again, the choice is a matter of style.

Once a dose is introduced into the dose compartment, it begins to distribute into the other compartments. Whether or not the original dose was 100% available, it is assumed that none of the dose appearing in the dose compartment, and in other compartments after the dose is introduced, is further reduced due to bioavailability effects. PREDPP cannot model "bioavailability effects" between compartments.

#### 4.5. Output Fraction

The Output Fraction parameter,  $F_0$ , is an optional additional PK parameter of every model. As discussed in Section 2 above, every model contains an output compartment. If this compartment has been turned on prior to the advance from time  $t_{j-1}$  to time  $t_j$ , then the amount of drug lost from the system during this interval via elimination is multiplied by  $F_0$  and added to the prior contents of the output compartment. If the \$PK statements do not include an assignment statement giving a value to  $F_0$ , it is taken to be 1 (i.e., 100% of the drug excreted goes to the output compartment). In model (4.7), an example of the use of  $F_0$  is given. Assuming that the variables CLREN (renal clearance) and CL (total clearance) have been calculated with earlier \$PK statements, the statement

```
F0=CLREN/CL
```

can be used to compute F0.

## 5. \$PK Statements for Population Data

With population data, the structural models for the PK parameters tend to be more complicated than with individual data. In addition, the influence of interindividual random effects needs to be described. These will involve differences in the \$PK statements, but the same \$SUBROUTINE record and the same ADVAN and TRANS subroutines are used, and the same general requirements and examples of the earlier sections of this chapter still mostly apply. In this section, the models of Chapter 4 are implemented via \$PK statements. Many of these models could be implemented in a variety of ways; an experienced programmer may prefer to code them differently.

With population data, we must distinguish between the typical value of a PK parameter in the population and the value of that parameter for a given individual, the individual's value. The typical value is computed by a structural model involving only fixed effects. We have chosen to denote it with the use of a tilde: e.g.  $\bar{Cl}$ . The individual's value is computed by a model including random interindividual effects (represented by random variables) and is denoted without a tilde: e.g.,  $Cl$ . There is no tilde character in the FOR-TRAN character set, and with NM-TRAN we do not need to distinguish typical and individual values. However, for purposes of clarity, in all the examples which follow we will include the letters TV (Typical Value) at the start of those variable names which we think of as having a tilde (e.g., TVCL). This is a matter of style.

### 5.1. Structural Part of Parameter Models

In models such as (4.3), the subscript  $i$  indicates that the model applies to the  $i^{th}$  individual. As noted in Chapter 4, the subscript is not needed and, indeed, is not used in \$PK statements.

#### 5.1.1. Linear Models

Models (4.4), (4.5a), (4.5b) and (4.6) can be coded as they appear. Assuming that WT, AGE, and SECR are input data items or have been calculated with earlier \$PK statements, the code is:

```
TVCLM=THETA (1) *WT
RF=WT* (1.66-.011*AGE) /SECR
TVCLR=THETA (4) *RF
TVCL=TVCLM+TVCLR
```

#### 5.1.2. Multiplicative Models

Model (4.4.1) can be coded as follows:

```
TVLCLM=THETA (1) +THETA (2) *LOG (WT)
TVCLM=EXP (TVLCLM)
```

Model (4.4.2) can also be coded as it appears:

```
TVCLM=THETA (1) *WT**THETA (2)
```

#### 5.1.3. Saturation Models

Model (4.4.3) presents a problem. Subscripted variables that can appear in \$PK statements are few; naturally, they include THETA and (as seen below) ETA. The variable CPSS cannot be subscripted, and a variable name such as CPSS2 (rather than CPSS(2)) must be used for  $C_{pss_2}$ . The model can be coded exactly as it appears:

```
TVCLM=WT*(THETA(1)-THETA(2)*CPSS2/(THETA(3)+CPSS2))
```

#### 5.1.4. Models with Indicator Variables

When dealing with typical values, indicator variables (0/1 variables) can be used interchangeably with conditional (IF) statements, as we have already seen. Model (4.4.4) can be coded in a variety of ways, two of which are:

1. 

```
TVCLM=(THETA(1)-THETA(2)*HF)*WT
```
2. 

```
IF (HF.EQ.0) THEN
TVCLM=THETA(1)*WT
ELSE
TVCLM=(THETA(1)-THETA(2))*WT
ENDIF
```

#### 5.2. Population Random Effect Models

Random variables  $\eta$  are used in the models for interindividual errors. (With population models, random variables  $\varepsilon$  are used in the models for intraindividual errors; see Chapter 4, Section 2.) In \$PK statements they are denoted by ETA(1), ETA(2), etc. Even if there is only once such variable it must still be subscripted. It is the presence of one or more such variables that indicates to NM-TRAN that the data is from a population. Just as there is no particular need for certain  $\theta$  elements to be identified with certain PK parameters, there is no particular need for certain  $\theta$  elements to be associated with certain  $\eta$  variables, and any association need not be one-to-one. The following models are both valid:

1. 

```
CL=THETA(1)+ETA(1)
V=THETA(2)+ETA(2)
```
2. 

```
CL=THETA(1)+ETA(2)
V=THETA(2)+ETA(1)
```

However, it will be easier to keep things straight if the first model is used.

Here are three different ways of coding a model for an individual's value of clearance:

1. 

```
TVCL=THETA(1)
CL=TVCL+ETA(1)
```
2. 

```
CL=THETA(1)
CL=CL+ETA(1)
```
3. 

```
CL=THETA(1)+ETA(1)
```

We prefer the first way because it clearly distinguishes the model for the typical value from the model for the individual's value. With any of the three ways for coding the model the typical value of the parameter can be computed as follows: The  $\eta$  variables are set to 0, and the parameter is computed. Any variable whose value depends on  $\eta$  variables is called a random variable.

Random variables are called true-value variables in the first edition of this guide. This is because, in principle, a random variable can assume an individual's true value under the model. Such a variable is in contrast to a variable which assumes only a typical value for the population.

An individual's true value is never actually known, although an estimate of it can be obtained. See Chapter 12, Sections 4.11-4.13.

### 5.3. Models for Interindividual Errors

Here we show how to express the most commonly used models for interindividual errors with \$PK statements. In addition, all the error models described in Chapter 8 may also be used in \$PK statements.

#### 5.3.1. Additive/Multiplicative Models

This is the error model of (4.9):

```
K=TVK+ETA (1)
```

This is the error model of (4.10):

```
K=TVK* (1+ETA (1) )
```

This model can also be coded as:

```
K=TVK+TVK*ETA (1)
```

Here, the variable TVK has been "multiplied through". The choice is a matter of style.

#### 5.3.2. Other Models

The model (4.11) may be coded as written.

```
CLM=TVCLM+ (1-ICU) *ETA (1) +ICU*ETA (2)
```

It may also be coded with an IF statement.

```
IF (ICU.EQ.0) THEN  
CLM=TVCLM+ETA (1)  
ELSE  
CLM=TVCLM+ETA (2)  
ENDIF
```

The choice is a matter of style.

Note that, under the parameterizations given in Appendices 1 and 2, CLM is neither a basic nor an additional PK parameter, yet its model involves an  $\eta$  variable. This is legitimate: any variable can be defined in terms of an  $\eta$  variable. However, just as with  $\theta$ 's, the values assigned to the  $\eta$  variables must somehow affect the predictions of observations. Otherwise, the variance of some  $\eta$  variable cannot be estimated, and consequently, none of the variances of these variables can be estimated. Presumably, within the \$PK statements, CLM is used to compute CL, and (either within the \$PK statements or within the TRANS routine) CL is used to compute K.

### 5.4. Restrictions on Random Variables

This section discusses the use of random variables in some depth and may be skipped by the casual reader. The remarks here apply to all random variables: both the ETA variables of this chapter and the ERR/EPS variables of Chapter 8.

In general, ETA variables can be used like any other variables.

Any variable whose value is affected by an ETA variable is a random variable, whether the ETA variable occurs explicitly in the defining expression for the random variable or whether another random variable occurs in this expression. For example, consider the following:

```
TVCLM=THETA (2) *WT  
CLM=TVCLM+ETA (2)  
RF=WT* (1.66-.011*AGE) /SECR  
TVCLR=THETA (4) *RF  
CLR=TVCLR+ETA (1)  
CL=CLM+CLR
```

CL is a random variable, because it is computed from random variables. It depends on both  $\eta_1$  and  $\eta_2$ .

Random variables may be changed and may be assigned conditionally, subject to the following restrictions.

A random variable may not appear anywhere within a nested if structure.

A random variable defined in the \$PK block may not be redefined in the \$ERROR block.

As an example of the first restriction, suppose in the model (4.11) it is also believed that, for ICU patients, age affects CLM. The following code expresses the model, but is not permitted:

```

IF (ICU.EQ.1) THEN
  IF (AGE.GE.50) THEN
    TVCLM=THETA (1)
  ELSE
    TVCLM=THETA (2)
  ENDIF
  CLM=TVCLM+ETA (1)
ELSE
  TVCLM=THETA (3)
  CLM=TVCLM+ETA (2)
ENDIF

```

An alternate code follows, in which the calculation of TVCLM (which involves a nested IF) precedes the calculation of CLM (which does not require a nested IF). This code is permitted.

```

IF (ICU.EQ.1) THEN
  IF (AGE.GT.50) THEN
    TVCL=THETA (1)
  ELSE
    TVCL=THETA (2)
  ENDIF
ELSE
  TVCL=THETA (3)
ENDIF
IF (ICU.EQ.1) THEN
  CL=TVCL+ETA (1)
ELSE
  CL=TVCL+ETA (2)
ENDIF

```

Indentations are used in the above code for clarity, but have no affect on NM-TRAN's processing of the abbreviated code.

## Chapter 8 - \$ERROR Record

### 1. What This Chapter is About

This chapter tells how to write a simple \$ERROR record for PREDPP. This chapter is meant to be read in parallel with Chapters 3 and 4.

### 2. \$ERROR Abbreviated Code

\$ERROR abbreviated code consists of a block of \$ERROR statements, one per line. The \$ERROR abbreviated code must be preceded by a record containing the characters "\$ERROR". This record and the abbreviated code constitute the \$ERROR record.

\$ERROR statements describe the error model for PREDPP. These statements are very similar for individual data and for population data. In fact, by making use of variables called ERR variables, the \$ERROR statements are identical for both kinds of data.

#### 2.1. Syntax

The syntax of a \$ERROR record is very similar to that of a \$PK record. Certain differences will be mentioned here.

There must be an assignment statement giving a value to a special (reserved) variable Y. Y is a random variable representing the random variable y (the modeled observation). Y is usually defined in terms of a special (reserved) variable F, which represents the prediction for Y. When the data are from a population, F is a random variable. With individual data, ETA variables may be used in the definition of Y. With population data, EPS variables may be used in the definition of Y. There are also special random variables called ERR variables. The variable ERR(I) is the same as ETA(I) or EPS(I), depending on whether the data are individual or population, respectively. For the purpose of giving a general discussion, applying equally to both individual and population data, ERR will be used in all the examples in this chapter. (It is also useful to use ERR in \$ERROR statements as a practical matter. Sometimes the same data is analyzed from both the population and the individual point of view. By using ERR variables, changes to the NM-TRAN input file are minimized.) An ERR variable (as with ETA and EPS variables) must always include a subscript (e.g., ERR(1)), even when there is only one such variable in the model.

Variables computed within \$PK statements may be used in \$ERROR statements, but not vice versa.

#### 2.2. When are \$ERROR Statements Evaluated?

\$ERROR statements are normally evaluated with every event record. This may be more frequent than is necessary. PREDPP can be instructed that the set of event records with which the \$ERROR statements are evaluated is to be limited to only observation events, once per individual record, or once per problem. Such limitation does not apply to the Simulation Step (Chapter 12, Section 4.8). With the additive (3.4) and constant coefficient of variation (3.5) error models, and with the exponential error model, NM-TRAN instructs PREDPP to evaluate the \$ERROR statements only once per problem. Again, the CALL data item can be used to force evaluation of the \$ERROR statements with any event records.

### 3. Error Models

The following sections show how the error models of Chapter 3 are expressed using \$ERROR statements.

#### 3.1. The Additive Error Model

This is the error model (3.4):

$$Y=F+ERR(1)$$

Both examples in Chapter 2 use this error model.

#### 3.2. The Constant Coefficient of Variation and Exponential Models

This is the CCV error model (3.5):

$$Y=F*(1+ERR(1))$$

This error model can also be coded as:

$$Y=F+F*ERR(1)$$

Here, the variable F has been "multiplied through". The choice is a matter of style.

This is the exponential error model (3.5a):

$$Y=F*EXP(ERR(1))$$

When the \$ERROR statements consist solely of one of these statements (in any of the forms), the output from PREDPP will include the message:

**ERROR IN LOG Y IS MODELED**

This is done because during data analysis NONMEM cannot distinguish between the CCV error model  $y = \tilde{f} + \tilde{f}\varepsilon$  and the exponential error model  $y = \tilde{f}\exp(\varepsilon)$ , for which  $\log(y) = \log(\tilde{f}) + \varepsilon$ †. By using the latter model and modelling the error in  $\log(y)$  rather than in  $y$ , NM-TRAN enables PREDPP to achieve an improvement in run time.

#### 3.3. Combined Additive and CCV Error Model

This is the error model (3.6):

$$Y=F+F*ERR(1)+ERR(2)$$

#### 3.4. The Power Model

This is the error model (3.7):

$$Y=F+F**P*ERR(1)$$

The variable P must be assigned a value before its use above. P is typically identified with an element of  $\theta$  so that it can be estimated in the fitting process. Let us assume that  $\theta_4$  is chosen for this purpose. Then an alternative coding is:

$$Y=F+F**THETA(4)*ERR(1)$$

#### 3.5. Two Different Types of Measurements

We have already seen how an indicator variable, e.g., ASY, can be used in \$PK statements for a variety of purposes. The same technique is used in \$ERROR statements. Consider model (3.8) where the variable ASY has the value 1 or 0, corresponding to assay 1 or assay 2. ASY is a data record item. Then the error model (3.8) is coded:

$$Y=F+ASY*ERR(1)+(1-ASY)*ERR(2)$$

This model can also be coded in several ways, the choice of which is a matter of style.

```
1)  IF (ASY.EQ.1) THEN
      Y=F+ERR(1)
```

† During Simulation, NONMEM does distinguish between the CCV and exponential error models.

```

ELSE
Y=F+ERR (2)
ENDIF
2) IF (ASY.EQ.1) Y=F+ERR (1)
IF (ASY.NE.1) Y=F+ERR (2)
3) Y=F+ERR (2)
IF (ASY.EQ.1) Y=F+ERR (1)

```

### 3.6. Two Different Types of Observations

In Chapter 3, Section 3.6, an example is given in which there are two kinds of observations, plasma ( $C$ ) and urine ( $C_u$ ). With PREDPP, measurements from different compartments of the model are recorded in the DV data item of different observation event records. The CMT data item identifies the compartment from which the prediction associated with the event record is to be obtained. When the \$ERROR statements are evaluated for a given event record, the variable F contains the prediction from the compartment specified for that event record. All that need be done is to select the correct error model, depending on the compartment. Suppose, for example, that ADVAN2 is used, so that the central compartment is compartment 2 and the output (urine) compartment is compartment 3. Then the error model (3.10) can be coded:

```

TYP=0
IF (CMT.EQ.2) TYP=1
Y=F+TYP*ERR (1) + (1-TYP) *ERR (2)

```

This model can also be coded in several ways, one of which is shown here:

```

IF (CMT.EQ.2) THEN
Y=F+ERR (1)
ELSE
Y=F+ERR (2)
ENDIF

```

### 3.7. More than One Indicator Variable

In Chapter 3, Section 3.7, an example is given in which there are three kinds of observations. Suppose that there are two data items, ASY1 and ASY2. ASY1 is 1 if assay 1 is used and 0 otherwise. ASY2 is 1 if assay 2 is used and 0 otherwise. This is the error model (3.11):

```

Y=F+ASY1*ERR (1) +ASY2*ERR (2) + (1-ASY1) * (1-ASY2) *ERR (3)

```

This model can also be coded in several ways, one of which is shown here:

```

Y=F+ERR (3)
IF (ASY1.EQ.1) Y=F+ERR (1)
IF (ASY2.EQ.1) Y=F+ERR (2)

```

## Chapter 9 - Additional NM-TRAN Records

### 1. What This Chapter is About

This chapter tells how to give initial estimates to NONMEM's parameters (\$THETA, \$OMEGA, \$SIGMA records); how to tell NONMEM what tasks to perform (\$ESTIMATION, \$COVARIANCE records); and how to tell NONMEM what additional output to produce (\$TABLE, \$SCATTERPLOT records).

### 2. Providing Initial Estimates For $\theta$ : The \$THETA Record

This record provides an initial estimate (and, optionally, provides lower and upper bounds) for every element of NONMEM's  $\theta$  vector.

#### 2.1. Providing Initial Estimates For Elements Of $\theta$

The \$THETA record contains a list of values, separated by spaces or commas, which are the initial estimates for the  $\theta$ 's used in the \$PK and \$ERROR statements. The position of a value in the list corresponds to its position (subscript) in the  $\theta$  vector. For example, consider the following statement:

```
$THETA 1.7 .102 29.
```

This says that the initial estimate for  $\theta_1$  is 1.7, the initial estimate for  $\theta_2$  is .102, and the initial estimate for  $\theta_3$  is 29. Some users of NONMEM prefer to code each value on a separate line so that they can include comments to themselves describing the significance of the  $\theta$ 's. The above record could have been coded as follows:

```
$THETA 1.7 ; RATE CONSTANT OF ABSORPTION  
.102 ; RATE CONSTANT OF ELIMINATION  
19. ; VOLUME OF DISTRIBUTION
```

This is a matter of style.

#### 2.2. Providing Constraints for Elements of $\theta$

When NONMEM is told to estimate the parameters (Section 4.1, the Estimation Step, below), it varies the elements of  $\theta$  to find values which cause the model to fit the observations best. The values on the \$THETA record are the initial estimates of  $\theta$  for this search. When only an initial estimate is provided, NONMEM is free to choose any positive or negative value for that element of  $\theta$ . We then say that the  $\theta$  element is *unconstrained*, which means that its lower bound (lower limit) is  $-\infty$  and its upper bound (upper limit) is  $+\infty$ . When finite bounds are desired, the initial estimate and its bounds must be enclosed in parentheses and specified in the order (lower, initial, upper). When the upper bound needn't be finite, the initial estimate and its lower bound are enclosed in parentheses and specified in the order (lower, initial). Note that when no estimation is performed, upper and lower bounds have no effect.

In the theophylline example of Chapter 2, for example, negative  $\theta$  values are physiologically impossible. Each  $\theta$  element was given a lower bound of 0, which constrained it to be non-negative:

```
$THETA (0, 1.7) (0, .102) (0, 29.)
```

It is possible to mix constrained and unconstrained  $\theta$ s; this was done in Chapter 2, figure 2.12:

```
$THETA (0, .0027) (0, .70) .0018 .5
```

An upper bound of  $+\infty$  may be stated explicitly using the value 1000000 or the word INFINITY. Similarly, a lower bound of  $-\infty$  may be stated explicitly as -1000000 or -INFINITY.

### 2.3. Fixing Elements of $\theta$

When estimation is performed, it is sometimes desirable to hold one or more elements of  $\theta$  to a constant value. One example is when a full model is reduced to a simpler model, as discussed in Chapter 5, Section 2.1; usually this is done by holding some  $\theta$  element to 0. In fact, the value 0 may not be used as an initial estimate for an element of  $\theta$  unless this element is fixed to this value. A  $\theta$  element is held constant by inserting the word FIXED *after* the initial estimate. For example, the following statement allows  $\theta_1$  and  $\theta_3$  to vary, but holds  $\theta_2$  to the value .102:

```
$THETA 1.7 .102 FIXED 29.
```

Parentheses may be used to make the statement easier to read:

```
$THETA 1.7 (.102 FIXED) 29.
```

If the lower, initial, and upper values for an element of  $\theta$  are identical, the element of  $\theta$  is understood to be fixed, even if the word FIXED does not appear.

### 2.4. How to Obtain Initial Estimates for $\theta$

When estimating parameters, good initial estimates for  $\theta$  are sometimes important. Poor initial estimates may occasionally cause the NONMEM run to take excessive amounts of computer time, to produce parameter estimates that are not physiologically reasonable, or to fail to produce any parameter estimates at all. For some drugs and models, initial estimates for  $\theta$  can be obtained from published literature describing prior studies with the drug. For some studies, very accurate values may have been obtained by prior runs with NONMEM or other regression programs. Highly accurate values should be perturbed (modified) by about 10% before being used as initial estimates in a NONMEM run. (Initial estimates that are too close to what may be the actual final estimates will cause problems in a NONMEM run; see Chapter 13.) Sometimes, however, there is little guidance in choosing initial estimates for some elements of  $\theta$ .

One approach with population data, where there is a reasonable amount of data for each individual, is as follows. It is often easier to guess at appropriate parameter values for individual data than for population data. So, first estimate each individual's parameter values using only the data from the individual. The mean values of the individuals' parameter estimates can then be used as the initial parameter estimates in the population analysis. Results from individual runs can also be used to obtain initial estimates for elements of  $\Omega$  and  $\Sigma$ ; see below.

Another approach is simply to let NONMEM find an initial estimate. NONMEM has an automatic strategy for so doing; see Chapter 12, Section 4.4.

## 3. Providing Initial Estimates for $\Omega$ and $\Sigma$ : the \$OMEGA and \$SIGMA Records

Recall that  $\Omega$  and  $\Sigma$  are variance/covariance matrices for the following random variables:

Individual Model

$\Omega$  (OMEGA) for  $\eta$  (Random Intraindividual Variability)

Population Model

$\Omega$  (OMEGA) for  $\eta$  (Random Interindividual Variability)

$\Sigma$  (SIGMA) for  $\varepsilon$  (Random Intraindividual Variability)

In all the examples in this document,  $\Omega$  and  $\Sigma$  are *diagonal* matrices, in which covariance elements such as  $\omega_{12}$  (which is  $cov(\eta_1, \eta_2)$ ) are assumed to be zero. NONMEM also allows full variance/covariance matrices; this is beyond the scope of this text, but see Chapter 12, Section 4.1.

Initial estimates for the variances must be provided to NONMEM via the \$OMEGA and \$SIGMA records. Initial estimates of *all model parameters* ( $\theta$ ,  $\Omega$ , and  $\Sigma$ ) must be provided even if estimation is not requested. \$OMEGA and \$SIGMA records each contain a list of values, separated by spaces or commas, which are the estimates for the corresponding variances. As in the \$THETA record, the position of a value in the list corresponds to the position (subscript) of the corresponding variance (along the diagonal) in the matrix.

### 3.1. \$OMEGA Record With Individual Data

With individual data,  $\eta$  variables are used in \$ERROR records, where they are called either ERR or ETA. For example, in the theophylline problem of Chapter 2 (figure 2.1) there appear the records:

```
$ERROR
Y=F+ERR(1)
$OMEGA 1.2
```

Here, ERR(1) corresponds to  $\eta_1$ , and the initial estimate for its variance is 1.2: i.e.,  $\Omega_{11} = \omega_1^2 = var(\eta_1) = 1.2$ .

### 3.2. \$OMEGA Record With Population Data

With population data,  $\eta$  variables are used in \$PK statements. For example, in the phenobarbital problem of Chapter 2 (figure 2.6) there appear the lines:

```
CL=TVCL+ETA(1)
V=TVVD+ETA(2)
$OMEGA .0000055, .04
```

The \$OMEGA record says that the initial estimate for the variance of  $\eta_1$  is  $5.5 \times 10^{-6}$ , and of  $\eta_2$  is .04: i.e.,  $\Omega_{11} = \omega_1^2 = var(\eta_1) = 5.5 \times 10^{-6}$  and  $\Omega_{22} = \omega_2^2 = var(\eta_2) = .04$ . Some users of NONMEM prefer to code each value on a separate line so that they can include comments:

```
$OMEGA .0000005 ; VARIANCE IN CL
        .04      ; VARIANCE IN V
```

### 3.3. The \$SIGMA Record

This record is used only with population data, and is similar to the \$OMEGA record. It gives the initial estimates of the variances of the  $\varepsilon$  variables used in the \$ERROR statements, where they are called either ERR or EPS. For example, in Figure 2.6, there also appears the records:

```
$ERROR
Y=F+ERR(1)
$SIGMA 25
```

Here, ERR(1) corresponds to  $\varepsilon_1$ , and the initial estimate for its variance is 25: i.e.,  $\Sigma_{11} = \sigma_1^2 = var(\varepsilon_1) = 25$ .

### 3.4. Fixing Elements of $\Omega$ or $\Sigma$

It is sometimes desirable to hold one or more elements of  $\Omega$  or  $\Sigma$  to constant value(s). In the population example of Chapter 2 it is possible to ignore interindividual variability in

CL by fixing  $\eta_1$  to 0†. The variance of an  $\eta$  or  $\varepsilon$  variable is held constant by inserting the word FIXED *after* the initial estimate:

```
$OMEGA 0 FIXED .0225
```

Parentheses may be used to make the statement easier to read:

```
$OMEGA (0 FIXED) .0225
```

As with  $\theta$ , the value 0 may not be used as an initial estimate for any element of  $\Omega$  or  $\Sigma$  unless the element is fixed to this value.

### 3.5. How to Obtain Initial Estimates for $\Omega$ and $\Sigma$

The initial estimates for the variances will depend on the particular (interindividual and/or intraindividual) error models chosen. The estimates do not have to be particularly accurate, although values which are much too small can cause difficulties for NONMEM. In general, it is better to over-estimate the variances rather than to under-estimate them. As with initial estimates for  $\theta$ , initial estimates can sometimes be obtained from published literature or from prior runs with NONMEM or other regression programs.

Initial estimates can also be obtained by an approach which we illustrate with examples for both intraindividual and interindividual error models. The standard deviation of a physiological quantity is generally some fraction  $r$  of its typical value  $t$ :  $\sigma_y = rt$ .

For the additive model:

$$y = f + \varepsilon$$

$$\sigma_y = \sigma_\varepsilon = rt$$

$$\text{var}_\varepsilon = \sigma_\varepsilon^2 = (rt)^2 = r^2 t^2$$

Some ambiguity exists about what we mean by "the typical value" of  $y$ . For the purpose of obtaining an initial estimate of the variance, we need not be too particular about this. For the theophylline example (Figure 2.1), we may choose the mean of the observed values as the typical value. This value is approximately 5.4. Assuming 20% error, i.e.  $r = .2$ , then  $\sigma_\varepsilon^2 = (.2 \times 5.4)^2 = 1.2$ . Similarly, in the first phenobarbital example (Figure 2.6), the mean of the observations is approximately 25. Again assuming 20% error, then  $r = .2$ , and  $\sigma_\varepsilon^2 = (.2 \times 25)^2 = 25$ . For that same example, the typical value of CL was estimated according to the model for the parameter: TVCL=THETA (1). We used the initial estimate of  $\theta_1$ , .0047, as the typical value of CL, and assumed 50% error:  $\Omega_{11} = (.5 \times .0047)^2 = 5.5 \times 10^{-6}$ . The model for V is TVVD=THETA (2). Again, we used the initial estimate of  $\theta_2$ , .99, as the typical value of V, but assumed 20% error:  $\Omega_{22} = (.2 \times .99)^2 = .04$ . Note finally that in the second phenobarbital example (Figure 2.12), we used as initial estimates of variance the final estimates obtained from the first example (understanding that these estimates could be somewhat large due to some of the variability being explained in this example by a systematic influence of weight).

For the constant coefficient of variation model:

$$y = f + f\varepsilon$$

$$\sigma_y = f\sigma_\varepsilon = rt$$

† One could also re-write the \$PK statements to eliminate ETA(1) in the model for CL, which also requires that ETA(2) in the model for V be re-numbered as ETA(1). It is easier to modify only \$OMEGA.

$$\text{var}_\varepsilon = \sigma_\varepsilon^2 = \frac{r^2 t^2}{f^2}$$

If we identify  $t$  with the value of  $f$  (whatever it may be), we have:

$$\text{var}_\varepsilon = r^2$$

In other words, using the CCV model, we do not need to estimate the typical value of the variable. For example, assuming 20% error,  $\text{var}_\varepsilon = .2^2 = .04$ .

As with  $\theta$ , it is possible for NONMEM itself to obtain initial estimates of  $\Omega$  and  $\Sigma$  automatically; see Chapter 12, Section 4.4.

#### 4. Specifying Optional Tasks

Two main tasks of NONMEM, the Estimation Step and the Covariance Step, are optional and must be specifically requested by including the \$ESTIMATION and \$COVARIANCE records. To skip the Estimation Step, simply omit the \$ESTIMATION record. To skip the Covariance Step, simply omit the \$COVARIANCE record.

In every run NONMEM computes and prints the value of the objective function and the final parameter estimates. The values printed are based on the final parameter estimates if the Estimation Step is requested, and are based on the initial estimates if it is not.

##### 4.1. Requesting the Estimation Step: the \$ESTIMATION Record

In the Estimation Step, NONMEM performs a search to obtain those values of  $\theta$ ,  $\Omega$ , and (for population studies)  $\Sigma$  which give the lowest value of the objective function. The output of this step is the pages whose titles are "MONITORING OF SEARCH:", "MINIMUM VALUE OF OBJECTIVE FUNCTION", and "FINAL PARAMETER ESTIMATE". This step is requested by the presence of the following statement:

###### **\$ESTIMATION**

There are several options, which are described in the NONMEM Users Guide, Part IV. The most frequently used ones are as follows.

###### **METHOD=0**

NONMEM always sets  $\text{etas}$  to 0 during the computation of the objective function. Also called the "first order (FO) method." This is the default. It may also be coded as **METHOD=ZERO**.

###### **METHOD=1**

NONMEM uses conditional estimates for the  $\text{etas}$  during the computation of the objective function. **METHOD=1** is also called the "first order conditional estimation (FOCE) method." It may also be coded as **METHOD=CONDITIONAL**. When the option **INTERACTION** is also present, the method is called the "FOCE with **INTERACTION** method". It is recommended for continuous variables unless the data are very sparse. These methods are discussed in Guide VII, Conditional Estimation Methods.

###### **SIGDIGITS=n**

By default, the search continues until the estimates of all elements of  $\theta$ ,  $\Omega$ , and  $\Sigma$  have been determined to at least 3 significant figures. Because only 3 significant digits are used to print parameter estimates in the output, and for other reasons as well, this amount of accuracy is often sufficient. However, the **SIGDIGITS** option can be used to request a different number ( $n$ ) of significant digits.

MAXEVAL=*n*

The Estimation Step always runs with a specific limit on the number of objective function evaluations allowed during the search, as a protection against infinite loops and excessively long runs. The default maximum is computed according to the number of parameters being estimated. The MAXEVALS option can be used to request a different number (*n*) for the maximum number of function evaluations.

PRINT=*n*

As the Estimation Step progresses, by default it prints intermediate output summarizing the progress of the search. The search proceeds in stages, called iterations. At the end of certain iterations a summarization is printed which consists of the values of the objective function, its gradient vector with respect to the parameters, and the parameter values themselves. By default, this summarization is only printed for the first and last iterations. The PRINT option can be used to request a number (*n*) such that starting from the first iteration, only *n*-1 iterations are skipped before another summarization is printed†.

An example of the use of these options is:

```
$EST SIG=6,MAX=900,PRI=5
```

In addition to the first and last iterations, summarizations are printed every 5th iteration. Notice that abbreviations of the record and option names were used; this is a matter of style.

#### 4.2. Requesting the Covariance Step: the \$COVARIANCE Record

In the Covariance Step, NONMEM obtains information on the precision of the parameter estimates obtained in the Estimation Step. The output of this step are pages with titles "STANDARD ERROR OF ESTIMATE", "COVARIANCE MATRIX OF ESTIMATE", "CORRELATION MATRIX OF ESTIMATE", and "INVERSE COVARIANCE MATRIX OF ESTIMATE". This step is requested by the presence of the following record:

```
$COVARIANCE
```

There are several options, which are discussed in NONMEM Users Guide, Part IV. The Covariance Step cannot be requested by itself; the Estimation Step must precede it‡.

#### 5. Specifying Optional Output

\$TABLE and \$SCATTERPLOT records are used to request NONMEM steps which generate additional output. If one of these records is omitted, NONMEM does not produce the corresponding additional output. Tables and scatterplots are generated *after* all other tasks have been performed. This affects the values displayed for PRED, RES, and WRES. If the Estimation Step is *not* run, then the *initial* estimates of the parameters are used to compute these quantities. If the Estimation Step *is* run, then the *final* parameter estimates are used. Residuals (RES) and weighted residuals (WRES) are defined in Chapter 11, Section 4.4.2.

The UNCONDITIONAL option of the \$TABLE and \$SCATTERPLOT records requests that output of this type be generated even if the Estimation Step terminates unsuccessfully, and is the default. The CONDITIONAL option of these records requests that output of this type be generated only if the Estimation Step terminates successfully.

† The PRINT option can also be used to suppress intermediate printout altogether, but this should usually not be done because the information is often of value. See Chapter 10, Section 4.

‡ The Estimation Step may be omitted when the run is continued from a prior run using a Model Specification input file; see Chapter 12, Section 4.3, and Chapter 13, Section 3.2.

### 5.1. Requesting the Table Step: the \$TABLE Record

The values of DV, PRED, RES, and WRES are always printed in every table. Other data items to be printed should be listed on the record. The data items are printed in the order in which they are listed. This does not have to be the same order as in the data file, nor does every data item have to be listed. For example, the following record appears in Chapter 2, figure 2.12:

```
$TABLE ID TIME AMT WT APGR
```

Figure 10.10 in Chapter 10 shows a portion of the resulting output.

It is possible for the lines of a table to be sorted into a different order than that of the original input file; this is discussed in the NONMEM Users Guide, Part IV.

More than one table can be printed. A separate \$TABLE record is used to request each one.

### 5.2. Requesting Scatterplots: the \$SCATTERPLOT Record

Chapter 2 contained many examples of \$SCATTERPLOT records and the resulting output. Here, for example, are the records from figure 2.6:

```
$SCATTERPLOT PRED VS DV UNIT
$SCATTERPLOT RES VS WT
```

The word UNIT requests a unit-slope line, which is the line PRED=DV. Figures 2.10 and 2.11 show the resulting output.

Similarly, the word ORD0 can be used to request a zero line on the ordinate axis.

It is possible to generate several scatterplots with a single record, by using a list of data item names:

```
$SCATTERPLOT (PRED,RES,WRES) VS WT
```

This produces three scatterplots, and has the same effect as the three records:

```
$SCATTERPLOT PRED VS WT
$SCATTERPLOT RES VS WT
$SCATTERPLOT WRES VS WT
```

Sometimes it is desirable to partition a scatterplot into a number of separate scatterplots. For example, if the data contain both plasma and urine observations, it would be better to separate the scatterplot of PRED vs. DV into one scatterplot where the DV values are the plasma observations, and another one where the DV values are the urine observations. To do this, it is necessary to specify a partitioning data item, in this case, the CMT data item, which gives the compartment number of the observation. The following record could be used.

```
$SCATTERPLOT PRED VS DV BY CMT UNIT
```

This will produce separate scatterplots: one with plasma observations (CMT=1 if ADVAN1 is used), and one with urine observations (CMT=2 if ADVAN1 is used).

Two partitioning items can also be specified:

```
$SCATTERPLOT PRED VS DV BY CMT SEX UNIT
```

One scatterplot is produced for each unique *combination* of values of the two partitioning data items.

## 6. Placement and Order of Records

Two main rules control the placement and order of records within a NM-TRAN control file:

The \$INPUT record must appear *before* any records which contain data item names (\$PK, \$ERROR, \$TABLE, \$SCATTERPLOT)

The \$SUBROUTINE, \$PK, and \$ERROR records should appear in the indicated order, but do not have to be consecutive.

The records \$DATA, \$THETA, \$OMEGA, \$SIGMA, \$ESTIMATION, \$COVARIANCE, \$TABLE, and \$SCATTERPLOT can be placed anywhere among the control records, in any order. However, NONMEM always performs its tasks in a fixed order:

- Estimation Step
- Covariance Step
- Table Step
- Scatterplot Step

Thus, even if the \$TABLE record precedes the \$ESTIMATION record, the values of PRED, RES, and WRES in the table will be based on the final parameter estimates.

## 7. INCLUDE records

One or more records of the form

```
INCLUDE filename n
```

may appear anywhere among the NM-TRAN control records. The characters INCLUDE may be upper- or lower-case. "n" is an optional integer, and gives the number of copies (default is 1).

NM-TRAN opens the named file and reads it to end-of-file. The contents of the named file may be any portion of an NM-TRAN control stream, e.g., NM-TRAN control records and/or abbreviated code. After reaching end-of-file, if the number of copies is greater than 1, NM-TRAN rewinds the file and re-reads it the specified number of times. After reaching end-of-file on the final (or only) copy, NM-TRAN resumes reading the original control stream after the include record.

There may be more than one INCLUDE record, but they may not be nested. That is, an included file may not contain INCLUDE records.

For example,

```
$PROBLEM Model "a" with data set 27, proportional error
INCLUDE data27.def
INCLUDE modela.def
$ERROR Y=F+F*ERR(1)
$THETA 1.3 4
$OMEGA .04
$SIGMA 1
$ESTIMATION
```

The file data27.def contains the \$INPUT and \$DATA records.

The file modela.def contains the \$SUBROUTINE record and \$PK block.

## Chapter 10 - Reading the Output

### 1. What This Chapter is About

This chapter describes NONMEM's output in detail. Each page of a NONMEM-PREDPP output file is shown and discussed.

The input file to NM-TRAN is that of figure 2.12, which is reproduced here as figure 10.1 for convenience.

```
1   $PROBLEM PHENOBARB WITH WEIGHT IN MODELS FOR CL AND V
2   $INPUT  ID TIME AMT WT APGR DV
3   $DATA  INDATA
4   $SUBROUTINE ADVAN1
5   $PK
6       TVCL=THETA (1)+THETA (3) *WT
7       CL=TVCL+ETA (1)
8       TVVD=THETA (2)+THETA (4) *WT
9       V=TVVD+ETA (2)
10
11                                     ; THE FOLLOWING ARE REQUIRED BY PREDPP
12       K=CL/V
13       S1=V
14   $ERROR
15       Y=F+ERR (1)
16   $THETA  (0, .0027) (0, .70) .0018 .5
17   $OMEGA  .000007, .3
18   $SIGMA  8
19   $ESTIMATION PRINT=10
20   $COVARIANCE UNCONDITIONAL
21   $TABLE ID TIME AMT WT APGR DV
22   $SCATTER  PRED VS DV  UNIT
23   $SCATTER  RES  VS WT
```

Figure 10.1. The NM-TRAN input file (same as figure 2.12). The line numbers on the left are not actually part of the file.

### 2. NONMEM Describes its Inputs

The first page of NONMEM's output is shown in figure 10.2. In this page, NONMEM repeats ("echos") the instructions it was given in the control file and describes the data file. The first page of the output should be checked carefully. Problems in a NONMEM run can often be traced to errors in the problem specification. For example, always check that the initial parameter estimates were entered correctly.

```

1 NONLINEAR MIXED EFFECTS MODEL PROGRAM (NONMEM) VERSION 7.5.2
2 ORIGINALLY DEVELOPED BY STUART BEAL, LEWIS SHEINER, AND ALISON BOECKMANN
3 CURRENT DEVELOPERS ARE ROBERT BAUER, ICON DEVELOPMENT SOLUTIONS,
4 AND ALISON BOECKMANN. IMPLEMENTATION, EFFICIENCY, AND STANDARDIZATION
5 PERFORMED BY NOUS INFOSYSTEMS.
6
7 PROBLEM NO.: 1
8 PHENOBARB WITH WEIGHT IN MODELS FOR CL AND V
9 DATA CHECKOUT RUN: NO
10 DATA SET LOCATED ON UNIT NO.: 2
11 THIS UNIT TO BE REWOUND: NO
12 CREATE/ADD TO FDATA.csv: YES
13 NO. OF DATA RECS IN DATA SET: 744
14 NO. OF DATA ITEMS IN DATA SET: 8
15 ID DATA ITEM IS DATA ITEM NO.: 1
16 DEP VARIABLE IS DATA ITEM NO.: 6
17 MDV DATA ITEM IS DATA ITEM NO.: 8
18 INDICES PASSED TO SUBROUTINE PRED:
19 7 2 3 0 0 0 0 0 0 0 0
20 LABELS FOR DATA ITEMS:
21 ID TIME AMT WT APGR DV EVID MDV
22 FORMAT FOR DATA:
23 (6E6.0,2F2.0)
24
25 TOT. NO. OF OBS RECS: 155
26 TOT. NO. OF INDIVIDUALS: 59
27 LENGTH OF THETA: 4
28 DEFAULT THETA BOUNDARY TEST OMITTED: NO
29 OMEGA HAS SIMPLE DIAGONAL FORM WITH DIMENSION: 2
30 DEFAULT OMEGA BOUNDARY TEST OMITTED: NO
31 SIGMA HAS SIMPLE DIAGONAL FORM WITH DIMENSION: 1
32 DEFAULT SIGMA BOUNDARY TEST OMITTED: NO
33 INITIAL ESTIMATE OF THETA:
34 LOWER BOUND INITIAL EST UPPER BOUND
35 0.0000E+00 0.2700E-02 0.1000E+07
36 0.0000E+00 0.7000E+00 0.1000E+07
37 -0.1000E+07 0.1800E-02 0.1000E+07
38 -0.1000E+07 0.5000E+00 0.1000E+07
39 INITIAL ESTIMATE OF OMEGA:
40 0.7000E-05
41 0.0000E+00 0.3000E+00
42 INITIAL ESTIMATE OF SIGMA:
43 0.8000E+01
44 COVARIANCE STEP OMITTED: NO
45 EIGENVLS. PRINTED: NO
46 SPECIAL COMPUTATION: NO
47 COMPRESSED FORMAT: NO
48 GRADIENT METHOD USED: NOSLOW
49 SIGDIGITS ETAHAT (SIGLO): -1
50 SIGDIGITS GRADIENTS (SIGL): -1
51 EXCLUDE COV FOR FOCE (NOFCOV): NO
52 Cholesky Transposition of R Matrix (CHOLROFF): 0
53 KNUTHSUMOFF: -1
54 RESUME COV ANALYSIS (RESUME): NO
55 SIR SAMPLE SIZE (SIRSAMPLE):
56 NON-LINEARLY TRANSFORM THETAS DURING COV (THBND): 1
57 PRECONDITIONING CYCLES (PRECOND): 0
58 PRECONDITIONING TYPES (PRECONDS): TOS
59 FORCED PRECONDITIONING CYCLES (PFCOND): 0
60 PRECONDITIONING TYPE (PRETYPE): 0
61 FORCED POS. DEFINITE SETTING DURING PRECONDITIONING: (FPOSDEF): 0
62 SIMPLE POS. DEFINITE SETTING: (POSDEF): -1
63 TABLES STEP OMITTED: NO
64 NO. OF TABLES: 1
65 SEED NUMBER (SEED): 11456
66 NPDTYPE: 0
67 INTERTYPE: 0
68 RANMETHOD: 3U
69 MC SAMPLES (ESAMPLE): 300
70 WRES SQUARE ROOT TYPE (WRESCHOL): EIGENVALUE
71 -- TABLE 1 --
72 RECORDS ONLY: ALL
73 4 COLUMNS APPENDED: YES
74 PRINTED: YES
75 FORMAT: S1PE11.4
76 IDFORMAT:
77 LFORMAT:
78 RFORMAT:
79 FIXED_EFFECT_ETAS:
80 USER-CHOSEN ITEMS:
81 ID TIME AMT WT APGR
82 SCATTERPLOT STEP OMITTED: NO
83 FAMILIES OF SCATTERPLOTS: 2
84 -- SCATTERPLOT 1 --
85 UNIT SLOPE LINE: YES
86 ITEMS TO BE SCATTERED: DV PRED
87 -- SCATTERPLOT 2 --
88 UNIT SLOPE LINE: NO
89 ITEMS TO BE SCATTERED: WT RES
90

```

Figure 10.2. The first page of the output report. The line numbers on the left are not actually part of the report.

Line 8 is an identification line for the output report. The contents of the \$PROBLEM record are shown here.

Line 9 indicates that this is not a data checkout run. (Data checkout mode is discussed in Chapter 12 Section 4.10.) Lines 10 through 26 describe the input data file. Lines 13 and 14 describe the numbers of rows and columns in the input file, as shown in figure 6.1. Specifically, line 13 shows how many data records were read according to the FORTRAN format specification given in line 23. (Records that are dropped by the Data Preprocessor (nm6) using `$DATA...IGNORE=...` are never read by NONMEM, hence cannot be included in line 13.) With NONMEM 7.5, line 13 also does not include records that were read by NONMEM but dropped by PRED using the `PRED_IGNORE_DATA` variable. Line 14 describes the number of data items per record, which is the number of data items listed in the \$INPUT record, less any that were dropped by the Data Preprocessor, plus any that it added (see Chapter 6). Lines 15 to 17 describe the locations of those data items of interest to NONMEM itself (i.e. NONMEM data items). Lines 18 and 19 are discussed in Section 3. Line 21 gives the labels for all the data items. The first six labels are those of the data items specified in the \$INPUT record and the next two (EVID, MDV) are those of two data items added to the data set by the Data Preprocessor. (NONMEM itself supplies labels PRED, RES, and WRES for the prediction, residual, and weighted residual data items.) In the terminology of Chapter 4 (e.g. (4.15a)), ID, TIME, AMT, WT, and APGR are the elements of  $x$ ; DV is  $y$ ; PRED is  $f$  (evaluated for the typical individual in the population). Line 23 shows the format used to read each data record. In this example, the format was generated by the Data Preprocessor and describes the data file after processing by the Data Preprocessor.† Line 25 gives the number of observation records. Line 26 gives the number of individual records; that is, one less than the number of times that the ID data item changed value. With NONMEM 7.5, Lines 25 and 26 do not include records that were read by NONMEM but dropped by PRED using the `PRED_IGNORE_DATA` variable.

Lines 27 through 43 describe the contents of the \$THETA, \$OMEGA and \$SIGMA records. First, the number of elements of  $\theta$ ,  $\Omega$  and  $\Sigma$  are given (lines 27, 29 and 31), then their initial estimates are displayed. In lines 35-38, notice the values 0.1000e+07 and -0.1000e+07. These are NONMEM's way of expressing the values  $+\infty$  and  $-\infty$ ; i.e., of describing  $\theta$ s which are unbounded on one or both sides. Another FORTRAN system may display these numbers differently (e.g., 1.0000e+06), but the absolute value will always be 1,000,000. In lines 40 and 41, notice that the variances from the \$OMEGA record appear along the diagonal of the  $\Omega$  matrix, and that the off-diagonal element  $cov(\eta_1, \eta_2)$  is zero. Line 29 states that NONMEM understands  $\Omega$  to be diagonal; the off-diagonal element(s) are automatically fixed at zero.

The remaining lines of figure 10.2 describe the tasks that NONMEM will perform.

Lines 44 through 62 describe the \$COVARIANCE record, giving the default options chosen by NM-TRAN.

Lines 63 through 81 describe the \$TABLE record. Lines 82 through 89 describe the \$SCATTERPLOT records.

Figure 10.2b describes the options of the \$ESTIMATION record.

Lines 1 through 40 describe the \$ESTIMATION record. Line 1 contains the tag #TBLN:, and specifies that following it, on the same line, will be found an integer that refers to the number of this estimation method. As of NONMEM7, each \$ESTIMATION records

† When a format specification is supplied on the \$DATA record, and no data items are dropped or added by the Data Preprocessor, the original format specification is used unchanged and appears here.

```

1 #TBLN:          1
2 #METH: First Order
3
4 ESTIMATION STEP OMITTED:                NO
5 SHRINK INFO WITH EVALUATION (EVALSHRINK) NO
6 ANALYSIS TYPE:                          POPULATION
7 NUMBER OF SADDLE POINT RESET ITERATIONS: 0
8 GRADIENT METHOD USED:                    NOSLOW
9 EPS-ETA INTERACTION:                    NO
10 NO. OF FUNCT. EVALS. ALLOWED:          360
11 NO. OF SIG. FIGURES REQUIRED:           3
12 INTERMEDIATE PRINTOUT:                 YES
13 ESTIMATE OUTPUT TO MSF:                 NO
14 IND. OBJ. FUNC. VALUES SORTED:        NO
15 NUMERICAL DERIVATIVE
16     FILE REQUEST (NUMBER):              NONE
17 MAP (ETAHAT) ESTIMATION METHOD (OPTMAP): 0
18 ETA HESSIAN EVALUATION METHOD (ETADER):  0
19 INITIAL ETA FOR MAP ESTIMATION (MCETA): 0
20 SIGDIGITS FOR MAP ESTIMATION (SIGLO):   100
21 GRADIENT SIGDIGITS OF
22     FIXED EFFECTS PARAMETERS (SIGL):    100
23 NOPRIOR SETTING (NOPRIOR):              0
24 NOCOV SETTING (NOCOV):                  OFF
25 DERCONT SETTING (DERCONT):              OFF
26 FINAL ETA RE-EVALUATION (FNLETA):       1
27 EXCLUDE NON-INFLUENTIAL (NON-INFL.) ETAS
28     IN SHRINKAGE (ETATYPE):             NO
29 NON-INFL. ETA CORRECTION (NONINFETA):   0
30 RAW OUTPUT FILE (FILE): 2.11.ext
31 EXCLUDE TITLE (NOTITLE):                NO
32 EXCLUDE COLUMN LABELS (NOLABEL):        NO
33 FORMAT FOR ADDITIONAL FILES (FORMAT):   S1PE12.5
34 PARAMETER ORDER FOR OUTPUTS (ORDER):    TSOL
35 KNUTHSUMOFF:                            0
36 INCLUDE LNTWOPI:                        NO
37 INCLUDE CONSTANT TERM TO PRIOR (PRIORC): NO
38 INCLUDE CONSTANT TERM TO OMEGA (ETA) (OLNTWOPI):NO
39 ADDITIONAL CONVERGENCE TEST (CTYPE=4)? : NO
40 EM OR BAYESIAN METHOD USED:              NONE
41

```

Figure 10.2b. The \$ESTIMATION record description. The line numbers on the left are not actually part of the report.

represents a separate estimation method, in which the final parameters of the previous estimation are passed as initial parameters to the next estimation. This is further described in Introduction to NONMEM7. This number is also the table number listed in the title to tables in the various output files (raw output file .ext, .cov, .cor, etc). The table number is incremented for each \$EST statement, across all problems in the control stream file. On Line 2, the tag #METH: specifies that following it, on the same line, will be found a text that describes the estimation method. Lines 4 through 40 show the defaults (set by NM-TRAN) for various options, all of which could have been specified explicitly on the \$ESTIMATION record. In line 10 for example, NONMEM displays the maximum number of times it will evaluate the objective function during the Estimation Step (this number can be slightly exceeded). The value 360 was supplied by NM-TRAN. It is a function of the sizes of  $\theta$ ,  $\Omega$ , and  $\Sigma$ . Line 11 displays the desired number of significant digits in the final parameter estimate; the value 3 is the default number requested by NM-TRAN.

### 3. PREDPP Describes Its Inputs

The next two pages are produced by PREDPP and will not appear if \$PRED statements (or a user-written PRED subroutine) are used. PREDPP uses these pages to repeat ("echo") the instructions it was given in the control file, and to identify the ADVAN and TRANS routines chosen by the user. The first page of PREDPP's output is shown in figure 10.3.

In its first page of output, PREDPP describes the features of the pharmacokinetic model and its parameterization encoded into the ADVAN and TRANS routines specified on the \$SUBROUTINE record. The information displayed here includes the kind of information summarized in Appendices 1 and 2. In the particular output of Figure 10.3 no

```

1 DOUBLE PRECISION PREDPP VERSION 7.5.2
2
3 ONE COMPARTMENT MODEL (ADVAN1)
4 MAXIMUM NO. OF BASIC PK PARAMETERS: 2
5 BASIC PK PARAMETERS (AFTER TRANSLATION):
6 ELIMINATION RATE (K) IS BASIC PK PARAMETER NO.: 1
7
8 COMPARTMENT ATTRIBUTES
9 COMPT. NO. FUNCTION INITIAL ON/OFF DOSE DEFAULT DEFAULT
10 STATUS ALLOWED ALLOWED FOR DOSE FOR OBS.
11 1 CENTRAL ON NO YES YES YES
12 2 OUTPUT OFF YES NO NO NO
13

```

Figure 10.3. The first page of PREDPP's output. The line numbers on the left are not actually part of the report.

information concerning an alternate parameterization appears because TRANS1 was specified. The information concerning basic parameters and compartments is displayed in a format similar to that used in NONMEM Users Guide, Part VI, which is the complete reference for PREDPP.

Lines 4 and 6 describe the basic PK parameters, which in this example is the single microconstant K. If a translator other than TRANS1 had been requested, an additional line would appear describing the translation. E.g., with TRANS2, this line would read:

**TRANSLATOR WILL CONVERT PARAMETERS CLEARANCE (CL) AND VOLUME (V) to K**

Lines 8 through 12 describe the compartment attributes. Even though the output compartment is never turned on by the data of this example, its attributes are described here because it is part of the model.

The information presented so far describes the model for computing drug amounts. For a given choice of ADVAN and TRANS, the contents of this page are completely fixed. PREDPP's second page of output describes user choices related to the given ADVAN routine, including choices for the scale parameters (and thus, to the model for computing concentrations). This page is shown in figure 10.4.

```

1 ADDITIONAL PK PARAMETERS - ASSIGNMENT OF ROWS IN GG
2 COMPT. NO. INDICES
3 SCALE BIOAVAIL. ZERO-ORDER ZERO-ORDER ABSORB
4 FRACTION RATE DURATION LAG
5 1 3 * * * *
6 2 * - - - -
7 - PARAMETER IS NOT ALLOWED FOR THIS MODEL
8 * PARAMETER IS NOT SUPPLIED BY PK SUBROUTINE;
9 WILL DEFAULT TO ONE IF APPLICABLE
10 DATA ITEM INDICES USED BY PRED ARE:
11 EVENT ID DATA ITEM IS DATA ITEM NO.: 7
12 TIME DATA ITEM IS DATA ITEM NO.: 2
13 DOSE AMOUNT DATA ITEM IS DATA ITEM NO.: 3
14
15 PK SUBROUTINE CALLED WITH EVERY EVENT RECORD.
16 PK SUBROUTINE NOT CALLED AT NONEVENT (ADDITIONAL OR LAGGED) DOSE TIMES.
17 DURING SIMULATION, ERROR SUBROUTINE CALLED WITH EVERY EVENT RECORD.
18 OTHERWISE, ERROR SUBROUTINE CALLED ONCE IN THIS PROBLEM.
19

```

Figure 10.4. The second page of PREDPP's output. The line numbers on the left are not actually part of the report.

Lines 2 through 9 describe the additional PK parameters that are computed by the \$PK statements (or PK subroutine). In line 5, the position marked with "3" corresponds to the scale parameter for compartment number 1. Thus, we know that the \$PK statements contained an assignment statement for S1. From the prior page we can see that compartment number 1 is the central compartment. The value "3" is a row number within GG, an array used for communication between PREDPP and the PK subroutine. With the use of NM-TRAN and \$PK statements, row numbers are of no interest to the user. With a user-written PK subroutine, it is important to check their correctness. Positions marked with "\*" correspond to additional PK parameters that are allowed by the model but that are not assigned a value by \$PK statements; an example is F1, the bioavailability fraction for compartment 1. Positions marked with "-" correspond to additional parameters that may

not be computed; for instance, dose-related parameters are not allowed for the output compartment, because (as shown on the preceding page) this compartment cannot receive doses.

Lines 10 through 13 describe the locations in the input data record of those data items of interest to PREDPP (PREDPP data items). (NM-TRAN causes the locations of these data items in the data set to be passed by NONMEM to PREDPP, as indicated in lines 15 through 17 of figure 10.2. NONMEM is not concerned with the significance of these data items.) Note that data item 7, Event ID, was appended by the Data Preprocessor.

Line 15 reflects the fact that, by default, \$PK statements are evaluated with every event record<sup>†</sup>. Lagged and additional doses are discussed in Chapter 12, Sections 2.4 and 2.5. They are not used in this example.

Line 18 reflects the fact that the \$ERROR statements describe the simple error model (3.4). This model uses no data items and no elements of  $\theta$  whatsoever (directly or indirectly). NM-TRAN has instructed PREDPP that the \$ERROR statements need be evaluated only once at the beginning of the problem. Line 17 indicates that, should the Simulation Step be implemented, PREDPP will disregard this limitation and evaluate the \$ERROR statements with every event record, so that randomly-generated values of intra-individual error can be applied at every observation event. (This example does not involve simulation, but the PK and ERROR routines which implement the \$PK and \$ERROR statements are capable of supporting all NONMEM tasks, including simulation.)

Finally, note that the \$PK and \$ERROR models (figure 10.1, lines 5-14) are not documented in the NONMEM-PREDPP output. It is a good idea to attach a printed copy of the NM-TRAN input records to the corresponding NONMEM output. MS/DOS batch file nmfe7x.bat and Unix C-shell script nmfe7x (supplied with NONMEM) do this automatically.

#### 4. Diagnostic Output from the Estimation Step

The next page of output, figure 10.5, is produced during the running of the Estimation Step.

##### 4.1. Intermediate Output from the Estimation Step

Lines 1 through 33 are referred to as the intermediate output. Lines 4 through 8 give numbers summarizing the 0-th iteration, which are based on the initial parameter estimates. Line 4 shows the initial value of the objective function. The value following "NO. OF FUNC. EVALS." is the number of objective function evaluations which were needed during the iteration. Line 5 gives the cumulative number of function evaluations including this and all prior iteration summaries. With NONMEM 7, the parameter estimates are displayed in their natural (unscaled) space. These lines are identified as NPARAMETR (Line 6). Line 7 gives the unconstrained parameter (UCP) estimates. The search is carried out in a different parameter space. The parameters are transformed to unconstrained parameters (UCP). In the transformation process a scaling occurs so that the initial estimate of each of the UCP is 0.1. Thus, in line 7, all parameters are .1 at the 0-th iteration. Parameters are printed in the following order: elements of  $\theta$ , elements of  $\Omega$ , elements of  $\Sigma$ . In this example, reading from left to right, the parameters are  $\theta_1$ ,  $\theta_2$ ,

<sup>†</sup> In this example, the \$PK statements (lines 5 through 12 of the input file, figure 10.1) involve only WT, which is constant for each individual. It is possible to limit the event records with which the \$PK statements are evaluated to the first event record of each individual, in order to reduce run time. This decision is left to the user.

```

1 MONITORING OF SEARCH:
2
3
4 ITERATION NO.:      0  OBJECTIVE VALUE:    675.657684094370      NO. OF FUNC. EVALS.:   7
5 CUMULATIVE NO. OF FUNC. EVALS.:      7
6 NPARAMETER:  2.7000E-03  7.0000E-01  1.8000E-03  5.0000E-01  7.0000E-06  3.0000E-01  8.0000E+00
7 PARAMETER:    1.0000E-01  1.0000E-01  1.0000E-01  1.0000E-01  1.0000E-01  1.0000E-01  1.0000E-01
8 GRADIENT:    -3.9976E+01 -8.0006E+01 -4.2941E+02 -1.0001E+03  1.5391E+01  5.2661E+01  9.0187E+00
9
10 ITERATION NO.:    10  OBJECTIVE VALUE:    613.258949532521      NO. OF FUNC. EVALS.:  84
11 CUMULATIVE NO. OF FUNC. EVALS.:    91
12 NPARAMETER:  7.1965E-04  2.5796E-01  4.3459E-03  8.4505E-01  2.2246E-06  9.9144E-02  8.9710E+00
13 PARAMETER:  -1.2222E+00 -8.9828E-01  2.4144E-01  1.6901E-01 -4.7316E-01 -4.5360E-01  1.5728E-01
14 GRADIENT:    3.7213E+00  6.3503E+00  5.0514E+01  5.2246E+01  2.6041E+00  4.2624E+00  1.4554E+01
15
16 ITERATION NO.:    20  OBJECTIVE VALUE:    609.398192823140      NO. OF FUNC. EVALS.:  81
17 CUMULATIVE NO. OF FUNC. EVALS.:   172
18 NPARAMETER:  1.1805E-04  8.8326E-02  4.6808E-03  9.3708E-01  1.3391E-06  7.3110E-02  8.7520E+00
19 PARAMETER:  -3.0299E+00 -1.9700E+00  2.6004E-01  1.8742E-01 -7.2697E-01 -6.0591E-01  1.4492E-01
20 GRADIENT:    1.6349E-01 -5.8676E-01 -6.1457E+00 -1.4122E+01 -5.9614E-02  3.5384E-01  1.4194E-03
21
22 ITERATION NO.:    30  OBJECTIVE VALUE:    609.179165845924      NO. OF FUNC. EVALS.:  99
23 CUMULATIVE NO. OF FUNC. EVALS.:   271
24 NPARAMETER:  2.7000E-05  1.1935E-01  4.7519E-03  9.1899E-01  1.3698E-06  7.5079E-02  8.7026E+00
25 PARAMETER:  -4.5116E+00 -1.6690E+00  2.6399E-01  1.8380E-01 -7.1561E-01 -5.9262E-01  1.4209E-01
26 GRADIENT:    0.0000E+00  8.9319E-03  1.4467E-01  5.4480E-01 -1.7084E-03 -3.2719E-03 -7.7586E-03
27
28 ITERATION NO.:    31  OBJECTIVE VALUE:    609.179165845924      NO. OF FUNC. EVALS.:   0
29 CUMULATIVE NO. OF FUNC. EVALS.:   271
30 NPARAMETER:  2.7000E-05  1.1935E-01  4.7519E-03  9.1899E-01  1.3698E-06  7.5079E-02  8.7026E+00
31 PARAMETER:  -4.5116E+00 -1.6690E+00  2.6399E-01  1.8380E-01 -7.1561E-01 -5.9262E-01  1.4209E-01
32 GRADIENT:    0.0000E+00  8.9319E-03  1.4467E-01  5.4480E-01 -1.7084E-03 -3.2719E-03 -7.7586E-03
33
34 #TERM:
35 MINIMIZATION SUCCESSFUL
36 NO. OF FUNCTION EVALUATIONS USED:      271
37 NO. OF SIG. DIGITS IN FINAL EST.:    3.7
38 PARAMETER ESTIMATE IS NEAR ITS BOUNDARY
39
40 TOTAL DATA POINTS NORMALLY DISTRIBUTED (N):      155
41 N*LOG(2PI) CONSTANT TO OBJECTIVE FUNCTION:    284.870945293449
42 OBJECTIVE FUNCTION VALUE WITHOUT CONSTANT:    609.179165845924
43 OBJECTIVE FUNCTION VALUE WITH CONSTANT:      894.050111139373
44 REPORTED OBJECTIVE FUNCTION DOES NOT CONTAIN CONSTANT
45
46 TOTAL EFFECTIVE ETAS (NIND*NETA):      118
47
48 #TERE:
49 Elapsed estimation time in seconds:    0.61
50 S MATRIX ALGORITHMICALLY SINGULAR
51 S MATRIX IS OUTPUT
52 INVERSE COVARIANCE MATRIX SET TO RS*RMAT, WHERE S* IS A PSEUDO INVERSE OF S
53 Elapsed covariance time in seconds:    0.16
54 Elapsed postprocess time in seconds:    0.10
55

```

Figure 10.5. The output from the Estimation Step. The line numbers on the left are not actually part of the report.

$\theta_3$ ,  $\theta_4$ ,  $\Omega_{11}$ ,  $\Omega_{22}$ , and  $\Sigma_{11}$ .

Two points should be noted. First, fixed parameters do not appear in the list. Therefore, the off-diagonal element  $\Omega_{12}$ , which is effectively fixed to 0, does not appear. Second, when off-diagonal elements of  $\Omega$  are being estimated, then as many additional UCP's appear as there are off-diagonal elements of  $\Omega$  being estimated. However, a 1-1 correspondence between each of the elements of  $\Omega$  and an UCP does not exist. The same is true for elements of  $\Sigma$  and the UCP's for  $\Sigma$  when off-diagonal elements of  $\Sigma$  are estimated.

Line 8 shows the gradient for each parameter, which may be thought of as the partial derivative of the objective function with respect to that parameter.

The Estimation Step proceeds in a series of stages called iterations. In this example, intermediate printout is produced for each of every 5 iterations, as well as for the 0-th and final iterations, for which intermediate printout is always printed by default. This printout consists of the same four lines as for the 0-th iteration, but using the parameters estimates obtained at the end of the iteration.

In lines 4, 10, 16, 22, and 28, observe that the objective function drops quickly at first, and then more slowly. After iteration number 31, there is no change above the fourth

significant digit.

In lines 6, 12, 18, 24, and 30, observe that each parameter also changes rapidly at first and then more slowly as it converges to its final value. (The first parameter,  $\theta_1$ , is an exception. It is clearly approaching a very small value close to its lower bound, 0. In Chapter 12, we shall see that both  $\theta_1$  and  $\theta_2$  are best fixed at 0.)

Finally, in lines 8, 14, 20, 26, and 32, observe that the gradients also approach 0, another sign that a minimum of the objective function has been located.

The values computed for the gradients are very sensitive to differences in computer arithmetic and precision. If a given NONMEM run is repeated on a different computer, or on the same computer with different machine precision or a different FORTRAN compiler, it is likely that the gradients will be different. This will cause the search to follow a different path to the minimum, so that lines 4 through 33 may be quite different. However, each final estimate of a parameter should always be the same to the number of requested significant digits. (Minor differences may also be observed in the output of the Covariance Step, below; this output is also sensitive to computational differences.)

#### 4.2. Summary Output from the Estimation Step

Lines 34 to 37 are always printed, even when intermediate printout is suppressed. The tag #TERM: (Line 34) defines the beginning of the summary output statements of the estimation results, and ends with the #TERE tag (Line 48). This allows a third party software to locate the summary output paragraph between these two tags. Line 35, "MINIMIZATION SUCCESSFUL", signifies that the search appears to have located a minimum of the objective function. Before one can be certain that a minimum has been located, or one which corresponds to a reasonable parameter estimate (there can be a number of "local minima"), the final parameter estimates must be examined in their (untransformed) state; see Section 5 below. The Estimation Step is not always successful. Chapter 13 discusses two other messages that sometimes appear instead of line 35.

In line 36, note that the number of function evaluations used, 271, is a total value and includes all iterations (not just those for which intermediate printout was displayed). This is under the limit of 271 supplied by NM-TRAN (figure 10.2b, line 10).

The number of significant digits in the final estimate is given in line 37 as 3.7. This can be interpreted as meaning that no (transformed) *parameter estimate* is actually determined to less than 3.7 significant digits. More specifically, when the UCP estimates were compared between the last two iterations, none differed in the first (almost) 4 significant figures *including* leading zeros after the decimal point. Because NONMEM displays only 3 significant digits in the printed parameter estimates, and for other reasons as well, by default NM-TRAN requests only 3 significant digits. However, more significance can be requested, as was discussed in Chapter 9, Section 4.1.

#### 5. Minimum Value of the Objective Function and Final Parameter Estimates

The next two pages in the NONMEM output are produced whether or not the Estimation Step was implemented and, if it was, whether or not the search terminated successfully. They give the values of the objective function and the parameter estimates, using the final parameter estimates if the Estimation Step was implemented (whether or not the search terminated successfully), and using the initial parameter estimates otherwise. These pages have already been shown in Chapter 2, figure 2.13. Even when the minimization routine is successful in locating a minimum of the objective function, the final (untransformed) parameter estimates must be carefully checked. Is any parameter's final estimate

physiologically unreasonable? Is any parameter's final estimate near its upper or lower constraint? If either answer is yes, the model, the constraints on  $\theta$ 's, or the data may be incorrect; see Chapter 11.

Sometimes the final estimates do not match anticipated values, e.g., values obtained by some other system of analysis. Additional refinement of the model may be needed, as discussed in Chapter 11. However, the discrepancy may well be traceable to an error in model specification, such as an error in specifying a compartment's scale. Along with the Estimation Step, it is important to obtain a scatterplot of PRED vs DV and make sure the unit slope line is visible. See Chapter 13, Section 4.4.

## 6. Output from the Covariance Step

Figures 10.6 through 10.7 show the output of the Covariance Step, which was requested via the \$COVARIANCE record. Figure 10.6 has already been displayed as figure 2.14, but is included here for completeness. This page displays the standard errors of the parameter estimates. Standard errors are discussed extensively in Chapters 5 and 11. A detailed discussion of the remaining three pages, containing the covariance, correlation, and inverse covariance matrices, is beyond the scope of this text. Note, however, the use of the notation ".....". Each sequence of dots denotes a value (such as the standard error in the estimate of  $\Omega_{12}$ ) that is 0 by definition, rather than due to a computation.

```

1 *****
2 *****
3 *****
4 *****
5 *****
6 *****
7 *****
8 THETA - VECTOR OF FIXED EFFECTS PARAMETERS *****
9 TH 1 TH 2 TH 3 TH 4
10 0.00E+00 1.48E-01 2.24E-04 1.13E-01
11
12 OMEGA - COV MATRIX FOR RANDOM EFFECTS - ETAS *****
13 ETA1 ETA2
14 ETA1 7.30E-07
15 ETA2 ..... 3.63E-02
16
17 SIGMA - COV MATRIX FOR RANDOM EFFECTS - EPSILONS ****
18 EPS1
19 EPS1 1.71E+00
20
21 OMEGA - CORR MATRIX FOR RANDOM EFFECTS - ETAS *****
22 ETA1 ETA2
23 ETA1 3.12E-04
24 ETA2 ..... 6.63E-02
25
26 SIGMA - CORR MATRIX FOR RANDOM EFFECTS - EPSILONS ***
27 EPS1
28 EPS1 2.90E-01
29

```

Figure 10.6. Standard error of the estimate. The line numbers on the left are not actually part of the report.

```

1 *****
2 *****
3 *****
4 *****
5 *****
6 *****
7 *****
8 *****
9 *****
10 TH 1 TH 2 TH 3 TH 4 OM11 OM12 OM22 SG11
11 TH 1 0.00E+00
12 TH 2 0.00E+00 2.18E-02
13 TH 3 0.00E+00 -1.46E-05 5.01E-08
14 TH 4 0.00E+00 -1.60E-02 1.05E-05 1.29E-02
15 OM11 0.00E+00 2.22E-08 -5.96E-12 -1.58E-08 5.33E-13
16 OM12 .....
17 OM22 0.00E+00 4.64E-04 -5.35E-07 5.43E-04 6.53E-10 ..... 1.32E-03
18 SG11 0.00E+00 -5.85E-02 1.12E-04 4.56E-02 -3.80E-07 ..... -1.04E-02 2.92E+00

```

Figure 10.7. Covariance matrix of the estimate. The line numbers on the left are not actually part of the report.

```

1 *****
2 *****
3 *****
4 *****
5 *****
6 *****
7 *****
8 *****
9 *****
10          TH 1      TH 2      TH 3      TH 4      OM11      OM12      OM22      SG11
11 TH 1      0.00E+00
12 TH 2      0.00E+00  1.48E-01
13 TH 3      0.00E+00 -4.43E-01  2.24E-04
14 TH 4      0.00E+00 -9.54E-01  4.13E-01  1.13E-01
15 OM11      0.00E+00  2.06E-01 -3.64E-02 -1.90E-01  7.30E-07
16 OM12      .....
17 OM22      0.00E+00  8.66E-02 -6.57E-02  1.32E-01  2.46E-02 ..... 3.63E-02
18 SG11      0.00E+00 -2.32E-01  2.93E-01  2.35E-01 -3.04E-01 ..... -1.67E-01  1.71E+00

```

Figure 10.8. Correlation matrix of the estimate. The line numbers on the left are not actually part of the report.

```

1 *****
2 *****
3 *****
4 *****
5 *****
6 *****
7 *****
8 *****
9 *****
10          TH 1      TH 2      TH 3      TH 4      OM11      OM12      OM22      SG11
11 TH 1      0.00E+00
12 TH 2      0.00E+00  2.76E+01
13 TH 3      0.00E+00  3.33E+03  4.02E+05
14 TH 4      0.00E+00  2.31E+01  2.78E+03  1.93E+01
15 OM11      0.00E+00 -7.61E+06 -9.19E+08 -6.36E+06  2.10E+12
16 OM12      .....
17 OM22      0.00E+00 -4.53E+01 -5.47E+03 -3.79E+01  1.25E+07 ..... 7.44E+01
18 SG11      0.00E+00 -1.10E+00 -1.32E+02 -9.17E-01  3.03E+05 ..... 1.80E+00  4.37E-02

```

Figure 10.9. Inverse covariance matrix of the estimate. The line numbers on the left are not actually part of the report.

## 7. Additional Output: Tables and Scatterplots

The use of \$TABLE and \$SCATTERPLOT records to request tables and scatterplots is discussed in Chapter 9.

### 7.1. Output from the Table Step

The first 12 lines of the table produced by the \$TABLE record are shown in figure 10.10. This is the data for the first individual.

Each row in the table corresponds to a record of the input file, and the rows appear in the same order as do the corresponding records of the input data file. Note that the values of RES and WRES are always shown as zero for non-observation records<sup>†</sup>, whereas a (possibly) nonzero value of PRED is printed for every record.

If there are more than 900 data records, separate tables are produced for groups of 900 records. The last table contains the remaining records. If the rows of the table are sorted, each group of records is sorted separately. When the input data file is large, the table will require many pages to print. Therefore, the \$TABLE record should be omitted unless needed for diagnostic purposes (such as when initially checking a new data set or model).

### 7.2. Output from the Scatterplot Step

Many examples of scatterplots are present in Chapters 2 and 11. They are not reproduced here. Whereas all the records in the input data file correspond to rows of a table, this is not true of a scatterplot that includes one or more of the items RES, WRES, and DV. When one of these three is being plotted, then only observation records contribute points

<sup>†</sup> Strictly speaking, RES and WRES are always zero for records having MDV=1. With PREDPP, this is the same thing.

```

1 TABLE NO. 1
2
3
4
5 LINE NO.      ID      TIME      AMT      WT      APGR      DV      PRED      RES      WRES
6
7 1  1.00E+00  0.00E+00  2.50E+01  1.40E+00  7.00E+00  0.00E+00  1.78E+01  0.00E+00  0.00E+00
8
9 2  1.00E+00  2.00E+00  0.00E+00  1.40E+00  7.00E+00  1.73E+01  1.76E+01 -3.14E-01 -2.92E-01
10
11 3  1.00E+00  1.25E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  1.92E+01  0.00E+00  0.00E+00
12
13 4  1.00E+00  2.45E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.07E+01  0.00E+00  0.00E+00
14
15 5  1.00E+00  3.70E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.20E+01  0.00E+00  0.00E+00
16
17 6  1.00E+00  4.80E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.33E+01  0.00E+00  0.00E+00
18
19 7  1.00E+00  6.05E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.45E+01  0.00E+00  0.00E+00
20
21 8  1.00E+00  7.25E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.56E+01  0.00E+00  0.00E+00
22
23 9  1.00E+00  8.53E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.66E+01  0.00E+00  0.00E+00
24
25 10 1.00E+00  9.65E+01  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.77E+01  0.00E+00  0.00E+00
26
27 11 1.00E+00  1.08E+02  3.50E+00  1.40E+00  7.00E+00  0.00E+00  2.87E+01  0.00E+00  0.00E+00
28
29 12 1.00E+00  1.12E+02  0.00E+00  1.40E+00  7.00E+00  3.10E+01  2.81E+01  2.88E+00  6.88E-01

```

Figure 10.10. A portion of a NONMEM table. The line numbers on the left are not actually part of the report.

to the scatterplot†. In figure 2.5, there are exactly 10 points "\*", corresponding to the 10 observation records in figure 2.2; the dose record does not contribute a point.

NONMEM displays only the first 900 records of the appropriate type in a scatterplot. This limit applies before any partitioning. For example, in a plot of DV VS ID, the first 900 observation records are displayed; in a plot of WT vs ID, the first 900 records of the data file are displayed. Additional scatterplots can be requested, showing additional points, using options "FROM=" and "TO=" of the \$SCATTERPLOT record. See NONMEM Users Guide, Part IV.

† Strictly speaking, it is only the records having MDV=0 that contribute points. With PREDPP, this is the same thing.

## Chapter 11 - Model Building

### 1. What This Chapter is About

In this chapter, the simple phenobarbital example begun in Chapter 2 will be continued to illustrate how NONMEM is used to build a model for population data. The topic of model building, diagnosis and verification is a large one. This chapter can only give a very abbreviated example.

### 2. The Stages of Model Building

To analyze a population data set and build a model for it, one must proceed in logical stages. There are five stages, and their relationship to one another is presented diagrammatically in figure 11.1. One begins by checking the data. One then tries to find an adequate model incorporating the fixed effects; then an adequate model incorporating the random effects and describing random inter- and intra-individual variability. After a reasonably complete model is found, attempts are made to refine it, and finally, if desired, the various parts of the models (which often, in effect, simply assert the existence of certain relationships between independent variables and the dependent variable) can be subject to formal hypothesis tests, as described in Chapter 5. (However, it is well known by statisticians that formal hypothesis testing undertaken *after* model building is just an approximation for the type of hypothesis testing described in textbooks, which assumes that the model is the correct model).




Figure 11.1. Stages in model building.

### 3. Check-out — Index Plots

The goal of this stage is to assure that the data are correct. There is no point to trying to model the data when gross errors are present. Most gross errors are encoding errors that cause certain values to be different from the intended value by a considerable amount (for example, a misplaced decimal point changes a value by a factor of 10), so that graphical display of the data is usually adequate to detect these. No numerical or statistical approaches are needed. Indeed, they are not usually useful, even for more subtle errors, as such errors cannot easily be detected by any means (how is a 10% error to be distinguished from inter- or intra-individual variability?).

To detect gross errors, then, one makes scatterplots of different data item types vs individuals' identification numbers (i.e. the ID data item, or, if the values of this data item are arbitrary, another data item that identifies patients using sequential integer values; call this the sequence data item: SEQ). Such plots (of one data item versus ID or SEQ) are called here index plots, and are quite useful for revealing the structure of the data, as will be noted below, as well as for finding gross errors.

If NONMEM is used to make index plots, it will also be useful to implement the Tables Step, so that if a problem is noted in a scatterplot, one can refer to the table to try to find the datum that might account for the problem. To run NONMEM some model must be specified, even if all that is desired is an index plot. In such case, it makes little difference what model is used. It is easiest and useful to (i) start with a simple ADVAN that is likely to provide at least a roughly satisfactory fit, (ii) set each PK parameter to a (different) element of  $\theta$ , (iii) use only one  $\eta$  variable, modifying the scale parameter only, and one  $\varepsilon$  variable, and (iv) use roughly reasonable fixed initial estimates.

For the phenobarbital example, one might use ADVAN1 with  $K = \theta_1$ ,  $V = \theta_2 + \theta_2\eta_1$ , and  $y = f + f\varepsilon_1$ . Initial estimates might be:  $K = .0057 \text{ hr}^{-1}$  (half-life = 5 days, a typical value for adults);  $V = 1.44 \text{ L}$ . (the first patient has a concentration of 17.3 mg/L some few hours after an initial loading dose of 25 mg;  $1.44 \text{ times } 17.3 = 25$ );  $\omega = .25$  (50% variability);  $\sigma^2 = .04$  (20% variability).

Figures 11.2 and 11.3 show index plots that might be seen in a check-out run (gross errors have been added). In figure 11.2, DV is plotted vs ID (here ID and SEQ are the same), and a gross error occurring at about patient #13 is seen (an observation of about 24 mcg/ml was erroneously recorded as 240 mcg/ml). In figure 11.3, AMT is plotted vs ID, and patient #3 appears to have a grossly erroneous value (again, a decimal point error; a dose of 18 was misrecorded as 180).




Figure 11.2. A scatterplot of the dependent variable, DV, vs the patient's ID number (a type of index plot). Note the outlier at about ID = 13.

Actually, figure 11.3 reveals a considerable amount about the data structure (this will be seen better in figure 11.4, below, when the outlier has been removed). Many points lie along the line  $AMT = 0$ , where one sees integers 5, 3, 3, 6, etc, as one proceeds along the ID axis, each integer indicating the corresponding number of points over-plotted at that location. They correspond to the observation records, since the doses on these records are all zero. Thus one can see how many observations each individual contributes (other type records would also plot at  $AMT=0$ , however). Proceeding to the next highest "line" of doses (where many points over-plot for each patient), one "sees" the event records giving the maintenance dose amount since this amount stays constant within a individual (many maintenance doses were given per individual), and this amount is approximately the same across individuals. Last, at the highest doses (except for the outlier), one has mostly single points. These are the loading doses. There is occasional over-plotting of loading-dose points. These points represent overlapping patient ID numbers (at the resolution of the NONMEM plot), not multiple loading doses to the same patient.




Figure 11.3. An index plot of the independent variable, dose amount (AMT). Note the outlier at about ID = 3.

Figure 11.4 replots the same data as figure 11.3 but with the misrecorded values of the data items corrected. Figures 11.5 and 11.6 show the index plots for the other two data items of interest to this data analysis: weight (WT) and Apgar score (APGR).




Figure 11.4. See figure 11.3; the outlier has been corrected.




Figure 11.5. Index plot for weight (WT)



the additions suggested by the diagnostic tools, or when the diagnostic tools fail to suggest any more additions.

The NONMEM runs at this stage, since there will be many of them, should be made as short as possible. To do so, only the estimation, table and scatterplot features need be used; the Covariance Step need not, in general, be run.

#### 4.2. The Minimal Model

As suggested above, the minimal model involves the simplest pharmacokinetic model (ADVAN) likely to fit the data, and the simplest possible structural PK parameter model: each parameter is simply identified with a separate element of  $\theta$ .

At this stage, the statistical model should also be very simple. Only one, or at most two  $\eta$  variables should be defined. These will usually affect (first) the scale parameter (which itself, is often a volume of distribution parameter) and (second) some other parameter influencing the overall kinetics. Since the overall kinetics exhibited in the data will usually be dominated by elimination, the second  $\eta$  should usually modify the rate constant of elimination or clearance. However, some (kinetic) data sets are dominated by absorption or distribution, and in such cases, the second  $\eta$  should probably modify the parameter most affecting these processes. A single  $\varepsilon$  should usually suffice. Both inter- and intra-individual errors can conveniently be modeled as proportional, so that the determination of initial estimates of variances is made easier, and all such estimates are on the same scale, but this is a matter of taste. The model for the phenobarbital data defined in Chapter 2 (figure 2.6) almost fulfills the spirit of these restrictions. However, the inter- and intra-individual error models there are additive, rather than proportional. The minimal model used on the phenobarbital data in this chapter is therefore a modified version of that used in Chapter 2. It is:

$$CL = \theta_1(1 + \eta_1) \quad (11.1a)$$

$$V = \theta_2(1 + \eta_2) \quad (11.1b)$$

$$y = F(1 + \varepsilon_1) \quad (11.1c)$$

In (11.1), it is understood that  $S = V$ , and that  $F$  is the prediction of  $y$  from ADVAN1 using  $CL$  and  $V$ . A control file to NM-TRAN that specifies this model, and instructs NONMEM to produce the desired output is:

```

$PROBLEM PHENOBARB  SIMPLE MODEL (#1)
$INPUT  ID TIME AMT WT APGR DV
$DATA   PHENO
$SUBROUTINE  ADVAN1
$PK
      TVCL=THETA(1)
      CL=TVCL*(1+ETA(1))
      TVVD=THETA(2)
      V=TVVD*(1+ETA(2))
      K=CL/V
      S1=V
$ERROR
      Y=F*(1+ERR(1))
$THETAS  (0, .0105)  (0, 1.05)
$OMEGAS  .25      .25
$SIGMAS  .04
$ESTIMATION
$TABLE          ID TIME AMT WT APGR
$SCATTERPLOT    PRED VS DV UNIT
$SCATTERPLOT    RES  VS (PRED, WT, APGR)
$SCATTERPLOT    WRES VS (PRED, WT, APGR)

```

### 4.3. Use of Constraints

It is important to realize that constraints on elements of  $\theta$  or  $\Omega$  may be part of a model.

For example, constraining clearance to be positive is a modelling choice. One might implement this constraint in NONMEM using a lower bound on the \$THETA record, and this would assure that the estimate of clearance will be positive. It may not be necessary to do this; even without the lower bound, the data might clearly force the estimate to be positive.

Often, however, analysts will constrain the range of a parameter in the belief that doing so will shorten computing time or stabilize the search for the minimum of the objective function. While this benefit may be gained, the data may force the parameter estimate to the constraint boundary even though this boundary may not, in fact, represent a true modeling choice. In this case the proper action is to relax the constraint and rerun the problem. To do otherwise, and leave the parameter estimate to be the boundary value, implies that at the outset the user assumes that the parameter must be within the boundary and elevates the constraint to the status of a modeling choice. If an estimate lies on a boundary, NONMEM will print a warning message (along with the standard message regarding the status of the termination of the Estimation Step). The reader is cautioned to look for such a message, and in general, it is a good idea to check the values of the final estimates against the boundary values. Alternatively, the implementation of constraints that are not intended to represent modeling choices might be used cautiously and only if they really seem necessary to stabilize a search.

### 4.4. Diagnostic Tools

#### 4.4.1. Plot of DV vs PRED

Most useful diagnostic tools are graphical. For an overall sense of the fit, a useful diagnostic plot is DV vs PRED. When there are substantial and systematic deviations from the line of identity, this plot suggests that there are problems with the fit, but it does not suggest what exactly these problems might be or what to do about them. This plot for the fit of the phenobarbital data to model (11.1) is seen in figure 11.7.




Figure 11.7. Predictions from fit of model (11.1) to phenobarbital data vs observations themselves. The line of identity (...) shows where the points should, ideally, fall.

Figure 11.7 reveals that there is a group of points where the observation is much lower than the prediction. To begin to determine why this is so, it will be useful to look at residual plots. Such plots are the basis of the most important of the diagnostic tools.

#### 4.4.2. Residual Plots

As mentioned in Chapter 2, a residual is the difference between an observation and its prediction. The prediction in this case (the same prediction as denoted by PRED) is the population prediction, i.e. the prediction for the typical individual having the given values for all the concomitant variables.

With population data, weighted residuals are often more informative than (plain) residuals. The weighted residuals for an individual are formed by transforming the individual's residuals so that under the population model, and assuming the true values of the population parameters are given by the estimates of those parameters, all weighted residuals



be larger in such individuals, so that predictions are strictly proportional to dose alone and may be too large for these heavier patients.

#### 4.4.2.2. Plot of WRES vs Independent Variable

Another way to see the association between weight (or dose) and the large residuals is to plot the residual against weight, say. Figure 11.9 is this plot, but where, for reasons already discussed, weighted residuals, rather than plain residuals, are used.




Figure 11.9. Plot of weighted residuals vs weight for fit of minimal model to phenobarbital data.

It is clear from figure 11.9, in a way that is particularly compelling, that it is precisely those individuals with the largest weight whose residuals are large and negative. This type of residual plot, where (weighted) residuals are plotted against some independent variable, is the single most useful diagnostic tool.

Systematic patterns of weighted residuals, then, suggest possible model improvements. For an independent variable that already appears in the model, such a pattern may suggest that the way in which it enters the model is incorrect; e.g., it might appear as having a linear influence on a PK parameter, and a curvilinear influence might be better, or it might affect additional PK parameters, beyond those it affects in the current model. An example of this will be seen shortly. For a variable that does not yet appear in the model, as in figure 11.9, such a pattern suggests that the element should appear.

Before examining what happens if patient weight is added to the model, a caution about residual plots is in order. Neither residuals, nor weighted residuals, should ever be

plotted against the observations themselves. Such a plot will always show a correlation, spuriously suggesting a problem with the model. This is most easily appreciated by considering the simple model that gives rise to the constant-valued prediction given by the mean of the observations. All positive residuals (observations greater than prediction) must then be associated with observations greater than the mean, while all negative residuals must be associated with observations less than the mean. Clearly, then, the residuals plotted against the observations must show a line with positive slope. This same type of association, although to a lesser degree, holds true, even in less extreme cases. The phenomenon is illustrated in figure 11.10.




Figure 11.10. Residuals always correlate with the observations themselves; the more so, the less the model explains the data!

#### 4.5. Judging Goodness of Fit

A more complex model is acceptable only if the complexity can be justified by some significant improvement in the fit. To evaluate whether this has been accomplished, several measures should be examined; no single measure suffices.

In the phenobarbital example, based on the finding in figure 11.9, a modified model is suggested. This model, (11.2), has (11.2b)=(11.1b), and (11.2c)=(11.1c), but

$$Cl = (\theta_1 + \theta_3 WT)(1 + \eta_1) \quad (11.2a)$$

which is a full model relative to the reduced model (11.1a), whence (11.2) is a full model relative to the reduced model (11.1).

The model-defining statements to NM-TRAN (\$PK and \$ERROR) now become:

```

$PK
TVCL=THETA (1) +THETA (3) *WT
CL=TVCL* (1+ETA (1) )
TVVD=THETA (2)
V=TVVD* (1+ETA (2) )
K=CL/V
S1=V
$ERROR
Y=F* (1+ERR (1) )

```

We now examine some measures of goodness of fit, and see how (11.2) fares relative to (11.1).

#### 4.5.1. A Global Measure — Change in the Objective Function

A global measure of goodness of fit is, of course, the objective function value based on the final parameter estimates, which, in the case of NONMEM, is minus twice the log likelihood of the data (see Chapter 5, Section 5.2.3). As noted in Chapter 5, if the new model differs from the previous model only by the addition of some new variable(s) (so that the two models form a full/reduced model pair), then the difference in objective function values has a known (approximate) statistical distribution. More informally, during model-building, a fall in objective function value of 4 when a single new parameter is introduced (and no old ones are eliminated) indicates that the new model has substantially improved the overall goodness of fit. Model (11.2) shows a decrease in objective function of 35.2 relative to (11.1), indicating considerable improvement.

#### 4.5.2. Decrease in Unexplained Variability

The purpose of adding independent variables to the model is usually to explain kinetic differences among individuals. This means that prior to adding a variable, such differences were not "explained" by the model, and hence were part of random interindividual variability, although these differences could also have been reflected as a part of random intraindividual variability. Accordingly, elaboration of the model should be accompanied by a decrease in the estimates of the variances in  $\Omega$  and/or  $\Sigma$ .

The estimates of  $\omega_{CL}^2$ ,  $\omega_V^2$ , and  $\sigma^2$  from the fit to Model (11.2) are .057, .12, and .0196, corresponding to coefficients of variation of 24%, 35%, and 14%, respectively. The corresponding values from the fit to (11.1) are .25 (CV=50%), .14 (CV=37%), and .016 (CV=13%), so that a considerable reduction in the variance of clearance is seen.

#### 4.5.3. Improvement in Plots

The last, and most useful, evidence confirming the value of elaborating a model is to find that the pattern(s) in the PRED vs DV and weighted residual plot(s) that suggested the need for the addition have now disappeared. Indeed, when a model is relatively complete, all weighted residual plots should show no pattern: the "unexplained" part of the data should have become featureless random noise.

Figures 11.11 and 11.12 correspond to 11.7 and 11.9, but are from the fit to model (11.2).




Figure 11.11. Predictions from fit of model (11.2) to phenobarbital data vs observations.

Compared to figures 11.7 and 11.9, figures 11.11 and 11.12 indicate an improvement in that the *number* of large negative residuals is clearly reduced in both plots.




Figure 11.12. Plot of weighted residuals vs weight for fit of model (11.2) to phenobarbital data.

#### 4.6. Using the Tools: Further Improvement

##### 4.6.1. An Additional Effect of WT

While all of the above suggests that model (11.2) is superior to model (11.1), figure 11.12 shows a persistent linear relationship between weight and residuals. Thus, the addition of weight to the model for clearance does not fully exploit the information in the variable, weight. An obvious modification to model (11.2) that might deal with this is to have weight affect  $V$  as well as  $CL$ . Accordingly, define model (11.3) such that (11.3a)=(11.2a), (11.3c)=(11.2c), but

$$V = (\theta_2 + \theta_4 WT)(1 + \eta_2) \tag{11.3b}$$

The model-defining portion of the control stream now becomes:

```

$PK
TVCL=THETA (1) +THETA (3) *WT
CL=TVCL* (1+ETA (1) )
TVVD=THETA (2) +THETA (4) *WT
V=TVVD* (1+ETA (2) )
K=CL/V
S1=V
$ERROR
Y=F* (1+ERR (1) )
    
```

When model (11.3) is fit to the data, the objective function decreases fully 126 relative to model (11.2). Moreover, the estimates of  $\omega_{CL}^2$ ,  $\omega_V^2$ , and  $\sigma^2$  are now .050 (CV=22%), .028 (CV=17%), and .011 (CV=10%), indicating a further substantial decrease in unexplained variation. The plots corresponding to 11.7/11.11 and 11.9/11.12 are shown as figures 11.13 and 11.14.




Figure 11.13. Predictions from fit of model (11.3) to phenobarbital data vs observations.

Now there are no obvious discrepancies, and the plot of weighted residuals vs *WT* shows no pattern, so that it is likely that no further use of weight in the model is required.




Figure 11.14. Plot of weighted residuals vs weight for fit of model (11.3) to phenobarbital data.

#### 4.6.2. The Effect of APGR

The structural model building stage is not over until all available independent variables have been examined for influence, and there is one additional variable, the Apgar score, that has not yet been seriously considered. A plot of the weighted residuals from the fit to model (11.3) vs *APGR* is shown in figure 11.15.




Figure 11.15. Plot of weighted residuals vs Apgar score for fit of model (11.3) to phenobarbital data.

There is a weak suggestion from figure 11.15 that for *APGR* less than 3, the weighted residuals tend to be negative. Accordingly, a new model (11.4) can be proposed, which is identical to (11.3) except that

$$V = \begin{cases} \theta_2 + \theta_4 WT, & \text{if } APGR > 2 \\ (\theta_2 + \theta_4 WT)\theta_5, & \text{if } APGR \leq 2 \end{cases} (1 + \eta_2) \quad (11.4b)$$

The relevant statements for NM-TRAN now become:

```

$PK
TVCL=THETA (1) +THETA (3) *WT
CL=TVCL* (1+ETA (1) )
TVVD=THETA (2) +THETA (4) *WT
IF (APGR .LE. 2) TVVD=TVVD*THETA (5)
V=TVVD* (1+ETA (2) )
K=CL/V
S1=V
$ERROR
Y=F* (1+ERR (1) )
    
```

When this model is fit to the data,  $\theta_5$  is estimated to be 1.18, implying that indeed, the volumes of distribution for infants with Apgar scores less than 3 are typically 18% higher than those of infants (of the same weight) with higher Apgar scores. The measures of improvement are now marginal, however: the objective function decreases only 3.7, and the decreases in the variances are all less than 10% of their previous values, with the variance of  $\varepsilon$  actually increasing a few percent. Inspection of figure 11.6 suggests a reason for this: note that only 5 distinct individuals (separate symbols) have Apgar scores less than 3. There is simply not very much information about babies with low Apgar scores in this data set.

For completeness, figure 11.16 corresponds to figure 11.5, but using model (11.4), and now shows no distinct pattern.




Figure 11.16. Plot of weighted residuals vs Apgar score for fit of model (11.4) to phenobarbital data.

The stage of building the structural model is now complete.

## 5. Building the Statistical Model

### 5.1. Judging Among Alternatives

NONMEM can provide estimates of the  $\eta$  variables for each individual (see Chapter 12, Sections 4.11-4.13). Plots of the estimated interindividual differences, which can be regarded as interindividual residuals, can be obtained. Plots of these residuals (associated with a particular PK parameter) versus the values of an independent variable provide

further help in building the structural part of the parameter model. Moreover, a plot of these residuals versus the typical values of the parameter (whose values depend on covariates) also provides help in building the model for interindividual differences themselves. For example, if interindividual differences are modeled with the additive model, but the plot shows a linear trend (in the boundaries enveloping the residuals), this suggests that a proportional model be tried.

Lastly, help can be provided in the selection of a model for intraindividual error. Predictions of concentrations, and hence residuals, based on estimates of individuals'  $\eta$ s, can be computed, and the residuals can be plotted versus the predictions. (This requires advanced techniques.) Again, if intraindividual errors are modeled with the additive model, but the plot shows a linear trend in the envelope, this suggests that a proportional model be tried.

The statistical model is usually of less interest than the structural model, so that frequently all that is sought is an adequate model, not necessarily the correct one, nor does one care whether the estimates of the random effects parameters (the elements of  $\Omega$  and  $\Sigma$ ) are particularly precise. Sometimes, however, the variability in the random effects is of genuine primary interest. In such cases more attention must be paid to building the random effects model. This, however, may not be easy because it is an unfortunate, but unavoidable fact, that a great deal more data is needed to estimate random effects parameters with a given precision than is needed to estimate fixed effect parameters with comparable precision.

The tools used to elaborate the statistical model are similar to those used for elaborating the structural model: alternative models are assessed using (available) residual plots, especially ones like those just discussed, and relative changes in the objective function.

### 5.1.1. Unexplained Variability

When the statistical model is developed, a new  $\eta$  variable may be added, or an old  $\eta$  variable used differently. Then differences in the  $\omega$ s between models cannot really be used to judge the benefit of the addition, and this evaluation tool becomes less useful. On the other hand, an addition of an  $\eta$  might be confirmed by a reduction in the estimates of the variances in  $\Sigma$ , the variances of the random components in the model for residual error. However, there is one sure sign that too many  $\eta$ 's are in the model: NONMEM may estimate one or more of the  $\omega$ s to be zero, or very nearly zero. This can be disconcerting, particularly if the  $\eta$  variable is the only such variable affecting Volume, for instance, as then this estimate seems to suggest that with respect to Volume, there is no interindividual variability in the population whatsoever! The result should not be interpreted this way, however. Rather, assuming the  $\eta$  affecting Volume is the one most recently added, it indicates that given the previous statistical model, no *additional* variability *needs* to be ascribed to volume to explain all the variability seen. The data cannot support such an elaborate statistical model, and a simpler model, such as the previous one, must be used.

### 5.1.2. Residual Plots

The most important residual plot is now a plot of the weighted residuals against predictions, where a pattern in the shape of the outer envelope of points can indicate deficiencies in the statistical model (recall that a distinct pattern in the local "average" residual vs the predictions would indicate a defect in the structural model). This can be illustrated using the phenobarbital data. Figure 11.17 shows the plot of weighted residuals vs predictions for model (11.4), and figure 11.18 shows the same plot for a modified model, (11.5), identical to (11.4) except for

$$y = F + \varepsilon_1 \tag{11.5c}$$

Only the \$ERROR statements of the control stream change:

```
$ERROR
Y=F+ERR(1)
```




Figure 11.17. Plot of weighted residuals vs predictions for fit of model (11.4) to phenobarbital data (proportional intraindividual error).

Although the plots do not differ greatly, there is a small suggestion in figure 11.18 that the envelope of weighted residuals is somewhat V-shaped with the apex of the V at PRED=0 (but which does not show on the plot), while in figure 11.17 the weighted residuals seem more homogeneous, and their magnitude seems less dependent on that of the predictions. That this impression is valid is suggested also by the increase in objective function of 7.6 in going from model (11.4) to (11.5).




Figure 11.18. Plot of weighted residuals vs predictions for fit of model (11.5) to phenobarbital data (additive intraindividual error).

## 6. Refine Model

The goal of this stage is to check whether the model is as parsimonious as reasonable, since if it is not, certain important parameters may not be estimated with as good precision as can be achieved. Although up to this stage, one tries to avoid adding parts to the model which are not well supported by the data, it is nonetheless possible that a part added at one stage may seem unnecessary after adding another part at a later stage. Perhaps, for example, weight affects  $V$ , and  $V$  and  $CL$  are correlated in the population (independent of weight), but first the influence of weight on  $CL$  is examined, and later its influence on  $V$  is examined (this was the order illustrated above). Then initially, weight might appear to influence  $CL$ , although this influence might only derive from the correlation between the two PK parameters. Later, after the influence of weight on  $V$  is a part of the model, the influence of weight on  $CL$  might disappear. One wants to check this possibility and, if indicated, eliminate the influence of weight on  $CL$  from the model at the stage now being described. The basic technique at this stage, is to run the Covariance Step with the best model thus far, and look for parameters with confidence intervals that include the parameter's null value, i.e., the value that causes the parameter to be effectively deleted from the model. A null value is usually zero (for a parameter quantifying an additive portion of the model), and sometimes unity (for a parameter quantifying a multiplicative part of the model). If such parameters are found, then one at a time, each

can be set to its null value and the consequences examined as discussed above for the earlier model building stages.

Figures 11.19 and 11.20 show two pages of NONMEM output from a run fitting model (11.4) to the phenobarbital data, and implementing the Covariance Step. Figure 11.19 shows the final parameter estimates, and 11.20, their standard errors.

```

*****
*****
***** FIRST ORDER *****
***** FINAL PARAMETER ESTIMATE *****
*****
*****
THETA - VECTOR OF FIXED EFFECTS PARAMETERS *****
      TH 1      TH 2      TH 3      TH 4      TH 5
      4.77E-05  2.80E-02  4.64E-03  9.52E-01  1.18E+00

OMEGA - COV MATRIX FOR RANDOM EFFECTS - ETAS *****
      ETA1      ETA2
ETA1  4.58E-02
ETA2  0.00E+00  2.63E-02

SIGMA - COV MATRIX FOR RANDOM EFFECTS - EPSILONS ****
      EPS1
EPS1  1.10E-02

OMEGA - CORR MATRIX FOR RANDOM EFFECTS - ETAS *****
      ETA1      ETA2
ETA1  2.14E-01
ETA2  0.00E+00  1.62E-01

SIGMA - CORR MATRIX FOR RANDOM EFFECTS - EPSILONS ***
      EPS1
EPS1  1.05E-01

```

Figure 11.19. Parameter estimates from fit of model (11.4) to phenobarbital data.

```

*****
*****
***** FIRST ORDER *****
***** STANDARD ERROR OF ESTIMATE *****
*****
*****
THETA - VECTOR OF FIXED EFFECTS PARAMETERS *****
      TH 1      TH 2      TH 3      TH 4      TH 5
      1.18E-03  9.69E-02  8.90E-04  7.77E-02  8.38E-02

OMEGA - COV MATRIX FOR RANDOM EFFECTS - ETAS *****
      ETA1      ETA2
ETA1  2.24E-02
ETA2  .....  7.10E-03

SIGMA - COV MATRIX FOR RANDOM EFFECTS - EPSILONS ****
      EPS1
EPS1  2.01E-03

OMEGA - CORR MATRIX FOR RANDOM EFFECTS - ETAS *****
      ETA1      ETA2
ETA1  5.24E-02
ETA2  .....  2.19E-02

SIGMA - CORR MATRIX FOR RANDOM EFFECTS - EPSILONS ***
      EPS1
EPS1  9.59E-03

```

Figure 11.20. Standard errors of parameter estimates from fit of model (11.4) to phenobarbital data.

## 6.1. Use of Standard Errors and Confidence Intervals

The null values of  $\theta_1$  through  $\theta_4$  are zero, while the null value of  $\theta_5$  is unity. Using the numbers from the figures, it is easily seen that for  $\theta_1$  and  $\theta_2$ , the parameter estimate minus the null value is a fraction of one standard error, and hence  $\theta_1$  and  $\theta_2$  may not be different from their null values.

As indicated in Chapter 5 (Section 4.2.2), an approximate (two-sided) 95% confidence interval for a parameter estimate is

$$\hat{\theta} \pm Z_{.975} SE$$

where  $Z_{.975}$  is the 97.5 percentile of the normal distribution ( $\approx 2$ ) and  $SE$  is the standard error of the parameter estimate. Therefore, for  $\theta_5$ , a 95% confidence interval is given by  $1.18 \pm (2)(.0836)$ , which is 1.01 - 1.35. This range only barely misses including the null value, unity, indicating, as did the marginal change in the objective function associated with going from (11.3) to (11.4), that one cannot be very sure of the influence of Apgar score on volume.

Finally, note the magnitudes of the standard errors of the other parameters' estimates. For  $\theta_3$  it is 16% of the estimate (i.e., the CV of the estimation error is 16%), for  $\theta_4$  it is 7.8%, while for the 2 elements of  $\Omega$  it is 49% and 27%. This pattern is typical: the precision of the fixed effect parameter estimates is considerably greater than that of the random effects parameter estimates, except when the number of individuals sampled is enormous.

## 6.2. A Model Refinement

Based on the observation that  $\theta_1$  and  $\theta_2$  may be equal to their null values, these parameters are next set to their null values, defining a new (and final) model,

$$Cl = \theta_3 WT(1 + \eta_1) \quad (11.6a)$$

$$V = \begin{cases} \theta_4 WT, & \text{if APGR} > 2 \\ (\theta_4 WT)\theta_5, & \text{if APGR} \leq 2 \end{cases} (1 + \eta_2) \quad (11.6b)$$

$$y = F(1 + \varepsilon_1) \quad (11.6c)$$

which is communicated to NM-TRAN without changing the \$PK or \$ERROR statements, but simply by fixing the values of  $\theta_1$  and  $\theta_2$  to 0, using the FIXED option in the \$THETA record:

```

$PK
  TVCL=THETA (1)+THETA (3) *WT
  CL=TVCL* (1+ETA (1) )
  TVVD=THETA (2)+THETA (4) *WT
  IF (APGR.LE.2) TVVD=TVVD*THETA (5)
  V=TVVD* (1+ETA (2) )
  K=CL/V
  S1=V

$ERROR
  Y=F* (1+ERR (1) )

$THETAS (0 FIXED) (0 FIXED) (0, .0018) (0, .43) 1.0

```

When this model is fit to the data, the objective function increases only .12 (a trivial change). However, now the CV's of the estimation errors in  $\theta_3$  and  $\theta_4$  are 4.4% and 2.5% respectively.

This is the main point of this section on model refinement; deletion of imprecisely estimated parameters can improve the precision of other parameter estimates. This is related to the correlation between parameter estimation errors, mentioned in Chapter 5. With little data from patients who weigh virtually nothing,  $\theta_1$  and  $\theta_2$ , the values of CL and V for such patients, are not well estimated (regardless of the fact that one might rationally model the values of these parameters to be 0), and so their parameter estimates are largely dependent on the estimates of the slope parameters  $\theta_3$ ,  $\theta_4$ , and  $\theta_5$ . The correlation

between the estimates of  $\theta_1$  and  $\theta_3$  is  $-.96$ , and that between  $\theta_2$  and  $\theta_4$  is  $-.95$ . Of course, since slope itself can only be well determined when the intercept is well determined, the parameter estimates of  $\theta_3$ ,  $\theta_4$ , and  $\theta_5$  themselves largely depend on the estimates of  $\theta_1$  and  $\theta_2$ ; correlations are symmetric. In other words, neither type of parameter (intercept or slope) is very precisely estimated since the estimate of each depends on the value assigned to the other. But if one of the parameters can be eliminated from the model (i.e., rationally assigned a fixed value), then the other can be more precisely determined.

### **7. Testing the Model**

This step is undertaken when it is desirable to assign p-values to the hypothesis test of one or more parameter values against null values. The procedure is as follows: Beginning with the final model resulting from all previous steps, each parameter to be tested is set, in turn, to its null value, and the reduced model is fit to the data (only the Estimation Step need be run; no tables, graphs or covariance output are necessary). A likelihood ratio test is done using the difference in minimum objective function values obtained with both the full (original) and reduced models. In doing this one must be careful that in the Estimation Step with a reduced model, no parameter other than the one under test (and those which are already constrained to fixed values under the full model) be constrained to a fixed value.

## Chapter 12 - Brief Descriptions of Other Features

### 1. What This Chapter is About

This chapter briefly describes a variety of features of PREDPP and NONMEM that are somewhat advanced for this text but are of interest to most users of NONMEM. References are given to other documents where additional information can be found. Section 2 is concerned with PREDPP, Section 3 is concerned with user-written PREDs, and Section 4 describes general NONMEM features. Section 5 contains an example that includes several of the advanced features. Descriptions of NM-TRAN control records in Section 4 have been augmented with sections headed "More about ...". These contain additional details, plus new options for NONMEM 7.3. Section 6 is new for NONMEM 7.3. It contains a supplemental list of features through NONMEM 7.5, including features from previous releases that are not otherwise discussed in this guide.

Note that wherever \$PK, \$ERROR, \$DES, \$AES, \$MODEL, \$MIX, \$INFN, \$TOL and \$PRED statements are referred to below, user-written subroutines PK, ERROR, DES, AES, MODEL, MIX, INFN, TOL and PRED can be used instead.

### 2. Advanced Features of PREDPP

#### 2.1. Pharmacodynamic Modeling Using the \$ERROR Record

\$ERROR statements may modify the value of F, the scaled drug concentration. They may also introduce new  $\theta$  and  $\eta$  variables. This allows pharmacodynamic modeling to be performed using PREDPP. Such models occur when a study involves measurement of a drug effect, such as blood pressure. A proposed model might relate the predicted effect to a pharmacokinetic quantity such as plasma level. PREDPP can be used to model  $C_p$  as is usual, and the predicted effect can be computed in the \$ERROR statements.

For example, suppose that a modified version of the phenobarbital data of Chapter 2 includes observations of some drug effect (in this case, perhaps a measure of the degree of sedation) but none of the concentration observations. The dose event records are the same as those of the earlier example. Suppose that the drug concentrations from each individual have been used to estimate that individual's K and V parameters, and that these estimates are now included on every event record for the individual. Finally, suppose that the proposed structural model for the effect, E, is an "E-max" model:

$$E = E_{\max} \frac{C_p}{C_{50} + C_p}$$

where here  $C_p$  is understood to mean the prediction of an individual's drug concentration in the plasma, and  $E_{\max}$  and  $C_{50}$  are PD (pharmacodynamic parameters) modeled as

$$E_{\max} = \theta_1 + \eta_1$$

$$C_{50} = \theta_2 + \eta_2$$

To fit this data we can use the control statements of figure 12.1. To obtain initial parameter estimates, let us assume that the following is observable in the data. The average value of all effect measurements is about 50. Across individuals, the average value of the largest effect measurement within each individual's data is about 100, and the average value of the individual's observed concentration at about half this largest measurement is about 20. (This is seen when concentration measurements and effect measurements are

examined together.) Let us also assume 20% random interindividual variability in  $E_{\max}$  and  $C_{50}$  and 4% intraindividual variability in the observation. From this we obtain initial estimates of 100 and 20 for  $\theta_1$  and  $\theta_2$ ,  $(100 \times .2)^2$  for  $\Omega_{11}$ ,  $(20 \times .2)^2$  for  $\Omega_{22}$ , and  $(50 \times .04)^2$  for  $\Sigma$ .

This example is examined again in in Section 3.2, which shows the use of \$PRED statements, and in Section 5, which shows how observed concentrations and effects can be fit simultaneously.

References: Users Guide VI (PREDPP) IV.B.2

```

$PROBLEM PHARMACODYNAMIC MODEL USING $ERROR STATEMENTS
$INPUT   ID TIME AMT INDK INDV DV
$DATA    EFFDATA
$SUBROUTINE ADVAN1
$PK
    K=INDK
    V=INDV
    S1=V
$ERROR
    EMAX=THETA (1) +ETA (1)
    C50=THETA (2) +ETA (2)
    E=EMAX*F / (C50+F)
    Y=E+ERR (1)

$THETA   100   20
$OMEGA   400   16
$SIGMA   4
$ESTIMATION

```

Figure 12.1. The input to NONMEM-PREDPP for analysis of effect observations.

## 2.2. Other Pharmacokinetic Models: ADVAN5-9, ADVAN13-18

Appendix 1 lists ADVAN routines for the most commonly-used pharmacokinetic models.

Other ADVAN routines are:

ADVAN5 (General Linear)

ADVAN6 (General Nonlinear)

ADVAN7 (General Linear with Real Eigenvalues)

ADVAN8 (General Nonlinear Kinetics with Stiff Equations)

ADVAN9 (General Nonlinear Kinetics with Equilibrium Compartments)

ADVAN13 (General Nonlinear Kinetics With Stiff/Nonstiff Equations using LSODA)(nm71)

ADVAN14 (General Nonlinear Kinetics With Stiff/Nonstiff Equations using CVODES)(nm74)

ADVAN15 (General Nonlinear Kinetics with Equilibrium Compartments using IDAS)(nm74)

ADVAN16 (General Nonlinear Kinetics with Stiff/Nonstiff and Delay Equations using RADAR5 (nm75)

ADVAN17 (Gen. Nonl. Kin. with Stiff/Nonstiff and Delay Equations and Equil. Comp. using RADAR5)(nm75)

ADVAN18 (General Nonlinear Kinetics with Nonstiff and Delay Equations using DDE\_SOLVER (nm75)

With the general methods the user defines a model of up to 999 compartments using special options of the \$MODEL record. For a linear model (ADVAN5 and ADVAN7), it is sufficient to specify (directed) compartmental connections and to compute their rate constant parameters with \$PK statements. ADVAN 5 and 7 make use of numerical approximations to the matrix exponential. For a nonlinear model (ADVAN6, ADVAN8, ADVAN9, ADVAN13, ADVAN14, ADVAN15, ADVAN16, ADVAN17, ADVAN18), differential equations must be supplied to govern the kinetics, via \$DES statements. It is possible to specify initial conditions for the differential equations using the I\_SS (Initial Steady State) feature; Reserved variable ISSMOD may be used.

For ADVAN9, ADVAN15 and ADVAN17, algebraic equations may also be supplied via \$AES statements.

The use of the term 'nonlinear' with ADVAN 6, 8, 9, 13, 14, 15, 16, 17, 18, only indicates that a system of any type of first-order differential equations is allowed; such equations could be linear or non-linear.

In all cases, the basic features of PREDPP described in Chapter 7 are still available, such as the ability to introduce doses of any kind to any compartment of the model. It should be noted that the general ADVAN routines are relatively slow. For example, when a general method is used for a model identical to that of an analytic method (ADVAN1 through ADVAN4 or ADVAN10 through ADVAN12) the run time increases, usually by an order of magnitude.

Some ADVAN and SS routines must be told the number of accurate digits that are required in the computation of drug amounts, i.e., the relative tolerance. They may also be told the absolute tolerance. With some ADVAN and SS, the tolerances may be specified for each compartment. They may be specified by \$SUBROUTINES record options TOL, ATOL, SSTOL, SSATOL; by the corresponding options of the \$TOL record; or by user-written subroutine TOL (which may also specify tolerances by NONMEM Step). Option TOL (relative tolerance) may also be specified on the \$COVARIANCE record. Option ATOL (absolute tolerance) may also be specified on \$ESTIMATION and \$COVARIANCE records.

See Guide NONMEM 7, "Controlling the Accuracy of the Gradient Evaluation and Individual Objective Function Evaluation"

With ADVAN9, ADVAN13, ADVAN14, and ADVAN15, reserved variable MXSTEP may be used to set the number of integration steps.

With \$AES, \$AESINIT statements are also required. If there is no TIME data item, \$AESINIT may specify a calling protocol for the AES subroutine. (See 2.7 below for a discussion of calling protocols.)

CALLFL=-1:

Call ADVAN9 and ADVAN15 and AES with every event record (default)

CALLFL=1:

Call ADVAN9 and ADVAN15 and AES once per individual record.

Equivalent calling protocol phrases are:

(EVERY EVENT)

(ONCE PER IR)

References: Users Guide VI (PREDPP) VI, VII

References: Users Guide IV (NM-TRAN) V.C.3, 4, 7-10

### 2.3. Zero-Order Bolus Doses

Instantaneous bolus doses, which have AMT>0 and RATE=0, are described in Chapter 6. Such doses appear instantaneously in the dose compartment. Zero-order bolus doses are doses that enter the dose compartment via a zero-order process (in the same manner as do infusions) except that the rate or duration of the process is computed with \$PK statements. When the RATE data item has the value -1, then the \$PK statements must include an assignment statement for an additional PK parameter, Rn (the "modeled rate for compartment n"), whose value gives the rate of entry of the drug during the interval of time between the last event record and the current one. There is a different such parameter for every compartment receiving a zero-order bolus dose. When the RATE data item has the

value -2, then the \$PK statements must include an assignment statement for an additional PK parameter, Dn (the "modeled duration for compartment n"), whose value at the time of the dose event gives the duration time of the dose. The rate and duration parameters can be modeled like any other PK parameters; in particular, the assignment statements can involve  $\theta$ 's which are to be estimated. These parameters can be used to model the drug release rate or dissolution time of a tablet or capsule.

Steady-state levels involving zero-order bolus doses can be computed.

Steady-state with constant infusion was described in Chapter 6. Steady-state infusions may also have modeled rates (i.e., the RATE data item may be -1).

References: Users Guide VI (PREDPP) III.F.3, F.4

#### **2.4. The Additional Dose Data Item: ADDL**

ADDL is a dose-related data item that is used to request that a given number of additional doses, just like the dose specified on the event record, be added to the system at a regular time interval, starting from the time on the event record. PREDPP itself adds these doses at the appropriate future times; no actual dose event record is generated by the Data Pre-processor or by PREDPP. A positive integer value in ADDL specifies how many additional doses (i.e., in addition to that already specified in the event record) are to be given, and the value in the II (interdose interval) data item (which is required) specifies the time interval between doses.

ADDL may be non-zero on a steady-state dose event record (except for steady-state infusions), in which case additional doses are given, maintaining the dosing regimen into the future. Non-steady-state kinetic formulas are used to advance the system between each additional dose. Reserved variables DOSTIM (the time of a lagged dose or additional dose to which the system is being advanced) and DOSREC (the dose record corresponding to the dose entering at DOSTIM) may be used.

See also Section 2.6 below.

References: Users Guide VI (PREDPP) V.K

#### **2.5. Lagged doses: the ALAG Parameter**

PREDPP permits an additional PK parameter called an absorption lag time. One such parameter can be defined for each compartment and applies to all doses to that compartment. It gives the amount of time that a dose is held as a "pending" dose. When the absorption lag time has expired, the dose is input into the system. In effect, the value of the absorption lag time parameter is added to the value of the TIME data item on the dose event record. With NM-TRAN, recognized names for absorption lag time parameters have the form ALAGn, where n is the compartment number. Reserved variables DOSTIM (the time of a lagged dose or additional dose to which the system is being advanced) and DOSREC (the dose record corresponding to the dose entering at DOSTIM) may be used.

See also Section 2.6 below.

See Guide VI, Chapter V, Note 3 for the effect of ALAGn with Steady-State doses.

References: Users Guide VI (PREDPP) III.F.6

References: Users Guide IV (NM-TRAN) V.C.5

#### **2.6. Model Event Times: MTIME**

Model event times MTIME(i) are additional PK parameters defined in the PK routine or \$PK block. A model event time is not associated with any compartment, but, like an

absorption lag time, defines a time to which the system is advanced. When the time is reached, indicator variables are set and a call to PK is made. At this call (and/or subsequent to this call) PK or DES or AES or ERROR can use the indicator variables to change some aspect of the system, e.g., a term in a differential equation, or the rate of an infusion. Reserved variables MNEXT, MPAST, MNOW, MTDIFF may be used.

MTIME does not apply to Steady-State doses. See Guide VI, Chapter V, Note 4.

## 2.7. Controlling Calls to PK and ERROR

In order to evaluate the \$PK and \$ERROR statements, PREDPP calls the PK and ERROR subroutines. By default, the subroutines are called with every event record. PREDPP may be instructed to limit calls to certain event records in order to save the computing time involved with unnecessary calls (e.g. when the PK parameters do not vary from event record to event record within an individual). It is also possible to cause the PK subroutine to be called at times which do not correspond to any actual event record.

Using NM-TRAN, calls to PK are controlled by the presence of one of the following pseudo-statements, at the start of the \$PK block:

CALLFL=-2:

call with every event record, at additional and lagged dose times, and at modeled event times.

CALLFL=-1:

call with every event record (default).

CALLFL=0:

call with the first event record of each individual record and with new values of TIME.

CALLFL=1:

call once per individual record.

A calling protocol phrase may be used instead of a pseudo-statement. A calling protocol phrase may use upper- or lower-case characters. It must be enclosed in parentheses. NM-TRAN can understand minor variations in the wording. E.g., the word "CALL" and prepositions such as WITH can be omitted. Here are calling protocol phrases equivalent to the above four pseudo-statements, respectively.

(CALL WITH NON-EVENT TIMES)

(CALL WITH EVERY EVENT RECORD)

(CALL WITH FIRST EVENT RECORD AND NEW TIME)

(CALL ONCE PER INDIVIDUAL RECORD)

The choice CALLFL=-2 (CALL WITH NON-EVENT TIMES) is intended to be used when PK parameters Dn and/or Fn apply to additional or lagged doses *and* the model for these parameters depends on some time-varying concomitant variable such as type of drug preparation or patient weight. By default, the values of the PK parameters which apply to the dose are those values computed by PK with the first event record having a value of TIME greater than the time at which the dose actually enters the system (the additional or lagged dose time). However, if PREDPP is instructed to also call PK at the additional or lagged dose time, then the values of the PK parameters are those values computed at these special calls. At such calls, PK has available to it information from the initiating dose event record itself, and information from the two event records whose TIME values bracket the additional or lagged dose time. Along with CALLFL=-2 in the \$PK block, the NM-TRAN \$BIND record may be useful; see Users Guide IV.

Using NM-TRAN, calls to ERROR are controlled by the presence of one of the following pseudo-statements at the start of the \$ERROR block:

CALLFL=-1:

call with every event record (default).

CALLFL=0: call with observation events only.

CALLFL=1: call once per individual record.

A calling protocol phrase may be used instead of a pseudo-statement. As in the \$PK block, the calling protocol phrase may use upper- or lower-case characters and must be enclosed in parentheses.

Here are calling protocol phrases equivalent to the above three pseudo-statements, respectively.

(CALL WITH EVERY EVENT RECORD)

(CALL WITH OBSERVATION EVENTS)

(CALL ONCE PER INDIVIDUAL RECORD)

NM-TRAN automatically instructs PREDPP to limit calls to ERROR to once per *problem* for the simple error models discussed in Chapter 8, Sections 3.1 and 3.2:

**Y=F+ERR (1)**

**Y=F+F\*ERR (1)**

**Y=F\* (1+ERR (1) )**

**Y=F\*EXP (ERR (1) )**

During the Simulation Step, PREDPP ignores any limitation and calls the ERROR sub-routine with every event record.

Even when calls to PK and/or ERROR are limited, the CALL input data item can be used to force additional calls for specific event records as needed.

References: Users Guide VI (PREDPP) III.B.2, III.H, IV.C, V.J

References: Users Guide IV (NM-TRAN) V.C.5, C.6

## 2.8. Output-Type Compartments

With all versions of PREDPP output-type compartments may be defined using the \$MODEL record. Suppose there is a compartment named METABURI (for metabolite in urine). If it is to be an output-type compartment, it must be defined as follows:

**\$MODEL COMP=(METABURI, NODOSE, INITIALOFF)**

The compartment is initially off, may be turned on and off, and may not receive a dose. Just as with the default output compartment, CMT may be negative on an observation record, allowing the observation to be obtained, and then the compartment turned off, with a single record. There may be more than one such compartment, in addition to the default output compartment. An output-type compartment must be turned on with an other-type event record in order to start accumulating drug. An output-type is not computed by mass-balance, but must instead be computed explicitly by the ADVAN routine, e.g., using a differential equation when a general non-linear model is used.

For an example, see Chapter 6, Section 9.

| ID | TIME | EVID | UVOL | DV   | CMT | AMT |
|----|------|------|------|------|-----|-----|
| 1  | 9.50 | 0    | 75   | .058 | -3  | 0   |

With ADVAN2, compartment 3 is the default compartment for output, and the observation at TIME 9.50 may have CMT=-3. But suppose a general linear or non-linear model

is used (ADVAN5,6,7,8,9,13) and there are more than 3 user-defined compartments.

If the \$MODEL statement describes the 3d. compartment as simply

```
$MODEL COMP=NAME
```

then the default compartment attributes apply (initial on, off/on allowed, dose allowed) and the compartment is not an output-type compartment. PREDPP produces this error message for data record 3:

```
SPECIFIED COMPARTMENT MAY NOT BE TURNED OFF WITH AN OBSERVATION RECORD
```

There are two ways to avoid this error message. First, it is always possible (for any compartment that may be turned off, even the output compartment) to use two records instead of one, e.g., first the observation, then a record with EVID=2 that turns off the compartment:

```
1  9.50  0  75  .058  3  0
1  9.50  2  0   0   -3  0
```

Alternately, it is possible to leave the data as-is, and change the \$MODEL statement so that compartment 3 is an output-type compartment.

## 2.9. Transgeneration of Input Data: the INFN Subroutine

NONMEM may be used to modify the data records before any computations are performed and also after all computations have been performed. This is referred to as transgeneration of the data. Transgeneration at the beginning of a problem can be used, for example, to change weight-normalized doses to unnormalized doses. PREDPP allows the user to supply a subroutine called INFN or a \$INFN block of abbreviated code ("initialization/finalization") in which transgeneration can be performed. (The PREDPP library includes a default INFN subroutine which does nothing.)

The NONMEM PASS subroutine is used for transgeneration. \$INFN and \$PRED code may use the following statements to process each record of the data set. ICALL values may be 0, 1 or 3, for run initialization, problem initialization, and problem finalization, respectively.

```
IF (ICALL == 3) THEN
DOWHILE (DATA)
  . . .
ENDDO
ENDDO
```

Reserved variable PASSRC may be of interest.

References: Users Guide VI (PREDPP) VI.A

## 3. User-written PRED Subroutines

It is not necessary to use PREDPP with NONMEM. Either \$PRED statements or a user-written PRED subroutine may be used in place of PREDPP to supply NONMEM with predicted values for the DV data item according to some (not necessarily pharmacokinetic) model. An example using \$PRED statements is given here. A special caveat applies to user-written PRED subroutines that are recursive: see 4.6 below.

References: Users Guide I (Basic) C.2

### 3.1. Required Data Items

The only required data items when PREDPP is not used are the NONMEM data items DV, MDV, and ID. When PREDPP is used, the Data Preprocessor is able to recognize

which records contain observed values and which do not, and it supplies the MDV data item if it is not already present in the data file. When PREDPP is not used, the Data Pre-processor cannot do this. The input data file must already contain the MDV data item if it is needed, i.e., if the DV item of some data record does not contain a value of an actual observation.

If \$PRED statements are used, they must calculate a variable called Y, using input data items and NONMEM's  $\theta$ ,  $\eta$ , and (for population models)  $\varepsilon$  vectors in the calculation.

References: Users Guide I (Basic) B.1

References: Users Guide IV (NM-TRAN) III.B.8

### 3.2. An Example of \$PRED Statements: Pharmacodynamic Modeling

The syntax of \$PRED statements is essentially the same as discussed for \$PK and \$ERROR statements. \$PRED statements can be used for simple pharmacokinetic and pharmacodynamic models. In figure 12.1 above an example was given of pharmacodynamic modeling using \$ERROR statements. Suppose that in that example, drug concentration is always measured at the same time as drug effect. Suppose too, that rather than input the individuals' values of K and V and use them to compute a predicted drug concentration for the individual, the observed drug concentration itself is used in the Emax model. This means that the the observed concentrations are again incorporated into the data, but now as values of an independent variable, rather than as the DV data item. This also means that a pharmacokinetic model is not needed, and therefore, PREDPP is not needed either. Figure 12.2 shows the control stream for this new example.

```

$PROBLEM A SIMPLE PHARMACODYNAMIC MODEL
$INPUT ID TIME CP DV
$DATA EFFDATA
$PRED
  EMAX=THETA(1)+ETA(1)
  C50=THETA(2)+ETA(2)
  E=EMAX*CP/(C50+CP)
  Y=E+ERR(1)
$THETA 100 20
$OMEGA 400 16
$SIGMA 4
$ESTIMATION

```

Figure 12.2. The input to NONMEM including \$PRED statements for analysis of effect data.

## 4. Advanced Features of NONMEM

### 4.1. Full Covariance Matrices: \$OMEGA BLOCK and \$SIGMA BLOCK

In the examples of Chapter 2 and 9, there appeared statements such as:

```
$OMEGA .0000055, .04
```

This is an example of the specification of initial parameter estimates for a variance-covariance  $\Omega$  matrix which is constrained to be *diagonal*. Initial estimates are given for the variances of  $\eta_1$  and of  $\eta_2$ . The covariance between  $\eta_1$  and  $\eta_2$  is constrained to be 0, i.e.,  $\omega_{12} = cov(\eta_1, \eta_2) = 0$ . Another way of writing this statement is:

```
$OMEGA DIAGONAL(2) .0000055, .04
```

The option DIAGONAL(2) states explicitly that the block contains two  $\eta$ s and that it has diagonal form.

If the data supports the possibility that  $\eta_1$  and  $\eta_2$  covary with each other, it may be useful to model  $\Omega$  as being unconstrained and allow NONMEM to estimate the covariance. A special form of the \$OMEGA record is used, in which initial values are supplied for both variances and the covariance. For example:

```
$OMEGA BLOCK(2) .0000055, .0000001, .04
```

The option BLOCK(2) states that there are two  $\eta$  variables in the block, and that covariance is to be estimated. The new element is  $\omega_{12} = \omega_{21} = cov(\eta_1, \eta_2) = cov(\eta_2, \eta_1) = 1 \times 10^{-7}$ .

\$OMEGA BLOCK is used for both population and individual studies, i.e., it is the same whether  $\eta$  is used in the first case in a model for residual error or is used in the second case in a model for random interindividual error. In a population study, if there is more than one  $\varepsilon$  variable, and the model allows these variables to covary, then \$SIGMA BLOCK is used in a similar manner.

The initial estimates of even more complicated  $\Omega$  and  $\Sigma$  matrices may be given using multiple \$OMEGA and \$SIGMA records. For example, the initial estimates of a mixture of correlated and uncorrelated random variables may given. Also, in this context (as with the simple form of the \$OMEGA and \$SIGMA records described in Chapter 9, Section 3) variances-covariances may be constrained to fixed values by means of the FIXED option. Finally, some variances-covariances may be constrained to equal others by means of the BLOCK SAME option.

The ability to fix all variances-covariances in both  $\Omega$  and  $\Sigma$  allows Bayesian estimates to be obtained of the pharmacokinetic parameters of a single individual, based on the individual's data and a prior population distribution for the parameters.

References: Users Guide IV (NM-TRAN) III.B.10

#### 4.1.1. More About \$OMEGA and \$SIGMA

Initial estimates of a block of \$OMEGA or \$SIGMA must be positive definite unless the entire block is fixed to 0.

If initial estimates of a block of \$OMEGA or \$SIGMA is not positive definite because of rounding errors, a value will be added to the diagonal elements to make it positive definite. A message in the NONMEM report file will indicate if this was done. (nm73).

Additional options include:

VARIANCE (initial estimates of diagonal elements are variances (default))

STANDARD or SD (initial estimates of diagonal elements are standard deviations)

COVARIANCE (initial elements of off-diagonal elements are covariances (default))

CORRELATION (initial elements of off-diagonal elements are correlation)

CHOLESKY (the block is specified in its Cholesky form)

NONMEM converts all initial estimates to variance and covariances. The values displayed in the NONMEM report and in the raw and additional output files are always variances and covariances.

If the initial estimate of \$OMEGA or \$SIGMA has band-symmetric form, NONMEM will be constrained to retain this form (nm7).

Special value of \$OMEGA elements for unconstrained etas: If all diagonal elements of \$OMEGA are "1.0E+06 FIXED" this indicates that, in a multi-subject data set, each subject's data is to be analyzed as individual data. This is described by NONMEM as ANALYSIS TYPE: POPULATION WITH UNCONSTRAINED ETAS(nm73)

Short-cuts may be used for entering repeated information.

#### BLOCK SAME(m) option

A count  $m$  may be included. With \$OMEGA BLOCK(n) SAME(m) the \$OMEGA BLOCK(n) SAME record is repeated  $m$  times. Similarly for \$SIGMA records (nm73).

#### \$THETA, \$OMEGA, \$SIGMA Repeated values

When specifying initial estimates, a repeated value can be coded using notation (...) $xn$ . E.g., \$OMEGA (2) $x4$  can be used in place of \$OMEGA 2 2 2 2. Similarly for \$SIGMA and \$THETA.

#### \$OMEGA,\$SIGMA VALUES option

If initial estimates of all diagonal elements of \$OMEGA or \$SIGMA are the same, and initial estimates of all off-diagonal elements are the same, they can be specified simply as \$OMEGA BLOCK(n)VALUES(diag,odiag).

#### \$OMEGA,\$SIGMA SCALE(d) option

The SCALE(d) option will cause NMTRAN to multiply any omega or sigma element that comes after it by the real number factor  $d$ .

Informative record names for \$OMEGA and \$SIGMA may be used to make it easier place the records in the control stream.

\$OMEGAP specifies omega priors

\$OMEGAPD specifies degrees of freedom (or dispersion factor) for omega priors

They are identical to \$OMEGA records, but understood to specify prior information for NWPRI. They may be placed anywhere in the control stream, whereas the same records without "P" or "PD" would have to be in a specific location.

Informative record names \$SIGMAP and \$SIGMAPD may be used similarly.

References: Introduction to NONMEM 7

## 4.2. Grouping Related Observations: The L1 and L2 Data Items

The \$ERROR statements for a problem may sometimes involve more than one random variable. For example, there may be two types of observations. One type may be an observation from one compartment of a PK system, or with one assay or preparation, and another type may be an observation from a different compartment or with a different assay or preparation. The model for the two types of observations would typically involve at least two  $\varepsilon$  variables (e.g. (3.8)). If all observations are made at sufficiently separated times, there may be little reason to be concerned about correlation between the two random errors. However, if the two types of observations are taken at the same or very close to the same time, it is possible that correlation will exist; whatever circumstance has influenced one observation to be different from the predicted level may also have some influence on the other observation. In this case a covariance between the two  $\varepsilon$  variables should be allowed, as described above in Section 4.1. Then the two types of observations at the same time point are regarded as two elements of a multivariate observation.

In the case of population data, there exists a NONMEM data item, L2, which is used to identify the elements of a multivariate observation. In effect, L2 acts in a similar way as ID, but grouping observations *within* individual records.

In the case of individual data, the ID data item already serves this purpose: it forms groups of observations whose  $\eta$  variables may be correlated. Thus, in the input data file,

the ID data item should be the same for those observations which may have correlated  $\eta$ s. However, for individual data, the Data Preprocessor normally replaces the ID data item with a new set of values which describe every observation as being independent of the others. To prevent the Data Preprocessor from doing this, L1 should be included in the \$INPUT record as the name or synonym for the user-supplied ID data item.

Auto-correlation: The values of epsilons used in the intraindividual model may be correlated across the observations contained in the L2 record. Auto-correlation may be part of both Simulation and Estimation. The CORRL2 reserved variable may be used.

References: Users Guide IV (NM-TRAN) II.C.4, III.B.2

References: Users Guide II (Supplemental) D.3

### 4.3. Continuing a NONMEM Run: MSFO and MSFI

The MSFO (Model Specification Output File) option of the \$ESTIMATION record instructs NONMEM to write a Model Specification File (MSF). It is created when NONMEM writes the first iteration summary to the intermediate output file, and is re-written when every subsequent iteration summary is written. This file can then be read in a subsequent NONMEM run using a \$MSFI (Model Specification File Input) record. This file has much of the information about the model used in the previous run, thus the name "Model Specification File". It also contains all the information that allows the Estimation Step from the previous run (which may have terminated, for example, due to the number of function evaluations exceeding its limit or a computer crash or some other externally-caused interruption of the NONMEM run) to be continued in the subsequent run. There are a number of benefits to using a MSF. First, what might be a long Estimation Step (due to a very lengthy search) can be split over a series of runs, each with a limited number of function evaluations. Any run which terminates prematurely due to computer failure can be restarted from the MSF output in the previous run. (This provides a "checkpoint/restart" capability.) The progress made in the Estimation Step can also be evaluated between runs, and a decision made as to whether it is worth continuing a search which is consuming excessive amounts of computer time. Second, the Covariance, Tables, and Scatterplot Steps can be performed in later runs, each using the MSF from the final run with the Estimation Step. It is advisable to perform the Covariance Step only after satisfactory results have been obtained from the Estimation Step. Third, when NONMEM writes to the MSF, it also writes iteration summaries to the intermediate printout file (INTER). These iteration summaries are in the original parameterization (nm72).

Options are described in Guide VIII. These include NORESCALE, ONLYREAD, and NPOPETAS (nmvi). (NPOPETAS gives information to NM-TRAN rather than NONMEM.) The VERSION option allows NONMEM to read MSF files generated by previous versions of NONMEM (nm74). The NOMSFTEST option tells NONMEM to turn off strict MSFI error testing (nm74).

Option NEW allows analysis to continue, or to allow an analysis on a new data set, resuming from the final parameters of the MSF file. (nm74)

Option Version specifies the NONMEM version that produced the MSF file. Thus MSF files produced from past NONMEM versions can be read in, even though their structure may differ from that of the present version.

References: Users Guide I (Basic) C.4.4

References: Users Guide IV (NM-TRAN) III.B.6, B.12

References: Introduction to NONMEM 7

#### 4.4. NONMEM Can Obtain Initial Estimates for $\theta$ , $\Omega$ , $\Sigma$

NONMEM can be directed to obtain initial estimates for one or more elements of  $\theta$ ,  $\Omega$ , or  $\Sigma$ . This is done in a separate Initial Estimates Step. For an element of  $\theta$ , omit the initial estimate but include lower and upper bounds, e.g., (1, .50) in the \$THETA record. (The NUMBERPOINTS option may be used to control the number of points in  $\theta$  space examined by NONMEM during the search for initial estimates of  $\theta$ .) For a block of  $\Omega$  or  $\Sigma$ , omit all initial estimates on the \$OMEGA BLOCK (or DIAGONAL) record, or \$SIGMA BLOCK (or DIAGONAL) record, respectively.

Note that when \$PK and \$ERROR statements are present but the \$OMEGA and/or \$SIGMA records are absent, NONMEM will be directed to obtain initial estimates for the variances of the random variables in question, assuming the diagonal form of the matrix.

References: Users Guide IV (NM-TRAN) III.B.9-11

#### 4.5. Improving Parameter Estimates: REPEAT and RESCALE

The Estimation Step can be immediately repeated after the search has terminated successfully, by including the REPEAT option on the \$ESTIMATION record. This can improve the accuracy of the parameter estimates when one or more initial estimates are wrong by a few orders of magnitude. The final estimates from the first implementation of the Estimation Step are used as the initial estimates of the second implementation, and thus the scaling used with the STP is different from that with the first implementation, allowing fewer leading zeros after the decimal point in the STP. When the Estimation Step is continued by means of a Model Specification File, similar rescaling can be requested using the RESCALE option of the \$MSFI record.

References: Users Guide IV (NM-TRAN) III.B.12, B.14

References: Users Guide II (Supplemental) F

#### 4.6. The Covariance Step: $R^{-1}$ , $S^{-1}$ , Special Computation

The Covariance Step, which computes standard errors of the parameter estimates, first computes a covariance matrix of the parameter estimates. (This is not the same as the  $\Omega$  or  $\Sigma$  matrix). It is possible to request that this covariance matrix be computed in one of three different ways: either as  $R^{-1}$ ,  $S^{-1}$ , or  $R^{-1}SR^{-1}$  (the default), where  $R$  and  $S$  are two matrices from statistical theory, the Hessian and Cross-Product Gradient matrices, respectively. Options MATRIX=R and MATRIX=S of the \$COVARIANCE record are used to request the  $R^{-1}$  and  $S^{-1}$  matrices, respectively. The Covariance Step can produce additional output. When the default covariance matrix is used,  $R^{-1}$  and/or  $S^{-1}$  can be printed. This is requested by options PRINT=R and/or PRINT=S. Eigenvalues are printed if requested by option PRINT=E. Multiple PRINT options can be specified.

A special computation is *required* when the data are from a single individual and a recursive PRED is used. A recursive PRED is one which stores the results of certain computations using the values from one event record, and uses these results in later computations with the values from a later event record. PREDPP advances the kinetic system from one time point to the next and therefore is an example of a recursive PRED. When PREDPP is used and the data is from a single individual, NM-TRAN automatically requests the special computation. When a recursive user-written PRED is used and the data are from a single individual, the SPECIAL option of the \$COVARIANCE record *must* be used.

The CONDITIONAL option of the \$COVARIANCE record requests that the Covariance Step be implemented only if Estimation Step terminates successfully, and is the default. The UNCONDITIONAL option can be used to request that it be implemented no matter

how the Estimation Step terminates.

References: Users Guide IV (NM-TRAN) III.B.15

References: Users Guide II (Supplemental) D.2.5

#### 4.6.1. More About \$COVARIANCE

Other options of interest:

COMPRESS (affects how the Covariance matrices are displayed in the NONMEM report)

NOSLOW | SLOW (SLOW Requests a slower method of computation)

SIGL | SIGLO (affects how computations are done in the Covariance Step)

RESUME (allows the Covariance Step to resume from a MSF)

NOFCOV (turns off the Covariance Step for Estimation steps using the classical methods)

The \$ESTIMATION record option NOCOV may be used to turn off the Covariance Step following a particular Estimation step, and to turn it back on again.

See Section 6.8 for more about \$COV.

#### 4.7. Multiple Problems in a Single NONMEM Run

NONMEM can implement more than one problem in a single run. That is, the input control stream can contain more than one \$PROBLEM record, each followed by its own set of problem specification statements. This feature can be useful in a variety of situations. A series of what otherwise would be separate runs, each analyzing a single individual's data within a population data file, can be performed conveniently without building separate data files for each individual. Also, more than one data set can be analyzed using the same model and the same problem specification. Multiple problems are also useful with NONMEM's Simulation Step, described below.

Note that abbreviated code such as \$PK and \$ERROR statements cannot appear after the first problem. If the \$DATA record is omitted or the filename is specified as \* on a \$DATA record in a problem subsequent to the first, the previous data set is re-used.

With multiple problems, the following NONMEM reserved variables are of interest:

NPROB,IPROB

A sequence of problems may be defined to be a superproblem by means of the NM-TRAN \$SUPER record, and NONMEM may also be directed to repeat them a specific number of times.

With superproblems, the following NONMEM reserved variables are of interest:

S1NUM S2NUM S1NIT S2NIT S1IT S2IT

SKIP\_ variable for Superproblem termination

References: Users Guide IV (NM-TRAN) III.B.1

#### 4.8. Simulation Using NONMEM: The \$SIMULATION Record

The term simulation refers to the generation of data points according to some model. A simple form of simulation is performed when the Estimation Step is omitted but the Table Step is implemented. The PRED column of the table contains predictions based on the information in the data records and the initial estimates of  $\theta$ , under the model specified in the PRED (PREDPP) subroutine. Random variables  $\eta$  and  $\varepsilon$  (if any) have no effect on the predictions and may be omitted. If the only purpose of the run is to obtain simulated values, and these variables are present, it is best (but not required) that their variances be fixed to 0. NONMEM does not compute the objective function in this circumstance,

which has certain advantages.

NONMEM can also perform a Simulation Step, in which another type of simulation is performed. In the Simulation Step, each value of the DV data item of each record with MDV=0 is replaced by a simulated observation generated from the model, but including statistical variability<sup>†</sup>. The PRED (PREDDP) routine uses  $\eta$  and  $\varepsilon$  values that are supplied by NONMEM according to user-specified random distributions (e.g., with variances given by the initial estimates of  $\Omega$  and  $\Sigma$ ). If  $\Omega$  and  $\Sigma$  matrices are fixed to zero, for example, the simulated values are the same as the predictions described above.

If the data are then displayed by the Table Step, the DV column for records with MDV=0 contains the simulated observations obtained from the Simulation Step. For records having MDV=1, the DV column contains whatever was in the original data record. The PRED column of the table contains predictions as described above. If the Estimation Step was not implemented, the values of  $\theta$  used for these predictions are the initial values. If the Estimation Step was implemented, the values of  $\theta$  used for the predictions in the PRED column are the final parameter estimates. Note that the observations that are fit during the search are the simulated values obtained by the Simulation Step.

Often data are simulated using the Simulation Step, then analyzed using one or more other steps (e.g. Estimation and Covariance Steps), and this process is repeated a fixed number of times, using the same model. The Simulation Step accommodates this easily with the notion of a NONMEM subproblem, whereby these steps are repeated within the same NONMEM problem. However, on occasion it can be useful to have multiple problems (see Section 4.7), where one problem implements the Simulation Step, and the subsequent problem implements other steps. For example, this is one way to obtain different initial parameter estimates for the Estimation Step than for the Simulation Step.

The ONLYSIMULATION option causes NONMEM to suppress evaluation of the objective function. With this option, PRED-defined variables displayed in tables and scatterplots (see Section 4.13) are simulated values, i.e., use simulated  $\eta$ s and initial  $\theta$ s, and weighted residual values in tables and scatterplots are always 0.

References: Users Guide IV (NM-TRAN) III.B.13

References: Users Guide VI (PREDDP) III.E.2, L.1 , IV.B.1-2, C, G.1

#### 4.8.1. More About \$SIMULATION

With simulation, subroutines SIMETA and SIMEPS are used.

With simulation and subproblems, the data set for each subproblem after the first is the same data set used by the previous subproblem, and includes any changes (transgeneration) made by the previous subproblem. With nm74, the REWIND option of \$SIMULATION may be used to request that the original data set be used for all sub-problems. (If transgeneration is performed on the data set by \$INFN when ICALL=1, the resulting data set is considered to be the original data set.)

See Section 6 for a discussion of the BOOTSTRAP and STRAT (stratification) features of simulation, and also parallelization during simulation.

The following NONMEM reserved variables are of interest during simulation:  
IREP, NREP

NONMEM subroutine RANDOM may be used in abbreviated code to obtain numbers from a random source (nmiv, nm7).

<sup>†</sup> During the Simulation Step, values of F computed by PRED or PREDDP for records having MDV=1 are irrelevant and are ignored by NONMEM.

The \$SIMULATION record has other options, including:

a random seed and options NEW, NORMAL, UNIFORM, or PARAMETRIC for each of several random sources;

TRUE=INITIAL, TRUE=FINAL, or TRUE=PRIOR, to specify what the "true parameter values" for the Simulation should be;

PREDICTION or NOPREDICTION to specify whether the Y (or F) variable or the DV variable is set to the prediction;

REQUESTFIRST or REQUESTSECOND to specify if any eta partials are to be computed.

NONMEM can use the BOOTSTRAP method for simulations. With BOOTSTRAP, other options are possible:

REPLACE or NOREPLACE

STRAT or STRATF.

\$SIM NOSUPRESET feature allows the simulation seeds not to be reset with each iteration of a super-problem.

\$SIM RANMETHOD allows the random number generator algorithm to be selected

\$SIM TTDF allows thetas to be simulated (when TRUE=PRIOR) using a t-distribution instead

\$SIM CLOCKSEED allows the initial seed to be selected based on the clocktime at runtime. This allows every instance of a run to have a unique starting seed.

\$SIM SOURCE\_EPS allows the user to choose an alternative source, other than the default of 1, for generating epsilons. This allows etas and eps to have independent seed chains, so that randomly generated etas are not changed if the data is changed.

\$SIM PARAFILE allows parallelization to be turned ON for simulation (default is OFF, unlike other records).

#### **4.9. Files for Subsequent Processing: the \$TABLE Record**

NONMEM can write the data for a table to an external formatted file, as requested by the FILE option of the \$TABLE record. Other computer programs can read these files. Such programs can perform further analysis or provide improved graphical displays. These files normally contain header lines similar to those in a printed table, but the header lines can be suppressed entirely or in part by means of the NOHEADER, ONEHEADER, ONE-HEADERALL, ONEHEADERPERFILE options. NOTITLE (suppresses the table titles) and NOLABEL (suppresses column labels) may be used.

Tables may be written to the same or to different table files.

References: Users Guide IV (NM-TRAN) III.B.16

##### **4.9.1. More about \$TABLE and \$SCATTER**

Some options may be used only with a table file.

Options NOFORWARD and FORWARD control whether a table file which is used with multiple problems is positioned at the start of the file or forwarded to the end of the file.

Option NOPRINT may be used to suppress the table in the NONMEM report, or PRINT to include it as usual. A printed table is limited to 8 items but a non-printed table file may have an unlimited number of items (controlled by PDT in \$SIZES with default 500).

FORMAT supplies an alternate format for every numeric item in a table file (the default is s1PE11.4). An alternate name for this option is DELIM.

RFORMAT supplies an alternate format for the full numeric record of a file.  
 LFORMAT supplies an alternate format for the full label record in a file.  
 IDFORMAT supplies an alternate format for the ID data item (such as F14.0 for integer) in a file.

Other options can be used with both printed tables and table files.

FIRSTONLY (include only the first data record from each individual record)  
 LASTONLY (include only the last data record from each individual record)  
 FIRSTLASTONLY (include only the first and last data record from each individual record)  
 BY (sort records in the table)  
 NOAPPEND (suppress items DV, PRED, RES, WRES)  
 APPEND (list items DV, PRED, RES, WRES; this is the default)

With a \$SCATTER record, additional options are:

FIRSTONLY (include only the first data record from each individual record)  
 OBSONLY (include only the observation records, having MDV=0)

The option ABS0 is similar to ORD0 described in Chapter 9, but adds a line zero line on the abscissa axis of the scatterplots.

Many additional diagnostic and reserved variables may be listed in tables and scatters; see 6.3 below.

With the Monte-Carlo generated diagnostics, new options of the \$TABLE record may be used. Note that if these options affect the values of the weighted residual, the scatterplots will also be affected.

ESAMPLE=n1  
 WRESCHOL  
 SEED=n2  
 RANMETHOD= [n | S | m]

#### 4.10. Data Checkout Mode

NONMEM's data checkout mode is intended for preliminary display of data without the use of a model. In data checkout mode, the PRED routine is not called. Predictions, the objective function, residuals, and weighted residuals are not computed. Only the Table and Scatterplot Steps can be implemented in the problem. With NM-TRAN, this mode is requested by coding the option CHECKOUT on the \$DATA record. A \$SUBROUTINES record and abbreviated code are required, but they have no effect and need only be syntactically correct.

References: Users Guide IV (NM-TRAN) III.B.6

#### 4.11. Obtaining Individual Parameter Estimates - Conditional Estimates of $\eta$ s

With population data, NONMEM can obtain estimates of individual-specific true values of  $\eta$  from any given set of values of  $\theta$ ,  $\Omega$ ,  $\Sigma$ , and the individual's data. These are called conditional estimates of  $\eta$ . When the conditional estimates are obtained after estimation is carried out by the First-Order method, they are referred to as "posthoc" estimates. With NM-TRAN, they are requested by the option POSTHOC on the \$ESTIMATION record.

References: Users Guide IV (NM-TRAN) III.B.14

#### 4.12. Population Conditional Estimation Methods

NONMEM can obtain conditional estimates of  $\eta$  variables as part of the computation of population parameter estimates. These are called conditional estimation methods. With NM-TRAN, such methods are requested by including the option METHOD=CONDITIONAL (or METHOD=1) on the \$ESTIMATION record. (The option METHOD=ZERO, or METHOD=0, requests the conventional First-Order method and is the default.) There are two conditional estimation methods. If NONMEM uses only first-order approximations, this is the First-Order Conditional Estimation Method. This has one variation, interaction, which takes into account  $\eta$ - $\varepsilon$  interaction and is requested by the additional option INTERACTION on the \$ESTIMATION record. If NONMEM uses a certain second-order approximation, this is the Laplacian method, which is requested by the additional option LAPLACIAN on the \$ESTIMATION record. Interaction may be specified with any method, including the Laplacian method.

Note that this usage of the term CONDITIONAL is different from the usage on the \$SCATTERPLOT, \$TABLE, and \$COVARIANCE records, in which it refers to the circumstances under which the step in question is implemented.

Option CENTERING requests that the average conditional estimates of each eta be constrained to be close to 0.

References: Users Guide IV (NM-TRAN) III.B.14

#### 4.13. Displaying PRED-Defined Variables and Conditional Estimates of $\eta$ s

NONMEM can display PRED-defined variables in table and scatterplots. With NM-TRAN, any variable appearing on the left-hand side of an assignment statement in abbreviated code can be displayed by listing it in a \$TABLE or \$SCATTER record. If the data are population, NONMEM can also display conditional estimates of  $\eta$ . With NM-TRAN, variables ETA(1), ETA(2), etc., can be simply listed in \$TABLE and \$SCATTER records. When conditional estimation is not performed, the values displayed are zero. Displayed values of PRED-defined random variables will use conditional estimates of  $\eta$  if they have been obtained, otherwise they will be typical values. This feature is available with PREDPP, as well as with user-written PRED routines. For example, the following records could replace the \$ESTIMATION record in Figure 12.2:

```
$ESTIMATION POSTHOC
$TABLE ETA(1) EMAX
```

The \$ABBREVIATED record can be used to limit the number of variables available for display when the number is excessive.

References: Guide III (Installation) V.2.4

References: Guide IV (NM-TRAN) III.B.16-17

References: Guide VI (PREDPP) III.J, IV.E

#### 4.14. Mixture Models

A mixture model is a model that explicitly assumes that the population consists of two or more sub-populations, each having its own model. For example, with two sub-populations, one might assume that some fraction  $p$  of the population has one set of typical values of the PK parameters, and the remaining fraction  $1-p$  has another set of typical values. Both sets of typical values and the mixing fraction  $p$  may be estimated. For each individual, NONMEM also computes an estimate of the number of the subpopulation of which the individual is a member. The user must supply a FORTRAN subroutine called MIX or a \$MIX block of abbreviated code to compute the fractions  $p$  and  $1-p$ .

Reserved variables NSPOP, P, MIXNUM, MIXEST, MIXP and MIXPT can be used in abbreviated code. Reserved variable TEMPLT may be used.

References: Users Guide VI (PREDDPP) III.L.2

#### 4.15. PRED Error Return Codes and Error Messages in File PRDERR

A PRED routine can return a PRED error return code (1 or 2) to NONMEM, indicating that it is unable to compute a prediction for a given data record with the current values of  $\theta$ 's and  $\eta$ 's. For example, PREDDPP returns error return code 1 when a basic or additional PK parameter has a value that is physically impossible (e.g., a scale parameter which is zero or negative). Error return codes can also be specified by the user in user-written code or in abbreviated code using the EXIT statement. One reason for doing this is to constrain parameters in order to avoid floating point machine interrupts. The PRED error recovery option determines what action NONMEM will take. With NM-TRAN, the PRED error recovery option is either ABORT (which is the default) or NOABORT, and is specified on the \$ESTIMATION and \$THETA records.

If an error return code is returned during the Simulation, Covariance, Table or Scatterplot Step, or during computation of the initial value of the objective function, NONMEM will abort. If the error return code is returned during the Estimation or Initial Estimates Step, NONMEM will try to avoid those values of  $\theta$  and  $\eta$  for which the error occurs. If they cannot be avoided, NONMEM's actions depend on the error return code value, as follows:

- 1 If NOABORT is specified on \$ESTIM or \$THETA, try to avoid the current values of  $\theta$  and  $\eta$ . If ABORT is specified on \$ESTIM or \$THETA, then abort.
- 2 Abort in all cases.

NOABORTFIRST may be specified on \$THETA (nmvi) Same as NOABORT option, but also applies to the first value of the theta vector that is tried.

NOHABORT may be specified on \$ESTIM (nm7).

PRED routines may optionally provide text accompanying the error return code. NONMEM writes all text associated with error return codes to a file, PRDERR. The contents of this file should always be carefully reviewed.

References: Users Guide III (Installation) III.2.1.1

References: Users Guide IV (NM-TRAN) IV.A, IV.C.5-6

References: Users Guide VI (PREDDPP) III.K, IV.F

#### 4.16. User-Written Subroutines

Although most NONMEM applications can be accomplished using NM-TRAN abbreviated code, there are cases in which user-written FORTRAN subroutines are needed. The \$SUBROUTINES record allows the user to specify the names of user-written routines that are needed in the NONMEM load module. A user may choose to write his own PRED, PK, ERROR, INFN, MODEL, DES, or AES subroutine. Some subroutines that are distributed with NONMEM are dummy, or "stub" routines, that do nothing. Of these, subroutines CCONTR, CONTR, CRIT, PRIOR, USMETA, SPTWO, MIX can be replaced to obtain an objective function different from the default. NONMEM subroutine MIX must be replaced for mixture models. The names of all such routines are specified using the identically named options of the \$SUBROUTINES record, e.g., PRED=subname, CONTR=subname, etc. User-written routines may call other FORTRAN subroutines, which can be specified for inclusion in the load module using the option

OTHER=subname.

With user-written CONTR routines, the NM-TRAN \$CONTR record may be useful.

THETA and THETAR are stubs that may be replaced to transform initial and final theta values. The \$THETA and \$THETAR records described in Section 6 can be used to generate the replacement code in FSUBS.

References: Users Guide IV (NM-TRAN) III.B.4, B.6

#### 4.17. PRIOR

The PRIOR subroutine and \$PRIOR record allows a Bayesian penalty function to be added to the NONMEM objective function. This serves as a constraint on the estimates of THETA, OMEGA, and SIGMA and thus as a way for stable estimates to be obtained with insufficient data.

NONMEM subroutines that may be used are NWPRI and TNPRI (nmvi). With NWPRI, informatively-named \$THETAP, \$THETAPV, \$OMEGAP, \$OMEGAPD, \$SIGMAP, \$SIGMAPD records can be used to provide prior information (nm73).

The option NOPRIOR of the \$ESTIMATION record controls whether or not the prior information is used for a given Estimation Step.

References: NONMEM Guides IV and VIII

References: Introduction to NONMEM 7

### 5. Observations of Two Different Types

An NM-TRAN control stream is shown in Figure 12.3, for the analysis of a data set which contains observations of two different types. A fragment of the data set, shown in Figure 12.4, contains the data for one individual. This example illustrates how concentration and effect data can be fit simultaneously, and includes many of the advanced features described in this chapter, such as pharmacodynamic modeling in the \$ERROR statements, correlation between elements of  $\Sigma$ , and the L2 data item.

Suppose that the data set for the phenobarbital example of Chapter 2 is modified to include both concentration and effect observations, and that a data item called TYPE is used to distinguish between them. When TYPE is 1, DV contains an effect measurement. When TYPE is 2, DV contains a concentration. The \$PK statements are the same as those of Figure 2.12. The \$ERROR statements are the same as those of Figure 12.1, except that the elements of  $\theta$  and  $\eta$  are renumbered to follow those used in the \$PK statements. The (random) variable Y1 is assigned the same value as Y in the \$ERROR statements of Figure 12.1. The (random) variable Y2 is assigned the same value as Y in the \$ERROR statements of Figure 2.12, except that  $\varepsilon_2$  is used rather than  $\varepsilon_1$ .

The input data file contains observations of both types which were made at the same time value. The event records therefore include the L2 data item. Figure 12.4, like Figure 2.7, shows the data for the first individual, but includes TYPE and L2 data items and effect observations. Note that the L2 data item has a different value for each multivariate observation within the individual record. (The values 1 and 2 are chosen arbitrarily and may be re-used for the L2 data items in the next individual's data, if desired.)

The \$THETA, \$OMEGA, and \$SIGMA records contain the values shown in Figures 2.12 and 12.1 and one other value, 2.8, for the covariance  $\Sigma_{12} = cov(\varepsilon_1, \varepsilon_2)$ . The estimate 2.8 is chosen so that the correlation is, arbitrarily, .5 ( $2.8 = \Sigma_{12} = (\Sigma_{11}\Sigma_{22})^{\frac{1}{2}} corr = (8 \times 4)^{\frac{1}{2}} .5$ ).

```

$PROBLEM COMBINED PK/PD MODEL
$INPUT  ID TIME AMT WT APGR DV TYPE L2
$DATA   COMBDATA
$SUBROUTINE ADVAN1
$PK
  TVCL=THETA (1)+THETA (3) *WT
  CL=TVCL+ETA (1)
  TVVD=THETA (2)+THETA (4) *WT
  V=TVVD+ETA (2)
                                ; THE FOLLOWING ARE REQUIRED BY PREDPP
  K=CL/V
  S1=V
$ERROR
  EMAX=THETA (5)+ETA (3)
  C50=THETA (6)+ETA (4)
  E=EMAX*F/(C50+F)
  Y1=E+ERR (1)
  Y2=F+ERR (2)
  Q=1
  IF (TYPE.EQ.2) Q=0
  Y=Q*Y1+(1-Q)*Y2
$THETA (0,.0027) (0,.70) .0018 .5 100 20
$OMEGA .000007 .3 400 16
$SIGMA BLOCK(2) 4 2.8 8
$ESTIMATION

```

Figure 12.3. The input to NONMEM-PREDPP for analysis of the population phenobarbital data, including both concentration and effect observations.

|   |       |      |     |   |      |   |   |
|---|-------|------|-----|---|------|---|---|
| 1 | 0.    | 25.0 | 1.4 | 7 | .    | 2 | 0 |
| 1 | 2.0   | .    | 1.4 | 7 | 6.0  | 1 | 1 |
| 1 | 2.0   | .    | 1.4 | 7 | 17.3 | 2 | 1 |
| 1 | 12.5  | 3.5  | 1.4 | 7 | .    | 2 | 0 |
| 1 | 24.5  | 3.5  | 1.4 | 7 | .    | 2 | 1 |
| 1 | 37.0  | 3.5  | 1.4 | 7 | .    | 2 | 0 |
| 1 | 48.0  | 3.5  | 1.4 | 7 | .    | 2 | 1 |
| 1 | 60.5  | 3.5  | 1.4 | 7 | .    | 2 | 0 |
| 1 | 72.5  | 3.5  | 1.4 | 7 | .    | 2 | 1 |
| 1 | 85.3  | 3.5  | 1.4 | 7 | .    | 2 | 0 |
| 1 | 96.5  | 3.5  | 1.4 | 7 | .    | 2 | 1 |
| 1 | 108.5 | 3.5  | 1.4 | 7 | .    | 2 | 0 |
| 1 | 112.5 | .    | 1.4 | 7 | 8.0  | 1 | 2 |
| 1 | 112.5 | .    | 1.4 | 7 | 31.0 | 2 | 2 |

Figure 12.4. The first individual's phenobarbital data, including both concentration and effect observations.

The above \$ERROR statements can be coded more simply.

```

$ERROR
  EMAX=THETA (5)+ETA (3)
  C50=THETA (6)+ETA (4)
  E=EMAX*F/(C50+F)
  IF (TYPE.EQ.2) THEN
  Y=F+ERR (2)
  ELSE
  Y=E+ERR (1)
  ENDIF

```

Figure 12.5. Alternate \$ERROR statements

## 6. Supplemental List of Features through NONMEM 7.5.2

With NONMEM 7 there are many new features, including new Estimation Methods. This section lists features of NONMEM, PREDPP, and NM-TRAN that are not discussed elsewhere in this guide. The version of NONMEM in which each feature appears is listed. The user should consult other guides for details.

### 6.1. NONMEM Features

NONMEM can drop data records (nm75)

The IGNORE=(list) and ACCEPT=(list) options of \$DATA provide a limited means of filtering the input data set, which is performed by NMTRAN (nm6). To provide more elaborate filtering for excluding data, PRED can request that NONMEM filter out additional data records at the beginning of the run. This is done by setting the reserved variable PRED\_IGNORE\_DATA to a non-zero value within \$INFN, \$PK, or \$PRED, for each record to be ignored.

NONMEM replicate data (nm75)

At run-time, NONMEM can create replicate of a basic data template, either via the REPL option, or by the REPL\_ data item. The final data can be reviewed in the file FDATA.csv, which can differ from FDATA in that the replications will be in FDATA.csv, and any PRED\_IGNORE\_DATA data items will not be present. Use NOFDATACSV option to not generate the FDATA.csv, as sometimes this can take considerable time for large data files.

Odd-Type Data (nmv)

Non-continuous observed responses ("odd-type data") can be analyzed. \$ESTIMATION options LIKELIHOOD or -2LL must be used. Y is set to a (conditional) likelihood.

Reserved variable F\_FLAG may be used (nmvi).

New methods of Estimation

METHOD=HYBRID with option ZERO (nmv)

STIELTJES with options GRID, REPEAT1, REPEAT2, ZERO (nmvi)

ITS Iterative Two Stage (nm7)

Expectation-Maximization (EM) and Monte Carlo Bayesian (nm7)

Expectation feature (nmv)

This feature uses the NONMEM marginal (MRG\_) data item. MRG\_ identifies records for which NONMEM computes and displays marginal quantities (expectations) Expectations are computed when ICALL=5.

Raw data average feature (nmv)

This feature uses the NONMEM raw-data (RAW\_) data item. RAW\_ identifies template records for which NONMEM computes and displays raw-data averages. Raw data averages are computed when ICALL=6. Reserved variables TEMPLT and the \$OMIT record may be used (nmvi). The NONMEM utility routine RANDOM may be used to obtain numbers from different random sources.

Non-parametric analysis methods (nmvi)

The \$NONPARAMETRIC record is used to request the Non-parametric method of analysis. Options include:

MARGINALS or ETAS, MSFO=filename, RECOMPUTE, EXPAND, NPSUPP=n or NPSUPPE=n

SORT option of \$ESTIMATION (nmvi)

With classical methods, individual contribution to the objective function and

gradients may be sorted before they are summed, so that smaller numbers are summed before larger numbers.

#### Reserved Variables YLO/YUP (nmvi)

During the analysis an interval is defined in which (or outside of which) an observation is conditioned to exist. Reserved variable PR\_Y is also of interest.

#### Reserved Variables CTLO/CTUP (nmvi)

An observation may be the event that the value of a normally distributed variable falls in a given interval. Reserved variable PR\_CT is also of interest.

#### NONMEM Repetition feature (nmvi)

This feature uses reserved variables RPTI,RPTO,RPTON,PRDFL. An alternate way is to use the RPT\_ data item.

#### MU Modeling (MU Referencing) (nm7)

MU\_i variables may be used in Abbreviated code with EM methods of Estimation. NM-TRAN checks the use of MU\_i variables, unless option *NOCHECKMU* of the \$ABBR record is used (nm73). Thetas may be input and reported in their natural domain, even when used as logs (e.g., linear MU referencing) using \$THETAI and \$THETAR records (nm73).

#### New method of setting initial values of thetas, omegas, and sigmas. (nm72)

See CHAIN option of \$ESTIMATION and \$CHAIN.

#### Multiple Estimation steps (nm72)

If the \$ESTIMATION record is present more than once within a problem, then each subsequent record requests a separate Estimation Step rather than providing more options for a single Estimation Step.

#### BOOTSTRAP method (nm73)

BOOTSTRAP may be specified with \$NONPARAMETRIC and \$SIMULATION records. This requests that a bootstrap sample be used. Options STRAT and STRATF may be used for stratification. Additional control can be made with NPESTIM, NPMAXITER, and PARAFIL. With \$SIMULATION, options REPLACE or NOREPLACE may be used. An example is given of bootstrapping single subject data (nm74).

#### More than 2 levels of mixed effects (nm73)

Increased number of mixed effects levels. Random effects across groups of individuals, such as clinical site, can be modeled. The \$LEVEL record is used.

#### Alternate method (POPULATION WITH UNCONSTRAINED ETAS) for single-subject analysis (nm73)

All the subjects may be analyzed together, but with \$OMEGA diagonal values fixed to a special value 1.0E+06.

#### New values of MDV (nm73)

MDV may be set to 100, 101. Such records are ignored during Estimation. Reserved variables MDVI1, MDVI2, MDVI3 may also be used; they are defined in include file nonmem\_reserved\_general.

#### Initial Estimates for ETAs feature (nm73)

By default, the initial value used for ETA's in the Estimation Step search is 0. The \$ETAS and \$PHIS records provide user-supplied initial estimates.

#### Transformations of THETA values (nm73)

\$THETAI transforms the initial values in the \$THETA and \$THETAP records. \$THETAR transforms the final theta values for the NONMEM report and

additional output files. May be used with MU Modeling.

#### Constraints on model parameters (nm73)

Additional algorithmic constraints may be imposed upon model parameters by use of the subroutine CONSTRAINT. Option CONSTRAIN of the \$ESTIMATION record and The \$FORMAT record may be used to specify the number of significant digits outputted for results in the NONMEM report file. The \$LDFOLD record may be used to have loss of degrees of freedom (LDF) values interpreted in the manner of NONMEM before nm751. The \$ANNEAL record may be used to give information to the subroutine. This feature is available only for the EM and Bayesian algorithms.

#### Additional Reserved Variables

The descriptions of the following reserved variables can be found in Introduction to NONMEM 7 MXSTEP FIRSTEM MDVRES NPDE\_MODE DV\_LOQ CDF\_L

## 6.2. Miscellaneous Features

#### Interactive control of NONMEM (nm7)

A NONMEM run can now be controlled to some extent from the console by issuing certain control characters.

#### Dynamic Memory Allocation (nm72)

No need to recompile NONMEM or NM-TRAN for large problems. Most arrays are sized automatically. If necessary, the \$SIZES record may be used. E.g., the default maximum number of data items per data record is 50, but may be increased by specifying a larger value for PD; the maximum number of items per table is 500, but may be increased by specifying a larger value for PDT.

#### Parallel Computing (nm72)

Parallel Computing is requested using the nmfe option -parafile and specified using .pnm files. The options PARAFILE of the \$ESTIMATION and \$COVARIANCE records may also be used. With nm74, Option FPARAFILE of the \$ESTIMATION record controls parallelization for final eta (EBE) computation. Option PARAFILE of the \$TABLE controls parallelization for weighted residual computation. Option PARAFILE of the \$SIMULATION record may also be used.

## 6.3. Changes to NONMEM Outputs

Reports include Covariance and Correlation Matrices for OMEGA and SIGMA (nm72)

Reports include ETABAR, SE, N, P VAL (nm7)

Option ETABARCHECK of the \$ESTIMATION record may be used.

Reports include ETAshrink, EBVshrink, EPSshrink, RELATIVEINF (nm7)

Eta shrinkage evaluation using empirical Bayes variances (EBVs, or conditional mean variances) is reported. The ETASTYPE option of the \$ESTIMATION record and the ETASXI reserved variable in abbreviated code may be used to control which etas from which subjects are included.

Reports include tag labels: #METH etc. (nm7)

Raw and additional output files: root.ext, root.cov, root.xml, etc. (nm7)

These files provide numerical results in a columnar format. \$ESTIMATION record option ORDER may be used to control the order of theta, omega, sigma in these

files. \$ESTIMATION record option NUMDER may be used to request files with numerical and analytic eta derivatives: root.fgh, root.agh (nm73)

Tables and Scatters may request NONMEM-generated items

Elements of G and H (e.g., G11, H11) and elements of ETA (nmvi)

A range of etas using the format ETAS(k:n) may be requested (nm73).

Number lists or a syntax flexible (TO, :, BY) may be used(nm74). Examples are ETAS(1 TO 10 by 3), ETAS(1,5,12,4).

OBJI (Objective function values for each individual) (nm72)

Additional statistical diagnostic items (nm7, nm73)

In addition to the PRED, RES, and WRES items, the following may be listed.

PREDI, RESI, WRESI  
 CPRED, CRES, CWRES  
 CPREDI, CRESI, CWRESI  
 CIPRED, CIRES, CIWRES  
 CIPREDI, CIRESI, CIWRESI  
 NIPRED, NIRES, NIWRES  
 IPRD, IRS, IWRS  
 EPRED, ERES, EWRES

Monte-Carlo generated diagnostics are not linearized approximations like the other diagnostic types. These include

ECWRES  
 EIPRED, EIRES, EIWRES  
 NPDE Monte-Carlo generated normalized probability distribution error) (nm71)  
 NPD correlated value of NPDE (nm72)

With FIXEDETAS=(list), the specified etas are treated as if they are fixed effects when NONMEM evaluates population diagnostics during the \$TABLE step.(nm74)

The EXCLUDE\_BY option can be used to exclude records from the table or scatter. (nm74).

The VARCALC option asks NONMEM to report standard errors (xxx\_SE) in the tables for PREDPP and user-defined items. (nm74)

The NPdtype and INTERPTYPE options influence how the NPD and NPDE are calculated.

A reserved variable of interest when evaluating residuals and weighted residuals is MDVRES which may be set in PRED to cause NONMEM to treat an observation as missing during the computation of residuals and weighted residuals. (nm73)

#### 6.4. PREDPP

New PREDPP data items in \$INPUT: XVID1 XVID2 XVID3 XVID4 XVID5 (nm72)

Special values of EVID allow repeated observation records, e.g., for Stochastic differential equations.

CMT and PCMT values 100,1000

Specification of the default compartment for output (nm, nm73)

Compartment Amounts A(i), TSTATE (nmvi)

A\_0 (compartment initialization) (nmvi)

The compartment initialization feature may be used with any ADVAN.

A\_U,A\_UFLG (compartment update) (nm75)

The compartment update feature is similar to the compartment initialization feature but updates compartments at a time given by MTIME. May be used with any ADVAN.

Empirical Steady State (nm75)

The Empirical steady state method computes steady state by giving doses until the state variables no longer change according to the SSTOL/SSATOL tolerance specified in \$SUBROUTINES. The SS data item is not used. A negative value of ADDL requests the computation, and also specifies the maximum number of doses (ABS(ADDL)+1). See ADDL\_ACTUAL,ADDL\_TIME,ADDL\_TIMEDIFF reserved variables. May be used with any ADVAN.

I\_SS (Initial Steady State) for general non-linear models (nmvi2.0)

It is possible to specify initial conditions for the differential equations using the I\_SS (Initial Steady State) feature. Reserved variable ISSMOD may be used.

DES array: COMPACT vs. FULL for general non-linear models (nmv)

ISFINL reserved variable with AES and DES (nmvi)

Allows the abbreviated code to take special action on the final call to AES and DES for an integration interval.

TIME may be negative (nm74)

With NONMEM 7.4, PREDPP permits the TIME data item to be negative.

ITASK\_ and STOP\_TIME (nm75)

The ITASK\_ reserved variable may be set to 4 by the user to avoid overshoot in ADVAN9, ADVAN13, ADVAN14, and ADVAN15. The STOP\_TIME reserved variable may be set to a STOP\_TIME (Tcrit) past which it should not integrate, if it is different from the end of the normal integration interval.

HINIT\_, HMIN\_, and HMAX\_ (nm752)

The HMAX\_ may be set to a limiting level such as 0.01 or 0.1, to help the ODE solver (ADVANS 9, 13, 14, 15) to not miss very short modeled infusion rate, such as those generated by a Gamma function high N(>10). The initial step size HINIT\_ and minimum step size HMIN\_, may also be modified.

Absolute Tolerance for ADVAN 9,13,14,15,16,17,18

ODE ADVANS can have an absolute tolerance for each compartment, e.g. ANRD(1)=10.

Relative Tolerance for ADVAN 9,13,16,17,18

ODE ADVANS except 14 and 15 can have a relative tolerance for each compartment, e.g. NRD(1)=6.

Values of absolute (ANRD) and relative (NRD) tolerance can be set for each NONMEM step

Tolerance can be set for specific NONMEM steps, e.g.,

IF(NM\_STEP==EST\_STEP) ANRD(1)=10

## 6.5. NM-TRAN

### 6.5.1. General Features

Case-insensitivity (nm72)

Both lower and upper case may be used in the NM-TRAN control file.

Continuation and line length (nm73)

Any line may be continued with "&" and may be 67000 characters long.

Warning messages (nmv)

The numbers of warning messages of various types may be controlled using the \$WARNING record.

### 6.5.2. Data Preprocessor

\$DATA TRANSLATE (nmv, nm73)

Allows TIME and II values to be rescaled, with specified number of decimal points.

ill-formed data files (nmvi)

NM-TRAN is better able to handle a data file whose final line does not terminate correctly.

tabs in data files (nmvi)

^M in data files (nmvi)

NM-TRAN can read data files in which tabs are present, and whose lines end with ^M.

\$DATA BLANKOK (nmvi)

NM-TRAN will not allow blank lines in a data file unless the BLANKOK option is used.

Larger data files (nmvi)

The RECORDS=n option of \$DATA may specify a number as large as 99999999.

MISDAT Missing Data Indicator (nm74)

MISDAT specifies a numerical value indicating a missing data value in the data set, which is displayed on \$TABLE table outputs, but is safely interpreted as 0 by other steps of NONMEM.

NOFDATACSV Turn off production of FDATA.csv (nm752)

Specify NOFDATACSV to prevent FDATA.csv from being produced. This saves time for very large FDATA files.

### 6.5.3. Abbreviated Code

FORTTRAN 90/95 syntax may be used.

For example, logical expressions may be written using symbols ==,>, instead of .EQ., .GT., etc.

Increased number of THETA, ETA, EPS (nm72)

Subscripts of THETA, ETA, EPS may be as large as 999.

\$ABBR record: COMRES, COMSAV

Creates variables that are saved between nonmem passes. NONMEM Reserved variables COM, COMACT are used.

\$ABBR record: DERIV2 (nmIV), NOFASTDER(nm72) DERIV1 (nm74)

Affects generated code in FSUBS. See also NOFIRSTDERCODE reserved

variable in abbreviated code.

#### \$ABBR REPLACE (nm73)

Any character string may be replaced. This allows for symbolic reference to thetas, etas, and epsilons. Replacement with selection by data item and parameter is permitted.

With nm74, the syntax is more flexible. Symbolic labels for eta may be used in the \$TABLE record. Symbolic label substitutions will appear in the NONMEM report file and \$TABLE outputs. \$ESTIMATION record option NOSUB may be used to control label substitution in the NONMEM report file. \$TABLE record option NOSUB may be used to control label substitution in \$TABLE files. \$SCATTER record option NOSUB may be used to control label substitution in Scatterplots.

#### \$ABBR DECLARE (nm73)

Allows integer variables and array (subscripted) variables to be used in Abbreviated code.

#### Recursive abbreviated code (nmvi)

Allows a random variable to retain the value from the previous data record instead of being set to zero. May be used to implement recursive kinetics in \$PRED.

#### User-supplied functions FUNCA,FUNCB,FUNCC and VECTRA,VECTRB,VECTRC (nmvi)

FUNCA etc. are reserved names for user-supplied functions They may have scalar or vector-valued arguments. VECTRA etc. are reserved names for vectors used as arguments. When functions are used in abbreviated code, the eta derivatives of the arguments are computed correctly. Any vector may be used with any function. With NONMEM 7, there are more reserved functions and vectors.

#### \$ABBR FUNCTION, \$ABBR VECTOR (nm74)

In NONMEM 7.4 the \$ABBR FUNCTION option and \$ABBR VECTOR option allows user-defined function names and user-defined argument vector names.

#### PROTECT functions (nm74)

Versions of FORTRAN functions are available that protect against domain violations, divide by zero, and floating point overflows. For example, PLOG is the protective code routine that performs the LOG operation. The \$ABBR PROTECT record causes NM-TRAN to automatically replace FORTRAN functions in abbreviated code with the protective functions.

#### WRITE/PRINT statements

Character strings, format specification, Array options FULL vs. DIAG

#### DO WHILE, DO WHILE(DATA) statements

Looping; transgeneration.

#### Include files for NONMEM\_RESERVED variables (nm73)

If the name of an include file starts with NONMEM\_RESERVED, it may contain definitions of variables that will be parsed by NM-TRAN for use in abbreviated code.

### 6.5.4. Reserved Variables in Abbreviated Code

Here is a partial list of reserved variables that are not mentioned elsewhere in this guide.

#### ICALL

NONMEM reserved variable. Tells PRED when NONMEM is doing Run initialization, Problem initialization, Estimation, Problem finalization, Simulation,

Expectation, Data Average. (nmv)

#### NEWIND

NONMEM reserved variable. Tells PRED when data from a new individual record is starting.

#### NIREC, NDREC (nmvi)

#### FIRSTOBS, LASTOBS (nm74)

NONMEM reserved variables. Input data file record counters. NONMEM 7.4 provides additional record counters such as FIRSTOBS, LASTOBS, etc. in file nonmem\_reserved\_general.

#### LIREC NINDR INDR1 INDR2 reserved variables (nmvi2.0)

NONMEM reserved variables. Descriptive of the individual record.

#### MSEC, MFIRST, IFIRSTEM

NONMEM reserved variables. Tells PRED which derivatives to compute.

#### THETAFR, OMEGA, SIGMA, SETHET, SETHETR, SEOMEG, SESIGM (nmvi,nm74)

NONMEM reserved variables. The current values of OMEGA, SIGMA, et. al., may be used in abbreviated code.

#### IIDX,CNTID (nmvi)

NONMEM reserved variables. Individual contribution to the objective function.

#### PRED\_,RES\_,WRES\_, and other variables

Variables with similar names and the same values as statistical diagnostic items PRED\_, RES\_, WRES\_, CPRED\_, CRES\_\_\_, CWRES, etc., may be used on the right in \$PRED and \$ERROR blocks (nm7)

#### NONMEM\_reserved\_general (nm73)

This is a file in the util directory with declarations for many additional reserved variables.

## 6.6. Utility Routines

This is a list of utility programs found in the util directory.

#### nmfe75

The nmfe shell script has many new options, including options for parallel computing.

#### finedata

Augments an NM-TRAN data file to incorporate additional, non-observation, time values spaced at regular increments.

#### nmtemplate

Performs variable substitution on appropriately tagged control stream template files, and produces new control stream files. Compare with the \$ABBR REPLACE feature, above.

#### table\_quant

Transforms results in raw output file of \$COV SIRAMPLE step, places into a table file with frequencies and cumulative values

#### table\_resample

Resamples from raw output file of \$COV SIRAMPLE step, using the WEIGHT information

#### table\_compare

Compares the numerical values between two table files produced by the

- \$TABLE record.
- table\_to\_xml  
Converts additional output table files produced by NONMEM to XML Formatted files.
- xml\_compare  
Compares the contents of two NONMEM report XML files.
- doexpand  
Expand an NM-TRAN control stream file that has been annotated with DOE (which stands for DO expand) and ENDDOE (which stands for ENDDO expand) directives.
- ddexpand  
Expands a control stream file by adding equations for time-delay differential equation problems.
- neff Performs effective sample statistics on population parameters in raw output file generated by Bayesian or NUTS analysis
- neffi Performs effective sample statistics from individual parameters generated by Bayesian or NUTS analysis
- summary  
Perform quantile summaries from table outputs generated by \$SIML ... SUBP=xxx
- csvalign  
Pad a csv file with spaces so that columns line up for easier reading.
- lpsc Translates the line-printer directives in column 1 (such as 0 1, etc.) and replaces them with next line, next page, etc.
- lblr Insert User-Defined Labels in Additional Files.
- priorget  
Package results from a previous analysis into prior statements that can be used for a subsequent problem. Calculates degrees of freedom for \$OMEGEPD and \$SIGMAPD as well.

### 6.7. All Options for \$ESTIMATION

This section lists all options of the \$ESTIMATION record. Some are discussed earlier in this guide and are listed here for completion. Some options are only appropriate with specific estimation methods. For more information, see the \$ESTIMATION help item.

- 2LL (nmv)  
Y evaluated in \$ERROR or \$PRED is interpreted as -2 times log likelihood
- ATOL (nm72)  
Absolute tolerance adjustment for ADVAN9 and ADVAN13
- AUTO (nm73)  
Have NONMEM determine optimal settings for certain EM/Bayes options
- BAYES\_PHI\_STORE (nm75)  
When set to 1, stores phi and eta values from each BAYES iteration root.iph.
- BIONLY (nm75)  
When set to 1, will create new samples of individual parameters only during

BAYES analysis, but will keep the population parameters fixed.

BOOTDATA (nm75)

By default (BOOTDATA=0), when data are selected based on \$SIML BOOSTRAP, the randomly selected subjects are analyzed during the subsequent estimation method. If BOOTDATA=1, then the subjects not selected are analyzed.

CALPHA (nm7)

alpha error rate for Monte Carlo EM and Bayes convergence

CENTERING (nmv)

Impose centering of average empirical Bayes estimates (EBEs) about zero (FOCE).

CINTERVAL (nm7)

Correlation iteration interval for Monte Carlo EM and Bayes convergence

CITER/CNSAMP (nm7)

Number of iteration samples to use for Monte Carlo EM and Bayes convergence

CLOCKSEED (nm75)

If CLOCKSEED=1, the computer clock time will be used to help create a unique starting seed position for each new run of the control stream.

CONDITIONAL (nmiv)

Assess objective function around each subject's (conditional) etas during Estimation (FOCE/Laplace)

CONSTRAIN (nm72)

Impose algorithmic constraints on thetas through CONSTRAINT subroutine (EM/BAYES)

CTYPE (nm7)

Select convergence criterion

DERCONT (nm73)

Correct for derivative continuity in change of objective function with theta (SAEM/IMP)

DF (nm71)

degrees of freedom of t-distribution of sampling density for IMP and IMPMAP

DFS (nm73)

degrees of freedom for simulating initial SIGMAS (CHAIN only)

EONLY (nm71)

Expectation step only, no advancement of thetas or sigmas for EM methods. With nm74, also affects individual conditional means/modes and conditional variances, and approximate variances.

ETABARCHECK (nmvi)

p-value of ETABAR (mean EBEs) tests similarity to ETABAR of a previous problem

ETADER (nm73)

Select alternative finite difference methods for eta derivatives

ETASAMPLES (nm74)

Generates posterior density samples of etas

ETASTYPE (nm73)

Determine whether non-influential etas should be included in ETABAR/Shrinkage statistics

- FAST (nm74)  
Uses analytical derivatives of thetas and sigmas to speed up FOCE analyses
- FILE (nm71)  
specify alternative name for raw output file containing fixed effects parameters  
progress
- FNLETA (nm72)  
Determine how final etas are obtained for table outputs
- FORMAT/DELIM (nm71)  
specify alternative numerical format for output files.
- FPARAFILE (nm74)  
Turn ON or OFF parallelization of final etas evaluation.
- GRD (nm71)  
Specify gradient behavior of THETAS and SIGMAS for EM/BAYES methods
- GRDQ (nm74)  
Gradient quick option, specifying what number of fraction of importance samples generate should be used for gradient evaluation of non-mu modeled parameters
- GRID (nmvi)  
Set up search grid pattern for Stieltjes method
- HYBRID (nmv)  
Use conditional etas except for those etas listed in ZERO option (hybrid of FOCE and FO)
- IACCEPT (nm71)  
Acceptance/rejection ratio or proposal density coverage for EM/BAYES
- IACCEPTL (nm74)  
Scale a second multi-variate normal density, to cover long tails in the posterior density.
- IKAPPA (nm75)  
For ISAMPLE\_M1B, individual parameters are averaged using a weight of N to the -IKAPPA power for the Nth iteration, in obtaining the mean and variance-covariance for the ISAMPLE\_M1B mode.
- INTERACTION (nmiv)  
Assess residual variance (epsilon terms) using conditional (non-zero) etas.
- ISAMPEND (nm73)  
Maximum value for ISAMPLE
- ISAMPLE (nm71)  
Number of Monte Carlo ETA samples to collect for each subject
- ISAMPLE\_M1 (nm71)  
Number of ETA samplings to test in the OMEGA space (SAEM/BAYES)
- ISAMPLE\_M1A (nm72)  
Number of ETA samplings to test using ETA samples of other subjects (SAEM/BAYES)
- ISAMPLE\_M1B (nm75)  
Number of eta samplings to test, using the individual conditional mean and individual conditional variance collected from previous iterations as the proposal density.

- ISAMPLE\_M2 (nm71)  
Number of multi-variate ETA vector samplings to test in the local space (SAEM/BAYES)
- ISAMPLE\_M3 (nm71)  
Number of uni-variate ETA samplings to test in the local space (SAEM/BAYES)
- ISCALE\_MAX (nm72)  
Maximum factor to expand proposal density for ETA sampling (SAEM/BAYES/IMP/IMPMPAP)
- ISCALE\_MIN (nm72)  
Minimum factor to scale proposal density for ETA sampling (SAEM/BAYES/IMP/IMPMPAP)
- KAPPA (nm74)  
Specify power term to be used in average accumulating samples for mass matrix production for NUTS analysis
- KNUTHSUMOFF (nm74)  
Turn off precision retaining KnuthSUM algorithm when summing individual OFVs to produce total OFV.
- LAPLACE (nmiv)  
2nd Order conditional estimation method
- LEVCENTER (nm75)  
If LEVCENTER=1, ensures the etas of super ID random levels sum to 0. LEVCENTER=0 is now preferred.
- LEVOBJTYPE (nm751)  
If LEVOBJTYPE=0, then for IMP/ITS/FOCE/Laplace, the reported objective function (and what is used for estimation) is the average of two cycles of optimization. The first optimization floats all etas, and the second optimization fixes the super-ID etas to the appropriate average of etas per super-id group from the first optimization, and then floats the ID (and below) level etas. If LEVOBJTYPE=1, then the OBJ reported (and used for estimation) is only that of the second optimization cycle.
- LEVWT (nm74)  
Specify how to weigh subjects in nested random levels (\$LEVEL) problem
- LIKE (nmv)  
Y evaluated in \$ERROR or \$PRED is interpreted as likelihood
- LNTWOPI (nm74)  
Add the  $N \cdot \log(2\pi)$  term to the objective function
- MADAPT (nm74)  
Specify how the mass matrix is updated during a NUTS analysis
- MAPCOV (nm74)  
MAPCOV=1 is the default.
- MAPINTER (nm72)  
Iteration interval at which to use MAP estimates for proposal density (IMP)
- MAPITER (nm72)  
Number of first set of iterations at which to use MAP estimates for proposal density (IMP)

- MAPITERS (nm72)  
 Calcualte MAP estimates to use to start an SAEM analysis.
- MASSRESET (nm74)  
 Initialize mass matrix accumulation, or borrow from previous estimation.
- MAXEVAL (nmiv)  
 Maximum number of function evaluations (FO/FOCE/FOCEI/Laplace)
- MCETA (nm73)  
 Number of Monte Carlo samples to assess best starting eta vector for MAP estimation
- METHOD (nmiv)  
 Specify method of estimation
- MSFO (nmiv)  
 File name for containing estimation information to use in subsequent analyses
- MUFIRSTREC, OBJQUICK (nm74)  
 Prevent certain calcuations inside PREDPP, to allow for faster evaluation, especially for NUTS analysis
- MUM (nm71)  
 Turn on or off MU-referencing for EM/BAYES analysis
- NBURN (nm71)  
 Number of burn-in iterations for SAEM/BAYES methods
- NITER/NSAMPLE (nm71)  
 Number of iterations for EM/BAYES methods
- NOABORT (nmiv)  
 Have NONMEM Recover from numerical errors during estimation
- NOCOV (nm73)  
 Do not evaluate covaruiance step for particular estimation step
- NOHABORT (nm73)  
 Have NONMEM recover from all numerical errors during estimation (stronger than NOABORT)
- NOLABEL (nm71)  
 Do not print column names in additional output files
- NONINFETA (nm73)  
 Determine how NONMEM treats etas that do not influence the subject's data likelihood
- NOOMEGABOUNDTEST (nmvi)  
 Do not limit how much OMEGA elements may change in an estimation (FO/FOCE/Laplace)
- NOSIGMABOUNDTEST (nmvi)  
 Do not limit how much SIGMA elements may change in an estimation (FO/FOCE/Laplace)
- NOTHETABOUNDTEST (nmvi)  
 Do not limit how much THETA parameters change in an estimation (FO/FOCE/Laplace)
- NOSLOW  
 Don't use the slow method of OMEGA FOCE optimization (default)

- NOSUB (nm74)  
Turn off substitution of variable labels in Table headers.
- NOTITLE (nm71)  
Do not print title (header) in additional output files
- NOPRIOR (nm71)  
Turn on or off the contribution of the prior information
- NSIG (nmiv)  
number of significant digits for convergence criterion (classical methods, ITS)
- NUMDER (nm73)  
Output numerical and/or analytical ETA derivatives
- NUMERICAL (nmv)  
Use finite difference method for 2nd derivative ETAS in MAP estimation (Laplace, ITS, MAP, IMPMAP)
- NUTS\_BASE (nm74)  
Specify number of iterations for stage II of warmup process of NUTS analysis
- NUTS\_DELTA (nm74)  
Sample acceptance rate for NUTS analysis
- NUTS\_EPARAM (nm74)  
Specify parameterization for individual parameters/etas in NUTS analysis
- NUTS\_GAMMA (nm74)  
Gamma factor for NUTS algorithm
- NUTS\_INIT (nm74)  
Specify number of iterations for stage I of warmup process of NUTS analysis
- NUTS\_MASS (nm74)  
Specify whether mass matrix should be full, diagonal, block-diagonal, etc.
- NUTS\_MAXDEPTH (nm74)  
Sets the maximum number of total branchings to try in the NUTS algorithm in the search for the next decorrelated sample
- NUTS\_OPARAM (nm74)  
Specify parameterization for Omegas in NUTS analysis
- NUTS\_REG (nm74)  
Specify diagonal dominance algorithm for mass matrix in NUTS analysis.
- NUTS\_SPARAM (nm74)  
Specify parameterization for Sigmas in NUTS analysis
- NUTS\_STEPINTER (nm74)  
An initial step size is calculated every NUTS\_STEPINTER iterations.
- NUTS\_STEPITER (nm74)  
An initial step size is calculated for the first NUTS\_STEPITER iterations.
- NUTS\_TERM (nm74)  
Specify number of iterations for stage III of warmup process of NUTS analysis
- NUTS\_TEST (nm74)  
Specify acceptance/rejection algorithm in NUTS algorithm
- NUTS\_TRANSFORM (nm74)  
Specify whether estimation parameters or momentum parameters are to be

transformed in NUTS algorithm.

- OACCEPT (nm7)  
Select acceptance/rejection ratio for Metroplis-Hastings algorithm of finding OMEGAS (BAYES)
- OLKJDF (nm74)  
Set degrees of freedom for LKJ correlation for Omegas
- OLNTWOPI (nm74)  
Include  $\log(2\pi)$  degrees of freedom from eta density portion of objective function
- OMEGABOUNDTEST (nm74)  
Limit how much OMEGA elements may change in an estimation (FO/FOCE/Laplace)
- OMITTED (nmiv)  
Omit estimation
- OPTMAP (nm73)  
Select optimization method for MAP estimation
- ORDER (nm72)  
Select ordering of fixed effects parameters in raw output file
- OSAMPLE\_M1 (nm71)  
Number of samples for Metroplis-Hastings global search of finding OMEGAS (BAYES)
- OSAMPLE\_M2 (nm71)  
Number of samples for Metroplis-Hastings local search of finding OMEGAS (BAYES)
- OSAMPLE\_M3 (nm75)  
Number of samples for generating individual cholesky elements of OMEGA.
- OVARF (nm74)  
The weight to STD prior to the log sqrt OMEGA diagonal elements
- PACCEPT (nm71)  
Select acceptance/rejection ratio for Metroplis-Hastings algorithm of finding THETAS/SIGMAS (BAYES)
- PARAFILE (nm72)  
Specify new parallization file for estimation, or turn ON/OFF parallelization
- PARAFPRINT (nm74)  
Print iteration interval for parallelization log file
- PHITYPE (nm74)  
have .phi file contain conditional means phis or etas
- POSTHOC (nmiv)  
Assess EBEs for each subject after FO estimation
- PREDICTION (nmv)  
Determines how Y or F is interpreted with simulation
- PRINT (nmiv)  
Iteration print interval
- PRIORC (nm75)  
Have the objective function reported include the constant term to the prior.

- PSAMPLE\_M1 (nm71)  
 Number of samples for Metroplis-Hastings (MH) global search of finding THETAS/SIGMAS (BAYES)
- PSAMPLE\_M2 (nm71)  
 Number of samples for MH local multi-variate search of finding THETAS/SIGMAS (BAYES)
- PSAMPLE\_M3 (nm71)  
 Number of samples for MH local uni-variate search of finding THETAS/SIGMAS (BAYES)
- PSCALE\_MIN (nm73)  
 Minimum factor to expand prospool density for MH sampling of THETAS/SIGMAS(BAYES)
- PSCALE\_MAX (nm73)  
 Maximum factor to scale prospool density for MH sampling of THETAS/SIGMAS(BAYES)
- RANMETHOD (nm72)  
 Select random number generator and behavior for Monte Carlo EM and BAYES methods
- REPEAT (nmiv)  
 repeat estimation starting at final parameters from first loop (FO/FOCE/Laplace)
- REPEAT1 (nmvi)  
 repeat first stage of Stieltjes estimation
- REPEAT2 (nmvi)  
 repeat second stage of Stieltjes estimation
- SADDLE\_HESS (nm74)  
 Selects type of Hessian to be used for Saddle reset process
- SADDLE\_RESET (nm74)  
 Set the number of times a saddle\_reset is performed
- SEED (nm7)  
 Select starting seed for Monte Carlo EM and Bayes methods
- SIGL (nm7)  
 Significant digits of individual objective function assessment
- SIGLO (nm72)  
 Significant digits to assess ETAS in MAP estimation
- SLOW (nmvi)  
 Use slow method of advancing fixed effects parameters
- SIGMABOUNDTEST (nmvi)  
 Limit how much SIGMA elements may change in an estimation (FO/FOCE/Laplace)
- SLKJDF (nm74)  
 Set degrees of freedom for LKJ correlation for Sigmas
- SORT (nmvi)  
 Sort individual objective function values before summing into total objective function

- STDOBJ (nm73)  
Stochastic standard deviation tolerance of objective function to determine best ISAMPLE for IMP/IMPMPAP
- STIELTJES (nmvi)  
Higher order assessment of objective function
- SVARF (nm74)  
The weight to STD prior to the log sqrt Sigma diagonal elements
- TBLN (nm75)  
Select table number TBLN from the chain file.
- THETABOUNDTEST (nmvi)  
Limit how much THETA parameters change in an estimation (FO/FOCE/Laplace)
- THIN (nm74)  
Sample intervals to be recorded in the raw output file for Bayesian analysis
- TPU (nm75)  
Select user-defined prior for thetas.
- TTDF (nm74)  
Set t-distribution degrees of freedom for priors to Thetas
- ZERO (nmv)  
List of etas for which conditional etas are not to be used in HYBRID method
- References: Introduction to NONMEM 7

### 6.8. All Options for \$COVARIANCE

This section lists all options of the \$COVARIANCE record. Some are discussed earlier in this guide and are listed here for completion. For more information, see the \$COVARIANCE help item.

- ATOL (nm73)  
Absolute tolerance for differential equation problems
- CHOLROFF (nm74)  
Have R matrix evaluated according to earlier versions of NONMEM.
- COMPRESS (nmv)  
Covariance Step arrays are printed in compressed format regardless of dimension size of covariance of estimates
- CONDITIONAL (nmiv)  
Evaluate covariance step only if estimation successful
- FAST (nm74)  
Uses analytical derivatives of thetas and sigmas to speed up covariance step
- FILE (nm74)  
Select file name of raw output file for SIR sampling
- FORMAT (nm74)  
Select format of numbers to be written to raw output file during SIR sampling
- FPOSDEF (nm74)  
Force positive definiteness on R matrix after Preconditioning
- IACCEPT (nm74)  
Acceptance rate (sampler expansion) during SIR importance sampling

- IACCEPTL (nm74)  
Acceptance rate of the secondary sampler during SIR Importance sampling
- KNUTHSUMOFF (nm74)  
Turn off precision retaining KnuthSUM algorithm when summing individual OFVs to produce total OFV.
- MATRIX (nmiv)  
Select type of Information matrix to be evaluated during Covariance step
- NOFCOV (nm72)  
Turn off covariance estimation for FOCE method
- NOSLOW (nm72)  
Use analytical derivatives of Omegas to evaluate gradients during covariance step
- PARAFIELD (nm74)  
Control parallelization during \$COV step
- PARAFPRINT (nm74)  
Print iteration interval for parallelization log file during covariance step
- PFCOND (nm74)  
Force preconditioning even if Rmatrix is positive definite during covariance step
- POSDEF (nm74)  
Specify positive definite filtering.
- PRECOND (nm74)  
Set number of preconditioning cycles to perform during covariance step
- PRECONDS (nm74)  
Select whether preconditioning should be done on Thetas, Omegas, and/or Sigmas of R matrix portion in covariance step
- PRETYPE (nm74)  
Select the R matrix corrector type when preconditioning during the variance-covariance step.
- PRINT (nmiv)  
Select to Print out additional matrices and items (E=eigenvalues, R=R matrix, S=S matrix)
- RANMETHOD (nm74)  
Select randomization method for SIR sampling
- RESUME (nm73)  
Collect intermediate information to resume covariance step if interrupted
- SIGL (nm71)  
Significant digits of individual objective function assessment during covariance step
- SIGLO (nm72)  
Significant digits to assess ETAS in MAP estimation during covariance step
- SIRCENTER (nm74)  
Where the sampling (proposal) density is to be centered during SIR sampling
- SIRCLOCKSEED (nm75)  
Initialize SIRSEED by the clock time, to create unique initial seeds on each run.
- SIRDF (nm74)  
Degrees of freedom of t-distribution sampler used during SIR sampling

- SIRMAXWT (nm75)  
Limit the maximal weight that a sample may have relative to the proposal density, to avoid extreme values.
- SIRMINWT (nm75)  
Limit the minimal weight that a sample may have relative to the proposal density, to avoid extreme values.
- SIRNITER (nm74)  
The number of times to perform SIR sampling
- SIRPARAFILE (nm75)  
Control parallization of SIR analysis.
- SIRPARAFPRINT (nm75)  
How often to print out parafile information in .log file
- SIRPRINT (nm74)  
Set the console print iterations interval during SIR sampling of covariance step
- SIRSAMPLE (nm74)  
Number of random samples to generate during SIR sampling of covariance step.
- SIRSEED (nm75)  
Initial seed for SIR sampling.
- SIRTHBND (nm74)  
Determines whether R and S matrix are evaluated in uncosntrained or constrained domain for thetas during SIR sampling
- SIR\_CAPCORR (nm75)  
Limit the correlation of omegas and sigmas generated from the proposal density to have |correlation| of SIR\_CAPCORR or less.
- SLOW (nmvi)  
Have Omega gradients evaluated numerically
- SPECIAL (nmiv)  
The special computation will be used in the Covariance Step with a recursive PRED subroutine.
- THBND (nm74)  
Determines whether R and S matrix are evaluated in uncosntrained or constrained domain for thetas during main covariance step
- TOL (nm72)  
Selects relative tolerance for differential equation integration during covariance step
- UNCONDITIONAL (nmiv)  
Evaluate covaraince step whether or not estimation successful

References: Introduction to NONMEM 7

## Chapter 13 - Errors in NONMEM Runs

### 1. What This Chapter is About

This chapter describes error messages that can appear in NONMEM's output and discusses some possible causes and remedies. It is not encyclopedic; only selected messages are discussed. NM-TRAN messages are meant to be self-explanatory, as are many PREDPP messages, and important NONMEM messages are documented in NONMEM Users Guide, Part I, Chapter G. Unlike certain other regression programs, NONMEM-PREDPP will not try to mask what is perceived as a real problem and to which attention must be given by the user before the computation can proceed; an error message results and often, the program terminates.

The Estimation and Covariance Steps do not always terminate successfully. This is a normal part of the process of model building.

### 2. Abnormal Termination of the Estimation Step

Normal termination of the Estimation Step is indicated by the message:

**MINIMIZATION SUCCESSFUL**

Even when this message is seen, it is possible that the Estimation Step has not run correctly. Final estimates should be different from initial estimates. If the initial and final estimates are the same and the gradients for a parameter are zero at every iteration<sup>†</sup>, this is a sign of a modelling error. The parameter does not affect any predictions, as discussed in Chapter 7, Section 4.2. If there were bounds, estimates should be well away from the bounds. A final estimate which is close to a bound is discussed in Chapter 11, Section 4.3.

Abnormal termination of the Estimation Step is indicated by a message whose first line is:

**MINIMIZATION TERMINATED**

One of several messages will follow, indicating the type of failure. The messages are listed in Users Guide I.

Two of the most common are discussed here separately.

#### 2.1. "DUE TO MAX. NO. OF FUNCTION EVALUATIONS EXCEEDED"

If after any iteration the total number of evaluations of the objective function (Chapter 10, figure 10.5, line 33) is equal to or greater than the maximum allowed (Chapter 10, figure 10.2, line 51), the minimization search is halted with this message. If the \$ESTIMATION record requested that a Model Specification File be written, it is possible to continue the search from this point in a subsequent NONMEM run. In Chapter 12, Section 4.3, a strategy is discussed by which the number of function evaluations is deliberately set to a low value in order to structure a lengthy run as a series of shorter runs.

Whenever this message is obtained, it is important to examine the intermediate output and evaluate the progress made so far. A poorly-specified model, for example, may cause very slow convergence of the minimization search. Raising the maximum number of function evaluations (using the MAXEVAL option of the \$ESTIMATION record) may not be advisable.

<sup>†</sup> A gradient may reach zero at or near the final iteration; this is not an error. Note also that no gradient is computed or printed for a parameter whose value is fixed, so if a gradient is always zero, it is not for this reason.

## 2.2. "DUE TO ROUNDING ERRORS (ERROR=134)"

This message will be accompanied in the intermediate output by a message beginning: NUMSIGDIG: .... which gives the approximate number of significant digits obtained in each of the parameters being estimated. At least one such number will be less than the number requested.

The number of significant digits obtained should be examined. If it is at least 2, and the gradient vector appears stable throughout the last few iterations, a satisfactory minimum may well have been obtained. (It may be desirable to re-run the problem with the print interval for iteration summarization set to 1 (PRINT=1 in the \$ESTIMATION record) so that the progress made at every iteration can be examined.) The final parameter estimates should be examined, and if they appear reasonable, they might be accepted. Although the user may have requested more than 2 significant digits, the data may only support about 2 digits, given the precision of the arithmetic being used. By examining the gradients carefully, it is often possible to obtain further information about which parameter estimates are less-well determined.

Even though the final parameter estimates may be adequate, it is unlikely that the minimum is sufficiently well-determined to allow the Covariance Step to run successfully, at least with the number of significant figures requested in the Estimation Step. The Estimation Step may need to be rerun, requesting only 2 significant figures, followed by the Covariance Step.

If the number of significant digits is less than 2 (or even negative), then the final estimates should not be trusted. The problem may be model misspecification or insufficient data.

Model misspecification is a very general problem involving some mismatch between the model and the data. This can result in particularly large values of the objective function or slow convergence of the minimization search. Sometimes the model is overparameterized. This means that the model has more parameters than can be well-enough estimated from the data (e.g., a biexponential model is fit to monoexponential data). When model misspecification occurs due to over-parameterization, then the Estimation Step will usually proceed smoothly, but terminate with fewer than 2 significant digits. It is best to start with simple models (see Chapter 11).

A related problem arises when a covariance element, e.g.,  $\Omega_{12}$  (or  $\Sigma_{12}$ ), is being estimated. If the ID (or L2 data item) is not used correctly, it may appear as though the covariance does not affect objective function values, and then this parameter will not be well estimated. In other words, it may appear as though the model is overparameterized due to the inclusion of this parameter. See Chapter 12, Section 4.2.

## 3. Abnormal Termination of the Covariance Step

It is possible for the Estimation Step to terminate successfully, and yet the Covariance Step generates an error message. Error messages from the Covariance Step are printed immediately after line 46 of Figure 10.5. The messages are listed in Users Guide I.

When a message arises, often it is:

```
R MATRIX ALGORITHMICALLY NON-POSITIVE-SEMIDEFINITE  
BUT NONSINGULAR  
COVARIANCE STEP ABORTED
```

In order for the minimization routine to terminate successfully, it needs to determine that the final gradient vector is sufficiently small, which is a necessary condition for a minimum to have been achieved. This condition, however, is not sufficient. A sufficient

condition, that the R matrix be positive definite (and therefore, that the apparent minimum not be a saddle point) is only checked in the Covariance Step. The message means that the sufficient condition appears not to be satisfied. The final estimate is, therefore, in doubt.

Sometimes the message is:

```
R MATRIX ALGORITHMICALLY SINGULAR
COVARIANCE STEP UNOBTAINABLE
S MATRIX ALGORITHMICALLY SINGULAR
```

This arises when there exists a parameter whose values do not actually affect the predictions and whose gradient in the intermediate output is always 0.

In general, successful completion of the Covariance Step requires a better defined minimum than does the successful completion of the Estimation Step.

#### 4. Miscellaneous Problems

This section discusses a few simple errors which prevent NONMEM-PREDPP from running successfully.

##### 4.1. Proportional Error Model

A common error is to use the proportional error model while some predicted values for actual observations are zero or close to zero. (For example, if the first dose is an infusion and there is a "baseline" observation at the start of the infusion, the predicted level will be zero.)

With individual data this will lead to an error message similar to the following (the individual number may be different from 1):

```
PROGRAM TERMINATED BY OBJ, ERROR IN ELS
WITH INDIVIDUAL 1 (IN INDIVIDUAL RECORD ORDERING)
VAR-COV OF DATA FROM INDIVIDUAL RECORD ESTIMATED TO BE SINGULAR
```

With population data this will lead to an error message similar to the following (the individual and record numbers may be different than 1):

```
PROGRAM TERMINATED BY OBJ, ERROR IN CELS
WITH INDIVIDUAL 1 (IN INDIVIDUAL RECORD ORDERING)
INTRAINDIVIDUAL VARIANCE OF DATA FROM OBS RECORD 1 ESTIMATED TO BE 0
```

##### 4.2. Errors in the Pharmacokinetic Model

When using a new model, a run should be done in which the Estimation Step is not run, and a scatterplot of PRED vs DV with unit slope line is produced, to verify that the model and the initial parameter estimates are reasonable. It is much harder to diagnose errors in the model or the initial estimates after the Estimation Step fails. Make sure that the initial value of the objective function is not excessively large, and that the unit slope line shows on the plot: scaling errors can easily go undetected! E.g., if the units are incorrect at some point in the model (L vs ml), the predictions may be wrong by a factor of 1000. Similarly, if no scale was specified for the compartment being observed, the predictions for the observations are compartment amounts rather than concentrations. In both cases, the shape of the PRED vs DV plot may appear linear, but the axes may be labeled quite differently. When observations from two different compartments are present in the data (e.g.,  $C_p$  and  $C_u$ ), some of the observations may be scaled incorrectly. This is discussed

in Chapter 6, Section 9, and Chapter 7, Section 4.3.3.

## 5. Errors with PREDPP

### 5.1. Error Messages from a TRANS Routine

TRANS routines can produce error messages. Here is one from TRANS2:

ERROR IN TRANS2 ROUTINE: V IS ZERO

Appendix 2 shows that TRANS2 normally computes  $K=CL/V$ . The routine checks that  $V$  is not zero, and upon finding that it is, it prints the informative message, and terminates the run (thus avoiding a machine "division by zero" interrupt by the operating system). This error usually occurs with the initial parameter estimates. E.g., suppose the relevant \$PK statement is:

**V=THETA (1) +WT\*THETA (2)**

For some values of  $\theta_1$ ,  $\theta_2$ , and  $WT$ , a value of zero is being computed for  $V$ . The initial estimates of  $\theta_1$  and  $\theta_2$  should be checked. The intercept  $\theta_1$  might have been fixed to zero, in which case then, the values of  $WT$  should also be checked. If  $WT$  is recorded only on the first event record of each individual's data, careful coding is required to insure that a value of zero is not used when the \$PK record is evaluated with subsequent event records.

### 5.2. Error Messages from ADVAN Routines

A similar error message can be generated in PREDPP, e.g.

PK PARAMETER FOR OBSERVATION COMPARTMENT'S SCALE IS ZERO

Some scale parameter is modeled in such a way as to produce a zero. Again, the code for that scale parameter, and the initial estimates for the  $\theta$ 's used therein, should be checked. Perhaps the scale parameter is being set equal to a volume parameter, and as described above, the volume parameter is being set to zero. When TRANS1 is used, the volume parameter is neither recognized nor checked.

### 5.3. Numeric difficulties in PREDPP

Numeric difficulties can occur with linear pharmacokinetic models (e.g., ADVAN1-4) in the process of computing certain exponentials. They can occur from an error in the units of either a rate constant and/or the TIME data items. They can also occur from inordinately large values for a rate constant which arise during the minimization search. This might be avoided by placing appropriate constraints on  $\theta$ 's.

They can also occur when the system is advanced over an excessively long period of time. This can happen within an individual record, when the individual had a course of drug treatment, followed by a wash-out period, followed by another course of drug treatment. The first dose record of treatment courses other than the first should have EVID data item equal to 4 (reset-dose) rather than 1 (dose), to avoid computing excessively small compartment amounts (see Chapter 6, Section 7.3), and to reduce computational cost.

Difficulties can occur in the process of computing predictions with ADVAN2 and ADVAN4 when values of  $KA$  and  $K$  arise during the minimization search that are very close to one another. The models encoded into the ADVAN routines assume that  $KA$  and  $K$  have fairly distinct values, and the formulas for the predictions have the term  $KA-K$  in the denominator. If, for example, the typical values of  $K$  and  $KA$  are associated with  $\theta_1$  and  $\theta_2$ , respectively, then one might try reparameterizing. The typical values of  $K$  and  $KA-K$  can be associated with  $\theta_1$  and  $\theta_2$ , so that  $\tilde{K} = \theta_1$  and  $\tilde{KA} = \tilde{K} + \theta_2$ . A lower bound

of zero should be placed on  $\theta_2$ †.

A similar situation occurs with TRANS3, where VSS-V occurs in the denominator of the expression for K21. As above, reparameterization and a constraint on an element of  $\theta$  may help.

---

† This technique also prevents a "flip-flop" from occurring. (In the original parameterization, the final estimates of  $\theta_1$  and  $\theta_2$  can be the final estimates of the typical values of KA and K, respectively).

## Appendix 1 - Standard Pharmacokinetic Models and Parameters

| ADVAN   | Compartments   | Basic and additional PK parameters           |   |
|---------|--|--|---|
| ADVAN1  | 1 = Central<br>2 = Output                                | K  | Rate constant of elimination  |
|         |  | S1<br>S2<br>F1<br>F0                         | Scale for central compartment<br>Scale for output compartment<br>Bioavailability for central compartment<br>Output Fraction   |
| ADVAN2  | 1 = Depot<br>2 = Central<br>3 = Output                   | KA<br>K                                      | Absorption rate constant<br>Rate constant of elimination  |
|         |  | S1<br>S2<br>S3<br>F1<br>F2<br>F0             | Scale for depot compartment<br>Scale for central compartment<br>Scale for output compartment<br>Bioavailability for depot compartment<br>Bioavailability for central compartment<br>Output Fraction   |
| ADVAN3  | 1 = Central<br>2 = Peripheral<br>3 = Output              | K<br>K12<br>K21                              | Rate constant of elimination<br>Rate constant from central to peripheral<br>Rate constant from peripheral to central  |
|         |  | S1<br>S2<br>S3<br>F1<br>F2<br>F0             | Scale for central compartment<br>Scale for peripheral compartment<br>Scale for output compartment<br>Bioavailability for central compartment<br>Bioavailability for peripheral compartment<br>Output Fraction   |
| ADVAN4  | 1 = Depot<br>2 = Central<br>3 = Peripheral<br>4 = Output | KA<br>K<br>K23<br>K32                        | Absorption rate constant<br>Rate constant of elimination<br>Rate constant from central to peripheral<br>Rate constant from peripheral to central  |
|         |  | S1<br>S2<br>S3<br>S4<br>F1<br>F2<br>F3<br>F0 | Scale for depot compartment<br>Scale for central compartment<br>Scale for peripheral compartment<br>Scale for output compartment<br>Bioavailability for depot compartment<br>Bioavailability for central compartment<br>Bioavailability for peripheral compartment<br>Output Fraction |
| ADVAN10 | 1 = Central<br>2 = Output                                | VM<br>KM                                     | Maximum Rate<br>Michaelis Constant  |
|         |  | S1<br>S2<br>F1<br>F0                         | Scale for central compartment<br>Scale for output compartment<br>Bioavailability for central compartment<br>Output Fraction   |

Appendix 1 - Standard Pharmacokinetic Models and Parameters"

| ADVAN   | Compartments   | Basic and additional PK parameters |   |
|---------|--|------------------------------------|---|
| ADVAN11 | 1 = Central<br>2 = Peripheral 1<br>3 = Peripheral 2<br>4 = Output              | K                                  | Rate constant of elimination              |
|         |  | K12                                | Rate constant from central to periph. 1   |
|         |  | K21                                | Rate constant from periph. 1 to central   |
|         |  | K13                                | Rate constant from central to periph. 2   |
|         |  | K31                                | Rate constant from periph. 2 to central   |
|         |  | S1                                 | Scale for central compartment             |
|         |  | S2                                 | Scale for peripheral 1 compartment        |
|         |  | S3                                 | Scale for peripheral 2 compartment        |
|         |  | S4                                 | Scale for output compartment              |
|         |  | F1                                 | Bioavailability for central compartment   |
|         |  | F2                                 | Bioavailability for periph. 1 compartment |
|         |  | F3                                 | Bioavailability for periph. 2 compartment |
|         |  | F0                                 | Output Fraction                           |
| ADVAN12 | 1 = Depot<br>2 = Central<br>3 = Peripheral 1<br>4 = Peripheral 2<br>5 = Output | KA                                 | Absorption rate constant                  |
|         |  | K                                  | Rate constant of elimination              |
|         |  | K23                                | Rate constant from central to periph. 1   |
|         |  | K32                                | Rate constant from periph. 1 to central   |
|         |  | K24                                | Rate constant from central to periph. 2   |
|         |  | K42                                | Rate constant from periph. 2 to central   |
|         |  | S1                                 | Scale for depot compartment               |
|         |  | S2                                 | Scale for central compartment             |
|         |  | S3                                 | Scale for peripheral 1 compartment        |
|         |  | S4                                 | Scale for peripheral 2 compartment        |
|         |  | S5                                 | Scale for output compartment              |
|         |  | F1                                 | Bioavailability for depot compartment     |
|         |  | F2                                 | Bioavailability for central compartment   |
|         |  | F3                                 | Bioavailability for periph. 1 compartment |
|         |  | F4                                 | Bioavailability for periph. 2 compartment |
|         |  | F0                                 | Output Fraction                           |

## Appendix 2 - Alternative Parameterizations

| Alternative Parameters |  | Reparameterization Lines     |                      |
|------------------------|--|------------------------------|----------------------|
| <b>ADVAN1</b>          | <b>TRANS2</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V                       |                      |
| V                      | Volume of distribution                 |                              |                      |
| <b>ADVAN2</b>          | <b>TRANS2</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V                       |                      |
| V                      | Volume of distribution                 | KA=KA                        |                      |
| KA                     | Absorption rate                        |                              |                      |
| <b>ADVAN3</b>          | <b>TRANS3</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V                       |                      |
| V                      | Central Volume                         | K12=Q/V                      |                      |
| Q                      | Intercompartmental clearance           | K21=Q/(VSS-V)                |                      |
| VSS                    | Volume of distribution at steady state |                              |                      |
| <b>ADVAN3</b>          | <b>TRANS4</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V1                      |                      |
| V1                     | Central volume                         | K12=Q/V1                     |                      |
| Q                      | Intercompartmental clearance           | K21=Q/V2                     |                      |
| V2                     | Peripheral volume                      |                              |                      |
| <b>ADVAN3</b>          | <b>TRANS5</b>                          |                              |                      |
| AOB                    | A/B                                    | K21=(AOB*BETA+ALPHA)/(AOB+1) |                      |
| ALPHA                  | alpha                                  |                              | K=ALPHA*BETA/K21     |
| BETA                   | beta                                   |                              | K12=ALPHA+BETA-K21-K |
| <b>ADVAN3</b>          | <b>TRANS6</b>                          |                              |                      |
| ALPHA                  | alpha                                  | K=ALPHA*BETA/K21             |                      |
| BETA                   | beta                                   | K12=ALPHA+BETA-K21-K         |                      |
| K21                    | Rate constant from periph. to central  | K21=K21                      |                      |
| <b>ADVAN4</b>          | <b>TRANS3</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V                       |                      |
| V                      | Central Volume                         | K23=Q/V                      |                      |
| Q                      | Intercompartmental clearance           | K32=Q/(VSS-V)                |                      |
| VSS                    | Volume of distribution at steady state | KA=KA                        |                      |
| KA                     | Absorption rate                        |                              |                      |
| <b>ADVAN4</b>          | <b>TRANS4</b>                          |                              |                      |
| CL                     | Clearance                              | K=CL/V2                      |                      |
| V2                     | Central volume                         | K23=Q/V2                     |                      |
| Q                      | Intercompartmental clearance           | K32=Q/V3                     |                      |
| V3                     | Peripheral volume                      | KA=KA                        |                      |
| KA                     | Absorption rate                        |                              |                      |

| <b>ADVAN4 TRANS5</b>  |   |  |
|-----------------------|---|--|
| AOB                   | A/B                                     | $K_{32}=(AOB*BETA+ALPHA)/(AOB+1)$                                |
| ALPHA                 | alpha                                   | $K=ALPHA*BETA/K_{32}$  |
| BETA                  | beta                                    | $K_{23}=ALPHA+BETA-K_{32}-K$                                     |
| KA                    | Absorption rate                         | $KA=KA$  |
| <b>ADVAN4 TRANS6</b>  |   |  |
| ALPHA                 | alpha                                   | $K=ALPHA*BETA/K_{32}$  |
| BETA                  | beta                                    | $K_{23}=ALPHA+BETA-K_{32}-K$                                     |
| K32                   | Rate constant from periph. to central   | $K_{32}=K_{32}$  |
| KA                    | Absorption rate                         | $KA=KA$  |
| <b>ADVAN11 TRANS4</b> |   |  |
| CL                    | Clearance                               | $K=CL/V_1$   |
| V1                    | Central volume                          | $K_{12}=Q_2/V_1$   |
| Q2                    | Intercompartmental clearance 1          | $K_{21}=Q_2/V_2$   |
| V2                    | Peripheral volume 1                     | $K_{13}=Q_3/V_1$   |
| Q3                    | Intercompartmental clearance 2          | $K_{31}=Q_3/V_3$   |
| V3                    | Peripheral volume 2                     | $V_3=V_3$  |
| <b>ADVAN11 TRANS6</b> |   |  |
| ALPHA                 | alpha                                   | $K=ALPHA*BETA*GAMMA/(K_{21}*K_{31})$                             |
| BETA                  | beta                                    | $V_1=ALPHA+BETA+GAMMA$   |
| GAMMA                 | gamma                                   | $V_2=ALPHA*BETA+ALPHA*GAMMA$                                     |
| K21                   | Rate constant from periph. 1 to central | $+BETA*GAMMA$  |
| K31                   | Rate constant from periph. 2 to central | $K_{13}=(V_2+K_{31}*K_{31}-K_{31}*V_1-K*K_{21})/(K_{21}-K_{31})$ |
|                       |   | $K_{12}=V_1-K-K_{13}-K_{21}-K_{31}$                              |
| <b>ADVAN12 TRANS4</b> |   |  |
| CL                    | Clearance                               | $K=CL/V_2$   |
| V2                    | Central volume                          | $K_{23}=Q_3/V_2$   |
| Q3                    | Intercompartmental clearance 1          | $K_{32}=Q_3/V_3$   |
| V3                    | Peripheral volume 1                     | $K_{24}=Q_4/V_4$   |
| Q4                    | Intercompartmental clearance 2          | $K_{42}=Q_4/V_4$   |
| V4                    | Peripheral volume 2                     | $V_4=V_4$  |
| KA                    | Absorption rate                         | $KA=KA$  |
| <b>ADVAN12 TRANS6</b> |   |  |
| ALPHA                 | alpha                                   | $K=ALPHA*BETA*GAMMA/(K_{32}*K_{42})$                             |
| BETA                  | beta                                    | $V_2=ALPHA+BETA+GAMMA$   |
| GAMMA                 | gamma                                   | $V_3=ALPHA*BETA+ALPHA*GAMMA$                                     |
| K32                   | Rate constant from periph. 1 to central | $+BETA*GAMMA$  |
| K42                   | Rate constant from periph. 2 to central | $K_{24}=(V_3+K_{42}*K_{42}-K_{42}*V_2-K*K_{32})/(K_{32}-K_{42})$ |
|                       |   | $K_{23}=V_2-K-K_{24}-K_{32}-K_{42}$                              |
| KA                    | Absorption rate                         | $KA=KA$  |

### Appendix 3 - NM-TRAN Control Records

The following is an alphabetic list of NM-TRAN control records.

See Guide VIII, On-line Help, or On-line HTML for the options and for more information. See Appendix 4 for the corresponding NONMEM control records (FCON).

**\$ABBREVIATED**  
**\$AES**  
**\$AESINIT**  
**\$ANNEAL**  
**\$BIND**  
**\$CHAIN**  
**\$CONTR**  
**\$COVARIANCE**  
**\$DATA**  
**\$DEFAULTS**  
**\$DES**  
**\$DESIGN**  
**\$ERROR**  
**\$ESTIMATION**  
**\$ETAS**  
**\$FORMAT**  
**\$INDEX**  
**\$INFN**  
**\$INPUT**  
**\$LEVEL**  
**\$LDFOLD**  
**\$MIX**  
**\$MODEL**  
**\$MSFI**  
**\$NONPARAMETRIC**  
**\$OMEGA**  
**\$OMEGAP**  
**\$OMEGAPD**  
**\$OLKJDF**  
**\$OMIT**  
**\$OVARF**  
**\$PHIS**  
**\$PK**  
**\$PRED**  
**\$PRIOR**  
**\$PROBLEM**  
**\$RCOV**  
**\$RCOVI**  
**\$SCATTER**  
**\$SIGMA**  
**\$SIGMAP**  
**\$SIGMAPD**  
**\$SIMULATION**

**\$SIZES**  
**\$SLKJDF**  
**\$SUBROUTINES**  
**\$SUPER**  
**\$SVARF**  
**\$TABLE**  
**\$THETA**  
**\$THETAI**  
**\$THETAP**  
**\$THETAPV**  
**\$THETAR**  
**\$TTDF**  
**\$TOL**  
**\$WARNING**

## Appendix 4 - NONMEM Control Records (FCON)

The following is a list of NONMEM control records and options. These are generated by NM-TRAN in a file called FCON. They are listed in the order that they appear in FCON.

Records marked with \* may be continued. The record name, e.g., "INDX", is not repeated on continuation(s). Any time a field may contain 0, it may contain blanks instead, which are read as 0. Constants SD, PD, LVR are from SIZES. Constants INF, INTBIG, INTSMALL indicate the largest floating point number, the largest integer value, and smallest integer value, respectively, that can be represented in the computer's architecture. (In some cases, e.g., BOOTSTRAP option of SIMULATION, it means an integer of up to 11 digits).

**FILE record** **(FILE)** **(A4, 4X, A72)**

| Field No. | Value    | Function            |
|-----------|----------|---------------------|
| 1         | NULL     | no file stream      |
|           | 72 chars | name of file stream |

**SUPER record** **(SUPR)** **(A4, 4X, I4, I8, I4)**

| Field No. | Value  | Function   |
|-----------|--------|--|
| 1         | 1-9999 | Number of problems in the superproblem                   |
| 2         | 2-9999 | Number of iterations of the superproblem.                |
| 3         | 0      | Input information will be printed for first problem only |
|           | 1      | Input information will be printed for all problems       |

**PROBLEM record** **(PROB)** **(A4, 4X, A72)**

| Field No. | Value    | Function        |
|-----------|----------|-----------------|
| 1         | 72 chars | problem heading |

**FORMAT record** **(FMTN)** **(A4, I4)**

| Field No. | Value              | Function  |
|-----------|--------------------|---|
| 1         | -23 to -3, 3 to 23 | Specify significant digits for output file in IPE (positive) or IPG (negative) format |

**LDFOLD record** **(LDFO)** **(no options)**

**QLOGMAX record** **(QLMX)** **(A4, I4)**

| Field No. | Value                | Function  |
|-----------|----------------------|---|
| 1         | 300 (default) to 350 | Max. exponent for PEXP() (PROTECT.f90), and for IMP sample scaling (RSCALE.f90) |

**DATA record** **(DATA)** **(A4, 4X, 8I4, I12, I4, I2)**

| Field No. | Value      | Function                                   |
|-----------|------------|--|
| 1         | 0 or blank | data set is embedded in the control stream |
|           | 1          | data set is in a separate file             |

|    |            |  |
|----|------------|--|
|    | -1         | re-use the data set from the previous problem.                 |
| 2  | 0 or blank | FORTTRAN unit not to be rewind                                 |
|    | 1          | FORTTRAN unit to be rewind                                     |
| 3  | 0          | data set to be read to FINISH record or end of file            |
|    | 1-9999     | no. of data records (low-order digits)                         |
| 4  | 1-PD       | no. of data items per data record                              |
| 5  | 0          | not data checkout  |
|    | 1          | data checkout only   |
| 6  | 0-9999     | no. of data records (high-order digits)                        |
|    |            | The no. of data records is Field 6 * 10000 + Field 3.          |
|    |            | When Field 6 is 0 or blank, this is simply Field 3             |
| 7  | 0          | Simulation NOREWIND from \$SIMULATION record                   |
|    | 1          | Simulation REWIND from \$SIMULATION record                     |
| 8  | 0          | NOSUPRESET   |
|    | 1          | SUPRESET (default)   |
| 9  | 0-INTBIG   | REPL   |
| 10 | 0-1        | PRED_IGNORE_DATA (1 if PRED_IGNORE_DATA feature is being used) |
| 11 | 0-1        | NOFDATACSV (1 to not produce FDATA.csv)                        |

**ITEM record** (ITEM) (A4, 4X, 18I4)

| Field No. | Value | Function  |
|-----------|-------|---|
| 1         | 0-PD  | index of ID data item                               |
| 2         | 1-PD  | index of DV data item                               |
| 3         | 0-PD  | index of MDV data item                              |
| 4         | 0-PD  | no. of data item indices in INDXS                   |
| 5         | 0     | no user-supplied labels.                            |
|           | 1     | user-supplied labels.                               |
| 6         | 0     | standard labels PRED,RES and WRES used.             |
|           | 1     | nonstandard labels used.                            |
| 7         | 0-PD  | index of L2 data item                               |
| 8         | 0-PD  | index of first data item specified in CONTR record  |
| 9         | 0-PD  | index of second data item specified in CONTR record |
| 10        | 0-PD  | index of third data item specified in CONTR record  |
| 11        | 0-50  | no. of user-supplied labels for tables, scatters    |
| 12        | 0-PD  | index of MRG_ data item                             |
| 13        | 0-PD  | index of RAW_ data item                             |
| 14        | 0-PD  | no. of items on OMIT record                         |
| 15        | 0-PD  | index of RPT_ data item                             |

**INDEX record** (INDEX) \* (A4, 4X, 18I4)

| Field No. | Value | Function             |
|-----------|-------|----------------------|
| 1         | 1-PD  | 1st element of INDXS |
| 2         | 1-PD  | 2nd element of INDXS |
|           | etc.  |                      |

**XVID record** (XVID) (A4, 4X, 18I4)

| Field No. | Value | Function |
|-----------|-------|----------|
| 1         | 0-PD  | XVID1    |
| 2         | 0-PD  | XVID2    |
| 3         | 0-PD  | XVID3    |
| 4         | 0-PD  | XVID4    |
| 5         | 0-PD  | XVID5    |

**MSDT record** (MSDT) (A4, 4X, 20 (1PE22.14E3, 1X)

| Field No. | Value    | Function   |
|-----------|----------|------------|
| 1         | -INF-INF | MISDAT(1)  |
| 2         | -INF-INF | MISDAT(2)  |
| 20        | -INF-INF | MISDAT(20) |

**LABEL record** (LABEL) \* (A4, X2, A74)

The LABEL record contains a comma-delimited list of labels, beginning at position 6, with an unlimited number of continuation records. Each label is right-adjusted in a field of SD characters. By default (i.e., with SD=20 in SIZES), there are 3 labels per line. The order is as follows:

| Field No. | Function                                    |
|-----------|---|
| 1:        | label of 1st data item                      |
| 2:        | label of 2nd data item                      |
|           | etc.  |
| m:        | label of last data item                     |
| m+1:      | label for PRED (if ITEM(6)=1)               |
| m+2:      | label for RES (if ITEM(6)=1)                |
| m+3:      | label for WRES (if ITEM(6)=1)               |
| m+p+1:    | label for 1st variable in NMPRD4†           |
| m+p+2:    | label for 2nd variable in NMPRD4†, etc.     |
| m+p+q:    | label for last displayed variable in NMPRD4 |

Note

- m=no. of data items per data rec.=DATA(4)
- p=3 if non-standard labels for PRED, RES, WRES (ITEM(6)=1)
- p=0 otherwise
- q=no. of user supplied labels for tables, scatters=ITEM(11)
- † Blank if this variable is not displayed

**Additional LABEL record** (LBW1) \* (A4, X2, A74)

The LBW1 record contains a comma-delimited list of labels for the additional diagnostic items, starting at position 6 in each line. The format is similar to that of the LABEL record, but leading spaces are omitted. The default labels are as follows:

IWRS, IPRD, IRS

NPRED, NRES, NWRES  
 NIWRES, NIPRED, NIRES  
 CPRED, CRES, CWRES  
 CIWRES, CIPRED, CIRES  
 PREDI, RESI, WRESI  
 IWRESI, IPREDI, IRESI  
 CPREDI, CRESI, CWRESI  
 CIWRESI, CIPREDI, CIRESI  
 EPRED, ERES, EWRES  
 EIWRES, EIPRED, EIRES  
 NPDE, ECWRES, NPD  
 OBJI

**LABEL record for THETA** (LTHT) \* (A4, X4, A72)  
**LABEL record for ETA** (LETA) \* (A4, X4, A72)  
**LABEL record for EPS** (LEPS) \* (A4, X4, A72)  
**LABEL record for RESIDUAL LABEL** (LRES) (A4, X1, A5)

Symbolic names for elements of THETA, ETA, and EPS (respectively), for NONMEM to use in the report file (*label substitution*). If label substitution is not requested, the LTHT, LETA, and LEPS records are optional and (if present) should have blanks starting in position 9.

Example: Suppose the NM-TRAN control file contains

\$ABBR REPLACE THETA (KA, K, CL) = THETA (1 TO 3)

\$ABBR REPLACE ETA (CL) = ETA (3), ETA (V) = ETA (5)

Then the generated LABEL records are:

LTHT 1=THETA (KA), 2=THETA (K), 3=THETA (CL)

LETA 3=ETA (CL), 5=ETA (V)

LEPS

**OMIT record** (OMIT) \* (A4, 4X, 18I4)

| Field No. | Value   | Function  |
|-----------|---------|---|
| 1         | 4 chars | no. of 1st data item omitted from template matching |
| 2         | 4 chars | no. of 2nd data item omitted from template matching |
|           | etc.    |   |

**FORMAT record** (FORM) (A4, 4X, A72/A80)

| Field No. | Value    | Function  |
|-----------|----------|---|
| 1         | 80 chars | format specification<br>(field begins on first continuation record) |

**FIND record** (FIND) (A4, 4X, 18I4)

| Field No. | Value | Function |
|-----------|-------|----------|
| 1         | 0     |          |
| 2         | 0     |          |

|   |   |  |
|---|---|--|
| 3 | 0 | No Model specification file (MSFI)               |
|   | 1 | A Model specification file (MSFI) is to be read. |
| 4 | 0 | estimate on file not to be rescaled.             |
|   | 1 | estimate on file to be rescaled.                 |
| 5 | 0 | No ONLYREAD option                               |
|   | 1 | ONLYREAD option                                  |
| 6 | 0 | MSFTEST option (default)                         |
|   | 1 | NOMSFTEST option                                 |
| 7 | 0 | MSFI not new (default)                           |
|   | 1 | MSFI new   |

**MSF Version Record (MSFV) (A4, X4, A72)**

Right after the FIND record for MSFI, if it exists, the MSFV (NM74) contains the MSF version, starting at position 9. This will be blank if not specified explicitly. Example:

MSFV 7.2.0

**INITIAL VALUES record for ETA (ETA)\* (A4, I4, (comma-delimited list))**  
**INITIAL VALUES record for PHI (PHI)\* (A4, I4, (comma-delimited list))**

With FILE specified:

| Line | Field No. | Value | Function  |
|------|-----------|-------|---|
| 1    | 1         | 0     | indicates file name is given.                     |
| 1    | 2         |       | File name starting in position 9 (through 88 max) |

**ADDITIONAL RECORD (UNLABELED) FOR ETA/PHI (A4, 4X, A)**

Record            Function  
                   DELIM

**ADDITIONAL RECORD (UNLABELED) FOR ETA/PHI (A4, 4X, 2I12)**

| Line | Field No. | Value         | Function  |
|------|-----------|---------------|-----------|
| 1    | 1         | 0-INF         | TBLN      |
|      | 2         | (-INF to INF) | ITERATION |

With no FILE specified:

| Line | Field No. | Value | Function  |
|------|-----------|-------|---|
| 1    | 1         | 1-LVR | number of initial values for etas or phis.<br>Listed starting at position 9 of each line. |

**Initial STRUCTURE record (STRC) (A4, 4X, 18I4)**

| Field No. | Value               | Function   |
|-----------|---------------------|--|
| 1         | 0-999               | length of THETA  |
| 2         | 0-999               | dimension of OMEGA   |
| 3         | 0-999               | dimension of SIGMA   |
| 4         | blank               |  |
| 5         | blank               |  |
| 6         | 0 or blank<br>1     | OMEGA constrained with a block set partition<br>OMEGA constrained to be diagonal |
| 7         | 0 or blank<br>1-999 | only if field 6 has value 1<br>number of block sets for OMEGA                    |

If the dimension of SIGMA is 0, the following fields may be ignored.

|    |                     |  |
|----|---------------------|--|
| 8  | 0 or blank<br>1     | SIGMA constrained with a block set partition<br>SIGMA constrained to be diagonal |
| 9  | 0 or blank<br>1-999 | SIGMA only if field 8 has value 1<br>number of block sets for SIGMA              |
| 10 | blank               |  |
| 11 | blank               |  |
| 12 | 0 or blank<br>1     | default THETA boundary test<br>No default THETA boundary test                    |
| 13 | 0 or blank<br>1     | default OMEGA boundary test<br>No default OMEGA boundary test                    |
| 14 | 0 or blank<br>1     | default SIGMA boundary test<br>No default SIGMA boundary test                    |

**STRUCTURE record for OMEGA (STRC) \* (A4, 4X, 18I4)**  
**STRUCTURE record for SIGMA (STRC) \* (A4, 4X, 18I4)**

| Field No. | Value | Function                                      |
|-----------|-------|---|
| 1         | 1-999 | size of 1st. block set                        |
| 2         | 1-999 | dimension of blocks in 1st. block set         |
| 3         | 1-999 | size of 2nd. block set                        |
| 4         | 1-999 | dimension of blocks in 2nd. block set<br>etc. |

**RECORDS FOR TTDF, OVARF, SVARF, OLKJDF, SLKJDF) (A4, 4X, I12)**

| Record | Function  |
|--------|---|
| OLDF   | Number of values for OLKJDF<br>Next lines have comm-delimited list of values for OLKJDF (3 to a line) |
| SVRF   | Number of values for SVARF<br>Next lines have comm-delimited list of values for SVARF (3 to a line)   |
| SLDF   | Number of values for SLKJDF<br>Next lines have comm-delimited list of values for SLKJDF (3 to a line) |
| SVRF   | Number of values for SVARF<br>Next lines have comm-delimited list of values for SVARF (3 to a line)   |
| TTDF   | Number of values for TTDF   |

Next lines have comm-delimited list of values for TTDF (3 to a line)

**THETA CONSTRAINT record** (THCN) (A4, 4X, 18I4)

| Field No. | Value      | Function   |
|-----------|------------|--|
| 1         | 0 or blank | THETA unconstrained                                      |
|           | 1          | THETA constrained  |
| 2         | 0 or blank | use default size of initial. est. search                 |
|           | 1-9999     | no. of points to be examined during initial est. search. |
| 3         | 0 or blank | ABORT if PRED sets error return code to 1 during search  |
|           | 1          | NOABORT - Ignore PRED error return code during search    |
|           | 2          | NOABORTFIRST - Same, even with first values.             |

**THETA record** (THTA)\* (A4, 4X, (comma-delimited list))

| Field No. | Value | Function  |
|-----------|-------|---|
| 1         |       | initial est. of $\theta_1$<br>(blank if NONMEM is to obtain the initial est.) |
| 2         |       | initial est. of $\theta_2$<br>(blank if NONMEM is to obtain the initial est.) |
|           | etc.  |   |

**THETA uninteresting for DESIGN** (THTU)\* (A4, 4X, (comma-delimited list))

| Field No. | Value | Function                             |
|-----------|-------|--------------------------------------|
| 1         |       | Uninteresting (1) or interesting (0) |
|           | etc.  |                                      |

**LOWER BOUND record** (LOWR)\* (A4, 4X, (comma-delimited list))

| Field No. | Value | Function                   |
|-----------|-------|----------------------------|
| 1         |       | lower bound for $\theta_1$ |
| 2         |       | lower bound for $\theta_2$ |
|           | etc.  |                            |

**UPPER BOUND record** (UPPR)\* (A4, 4X, (comma-delimited list))

| Field No. | Value | Function                   |
|-----------|-------|----------------------------|
| 1         |       | upper bound for $\theta_1$ |
| 2         |       | upper bound for $\theta_2$ |
|           | etc.  |                            |

**DIAGONAL record** (DIAG)\* (A4, 1X, A1, 1X, A1, (comma-delimited list))  
for OMEGA or SIGMA

| Field No. | Value | Function                                |
|-----------|-------|---|
| Pos. 1    | 0     | Diagonals Variance                      |
|           | 1     | Diagonals standard deviation (STANDARD) |

|        |       |  |
|--------|-------|--|
| Pos. 2 | blank | Not fixed.                                   |
|        | 1     | Fixed.                                       |
|        | 2     | NONMEM is to obtain the initial estimate(s). |
|        | 9     | Uninteresting (for DESIGN)                   |
| 1      |       | initial est. of (1,1) element of matrix      |
| 2      |       | initial est. of (2,2) element of matrix      |
|        | etc.  |  |

**BLOCK SET record** (BLST) \* (A4, 1X, A1, 1X, A1, (comma-delimited list))  
 for OMEGA or SIGMA

| Field No. | Value | Function   |
|-----------|-------|--|
| Pos. 1    | blank | Diagonals Variance, Off-diagonals covariance                                   |
|           | 1     | Diagonals standard deviation, Off-diagonals covariance (STANDARD)              |
|           | 2     | Diagonals Variance, Off-diagonals correlation (CORRELATION)                    |
|           | 3     | Diagonals standard deviation, Off-diagonals correlation (STANDARD CORRELATION) |
|           | 4     | Cholesky format (CHOLESKY)   |
| Pos. 2    | blank | Not fixed.   |
|           | 1     | Fixed.   |
|           | 2     | NONMEM is to obtain the initial estimate(s).                                   |
|           | 9     | Uninteresting (for DESIGN)   |
| 1         |       | initial est. of (1,1) element of matrix  |
| 2         |       | initial est. of (1,2) element of matrix  |
|           | etc.  |  |
|           |       | use symmetric enumeration  |

**DESIGN record** (OPTD) (A4, 4X, I2, I3, 2I2, 7I6, I12, I2, E23.16, I6, I3, 2I6, I3)

| Field No. | Value    | Function  |
|-----------|----------|---|
| 1         | 0-1      | IOPTD=0 do design/evaluation, IOPT=1, do not do design/evaluation |
| 2         | 0-1      | IONLYOPTD (not used)  |
| 3         | 0-6      | OPTDTYPE:   |
|           | 0        | FEDOROV   |
|           | 1        | NELDER  |
|           | 2        | STGR  |
|           | 3        | RS  |
|           | 4        | DISCRETE  |
|           | 5        | DISCRETE_SG   |
|           | 6        | DISCRETE_RS   |
| 4         | 0-10     | OFVTYPE   |
| 5         | 0-1      | OFVDIMSCALED  |
| 6         | 0-INTBIG | Column Number (data item) to STRAT                                |
| 7         | 0-INTBIG | Column number (data item) to STRATF                               |
| 8         | 0-INTBIG | Column number (data item) to STRATFMIN                            |
| 9         | 0-INTBIG | Column number (data item) to STRATFMAX                            |
| 10        | 0-INTBIG | Column number (data item) to NMIN                                 |
| 11        | 0-INTBIG | Column number (data item) to NMAX                                 |
| 12        | 0-1      | EOPTD   |

|    |          |  |
|----|----------|--|
| 13 | 0-INTBIG | SEED   |
| 14 | 0-1      | CLOCKSEED  |
| 15 | 0.0-INF  | GROUPSIZE  |
| 16 | 0-2      | MODE   |
| 17 | 0-1      | DATASIM  |
| 18 | 0-INTBIG | DOPTCOVCOLS sets to be estimated (each having DESEL, DESELSTRAT, DESELMIN, DESELMAX) |
| 19 | 0-3      | FIMDIAG(FIMTYPE)   |
| 20 | 0-1      | VARCROSS   |

**Additional Design Records (DESEL) ( ) (8X, I6, I6, I6, I6)**

| Field No. | Value    | Function                      |
|-----------|----------|-------------------------------|
| 1         | 0-INTBIG | DESEL column (data item)      |
| 2         | 0-INTBIG | DESELSRTAT column (data item) |
| 3         | 0-INTBIG | DESELMIN column (data item)   |
| 4         | 0-INTBIG | DESELMAX column (data item)   |

**SIMLUATION record (SIML) (A4, 4X, I2, I3, I2, I2, I13, 5I2, I13, 4 (I6) , 1X, A16)**

| Field No.  | Value      | Function   |
|--|------------|--|
| 1  | 0 or blank | Simulation Step implemented  |
|  | 1          | Simulation Step not implemented  |
| If the value is 1, the subsequent fields may be ignored. |            |  |
| 2  | 1-10       | no. of random sources (SORC records)                                       |
| 3  | 0          | eta (eps) changes with each record   |
|  | 1          | eta (eps) changes with new ind.rec. (L2 rec) (NEW)                         |
| 4  | 0-9999     | no. of subproblems   |
| 5  | 0          | compute objective function and other steps                                 |
|  | 1          | only the simulation step   |
| 6  | 0 or blank | no partial derivatives from PRED needed                                    |
|  | 1          | PRED should compute 1st. derivatives (REQUESTFIRST)                        |
|  | 2          | PRED should compute 2nd. derivatives (REQUESTSECOND)                       |
| 7  | 0 or blank | simulated observation is Y or F (PREDICTION)                               |
|  | 1          | simulated observation is DV (NOPREDICTION)                                 |
| 8  | 0 or blank | Use inital ests. (TRUE=INITIAL)  |
|  | 1          | with MSFI, use final ests. (TRUE=FINAL)                                    |
|  | 2          | use values in THET_P, OMEG_P, SIGM_P set by the PRIOR routine (TRUE=PRIOR) |
| 9  | 0          | REPLACE  |
|  | 1          | NOREPLACE  |
| 10   | -1         | BOOTSTRAP using as many subjects as are in the data set                    |
|  | 0          | No BOOTSTRAP (the default)   |
|  | 1-INTBIG   | BOOTSTRAP using the given number of subjects                               |
| 11   | 0-PD       | STRAT data column number   |
| 12   | 0-PD       | STRATF data column number  |
| 13   | 0-INF      | SOURCE_EPS (integer)   |
| 14   | 0-PD       | TTDF   |
| 15   | ALPHA      | RANMETHOD  |

**ADDITIONAL RECORDS FOR SIML (A4, 4X, I12, A)**

|        |   |
|--------|---|
| Record | Function  |
| SFIL   | PARAFPRINT (0-INTBIG),PARAFILE (line may accomodate up to 80 character file for total of 88 characters) |

**SOURCE record (SORC) (A4, 4X, 2A12, I4)**

| Field No. | Value          | Function  |
|-----------|----------------|---|
| 1         | -1-21474836447 | first seed  |
| 2         | 0-21474836447  | second seed   |
| 3         | 0 or blank     | random numbers are pseudo-normal (NORMAL)                 |
|           | 1              | random numbers are pseudo-uniform (UNIFORM)               |
|           | 2              | random numbers are from a nonpar. distrib (NONPARAMETRIC) |

**DEFAULT record (DFLT) (A4, 4X, I4)**

| Field No. | Value | Function                       |
|-----------|-------|--------------------------------|
| 1         | -1-1  | NOSUB option of DEFAULT record |

**INITIAL VALUES record for RCOV (RCOV) \* (A4, 4X, (A or I12))****INITIAL VALUES record for RCOVI (RCVI) \* (A4, 4X, (A or I12))**

| Line | Field No. | Value | Function |
|------|-----------|-------|----------|
| 1    | 1         | Alpha | Filename |

**ADDITIONAL RECORDS (UNLABELED) FOR RCOV/RCVI (A4, 4X, (I12 or A))**

|        |              |
|--------|--------------|
| Record | Function     |
|        | DELIM        |
|        | TBLN (0-INF) |

**CHAIN record (CHN)**

| Line | Format              | Field No. | Value           | Function                  |
|------|---------------------|-----------|-----------------|---------------------------|
| 1    | (A4,4I12,F12.5,I12) | 1         | 0-4             | CTYPE                     |
|      |                     | 2         | INTSMALL-INTBIG | SEED                      |
|      |                     | 3         | INTSMALL-INTBIG | ISAMPLE                   |
|      |                     | 4         | 0-INTBIG        | NSAMPLE                   |
|      |                     | 5         | 0.0001-1.0      | IACCEPT                   |
|      |                     | 6         | 0-INTBIG        | DF                        |
| 2    | (4X,4I12,A12)       | 1         | INTSMALL-INTBIG | ISAMPEND                  |
|      |                     | 2         | 0-3             | SELECT                    |
|      |                     | 3         | 0-3             | NOTITLE(1,3),NOLABEL(2,3) |
|      |                     | 4         | -1-INTBIG       | DFS                       |
|      |                     | 5         | ALPHA           | RANMETHOD                 |

**ADDITIONAL RECORDS FOR CHAIN (A4, 4X, A)**

|        |   |
|--------|---|
| Record | Function  |
| CFIL   | FILE (line may accomodate up to 80 character file for total of 88 characters)                               |
| CDLM   | FORMAT  |
| ORDR   | ORDER   |
| CHFL   | PARAFPRINT (I12:0-INTBIG),PARAFILE (line may accomodate up to 80 character file for total of 88 characters) |

**LEVEL record (OLEV) \* (A4, X4, A20, A52)**

|           |       |                   |
|-----------|-------|-------------------|
| Field No. | Value | Function          |
| 1         | ALPHA | Data item type    |
| 2         | ALPHA | level description |

**LEVEL rec. continuation rec. (OLEV) \* (A4, X4, X20, A52)**

|           |       |  |
|-----------|-------|--|
| Field No. | Value | Function   |
| 1         | blank |  |
| 2         | ALPHA | level description (continues level description from previous record) |

**ANNEAL record (ANNL) (A4, X4, A6, A6)**

|           |       |                      |
|-----------|-------|----------------------|
| Field No. | Value | Function             |
| 1         | 1-LVR | Eta Number           |
| 2         | 0-INF | Starting Omega value |

**ESTIMATION record (ESTM) (A4, 4X, 18I4)**

|           |            |                                 |
|-----------|------------|---------------------------------|
| Field No. | Value      | Function                        |
| 1         | 0 or blank | Estimation Step implemented     |
|           | 1          | Estimation Step not implemented |

If the value is 1, the subsequent fields may be ignored.

|           |            |   |
|-----------|------------|---|
| Field No. | Value      | Function  |
| 2         | 0-9999     | maximum no. of function. evaluations (low-order digits) |
|           | -1         | Reuse the value from the previous run (with MSFI)       |
| 3         | 1-8        | number of significant figs. required in final est.      |
| 4         | 0 or blank | no summarization of iterations                          |
|           | n>0        | every nth iteration summarized                          |
| 5         | 0 or blank | no second search (REPEAT)                               |

|    |            |  |
|----|------------|--|
|    | 1          | second search (REPEAT) implemented                           |
| 6  | 0 or blank | MSF not output   |
|    | 1          | MSF output   |
| 7  | 0 or blank | First order (FO) method                                      |
|    | 1          | Conditional method (METHOD=COND)                             |
| 8  | 0 or blank | No POSTHOC etas are to be estimated.                         |
|    | 1          | POSTHOC etas are to be estimated.                            |
| 9  | 0 or blank | Etas are 0 for comp. of intraind. error (NOINTERACTION)      |
|    | 1          | Nonzero etas for comp. of intraind. error INTERACTION        |
| 10 | 0 or blank | Do not use Laplacian method.                                 |
|    | 1          | Laplacian method is to be used.                              |
| 11 | 0 or blank | ABORT if PRED sets error return code to 1                    |
|    | 1          | NOABORT - Attempt theta-recovery when PRED error code 1.     |
|    | 2          | NOHABORT - Attempt recovery even at first iteration          |
| 12 | 0 or blank | Faster method of computation (NOSLOW)                        |
|    | 1          | Slower method of computation (SLOW)                          |
|    | 2          | Slower method of computation (SLOW=2); for Stieltjes         |
|    | 3          | Fast analytical derivative method of computation (FOCE only) |
| 13 | 0 or blank | avg. cond. est. of etas unconstrained (NOCENTER)             |
|    | 1          | avg. cond. est. of etas constrained close to 0. (CENTER)     |
| 14 | 0 or blank | First-order model not used (NOFO)                            |
|    | 1          | First-order model used with METHOD=1 CENTERING (FO)          |
| 15 | 0 or blank | Second eta-derivs. computed by PRED (NONNUMERICAL)           |
|    | 1          | Second eta-derivs. for Laplacian to be obtained numerically. |
| 16 | 0 or blank | Y or F (with user-supplied code) is a prediction.            |
|    | 1          | Y or F is a LIKELIHOOD.                                      |
|    | 2          | Y or F is a -2LOGLIKELIHOOD                                  |
| 17 | 0 or blank | Not the Hybrid method  |
|    | 1-99       | no. of etas fixed to zero by ZERO recs. (Hybrid method)      |
| 18 | 0 or blank | Not the Stieltjes method.                                    |
|    | 1          | Stieltjes method; no GRID option.                            |
|    | 2          | Stieltjes method; GRID was specified.                        |

**ESTIMATION rec. continuation rec. ( ) (A4, 4X, 18I4)**

| Field No. | Value       | Function  |
|-----------|-------------|---|
| 1         | 0 or blank  | Required if estimation step is omitted, otherwise:      |
|           | 0 or blank  | The REPEAT2 option is not coded; same as NOREPEAT2      |
|           | 1           | REPEAT2 (with Stieltjes)                                |
| 2         | 0 or blank  | No ETABARCHECK.   |
|           | 1           | ETABARCHECK option is coded.                            |
| 3         | 0 or blank. | Sum contrib. to obj. func. in data set order.           |
|           | 1           | Sort contrib. to obj. func. prior to sum (SORT)         |
| 4         | 0-9999      | maximum no. of function evaluations (high-order digits) |
|           |             | The no. of func. evals. is Field 4 * 10000 + low-order  |
|           |             | When Field 4 is 0 or blank, this is simply low-order    |
| 5         | -1,0,100    | SIGL default  |
|           | 1-15        | SIGL value  |
| 6         | -1,0,100    | SIGLO default   |

1-15 SIGLO value

| <b>BAYES ESTIMATION record</b> |                               | <b>(BEST)</b>               |                 |                           |            |            |            |
|--------------------------------|-------------------------------|-----------------------------|-----------------|---------------------------|------------|------------|------------|
| Line                           | Format                        | Field No.                   | Value           | Function                  |            |            |            |
| 1                              | (A4,4I12,F12.5,I12)           | 1                           | -1-16           | BAYES METHOD              |            |            |            |
|                                |                               |                             | <=0             | FO/FOCE/Laplace           |            |            |            |
|                                |                               |                             | 10              | DIRECT                    |            |            |            |
|                                |                               |                             | 11              | BAYES                     |            |            |            |
|                                |                               |                             | 12              | ITS                       |            |            |            |
|                                |                               |                             | 13              | SAEM                      |            |            |            |
|                                |                               |                             | 14              | IMP                       |            |            |            |
|                                |                               |                             | 15              | IMPMAP                    |            |            |            |
|                                |                               |                             | 16              | CHAIN                     |            |            |            |
|                                |                               |                             | 2               | -1-INTBIG                 | PSAMPLE_M1 |            |            |
|                                |                               |                             | 3               | -1-INTBIG                 | PSAMPLE_M2 |            |            |
|                                |                               |                             | 4               | 0-INTBIG                  | PSAMPLE_M3 |            |            |
|                                |                               |                             | 5               | 0.0001-1.0                | PACCEPT    |            |            |
|                                |                               |                             | 6               | -1-INTBIG                 | OSAMPLE_M1 |            |            |
|                                |                               |                             | 2               | (X4,2I12,F12.5,3I12)      | 1          | -1-INTBIG  | OSAMPLE_M2 |
|                                |                               |                             |                 |                           | 2          | 0-INTBIG   | OSAMPLE_M3 |
| 3                              | 0.0001-1.0                    | OACCEPT                     |                 |                           |            |            |            |
| 4                              | 1-INTBIG                      | ISAMPLE/ICHAINS (non-CHAIN) |                 |                           |            |            |            |
|                                | INTSMALL-INTBIG               | ISAMPLE (CHAIN)             |                 |                           |            |            |            |
| 5                              | 0-INTBIG                      | ISAMPLE_M1                  |                 |                           |            |            |            |
| 6                              | 0-INTBIG                      | ISAMPLE_M2                  |                 |                           |            |            |            |
| 3                              | (X4,I12,F12.5,2I12,E12.5,I12) | 1                           |                 |                           | 0-INTBIG   | ISAMPLE_M3 |            |
| 2                              | 0.0-1.0                       | IACCEPT                     |                 |                           |            |            |            |
| 3                              | 0-INTBIG                      | NSAMPLE/NITER               |                 |                           |            |            |            |
| 4                              | 0-INTBIG                      | NBURN                       |                 |                           |            |            |            |
| 5                              | 0-INF                         | DF (Real)                   |                 |                           |            |            |            |
| 6                              | 0-3                           | EONLY                       |                 |                           |            |            |            |
| 4                              | (X4,I11,I4,4I11,F12.5)        | 1                           | INTSMALL-INTBIG | SEED                      |            |            |            |
|                                |                               | 2                           | 0-1             | NOPRIOR                   |            |            |            |
|                                |                               | 3                           | 0-3             | NOTITLE(1,3),NOLABEL(2,3) |            |            |            |
|                                |                               | 4                           | 0-4             | CTYPE                     |            |            |            |
|                                |                               | 5                           | 1-INTBIG        | CITER/CNSAMP              |            |            |            |
|                                |                               | 6                           | 0.0000001,1     | CALPHA                    |            |            |            |
| 5                              | (X4,4I12,2E12.5)              | 1                           | 0-INTBIG        | CINTERVAL                 |            |            |            |
|                                |                               | 2                           | 0-INTBIG        | MAPITER                   |            |            |            |
|                                |                               | 3                           | -1-INTBIG       | MAPINTER                  |            |            |            |
|                                |                               | 4                           | 0-INTBIG        | ISAMPLE_M1A               |            |            |            |
|                                |                               | 5                           | 0-INF           | ISCALE_MIN                |            |            |            |
|                                |                               | 6                           | 0-INF           | ISCALE_MAX                |            |            |            |
| 6                              | (X4,5I12,A12)                 | 1                           | 0-INTBIG        | CONSTRAIN                 |            |            |            |
|                                |                               | 2                           | 0-15            | ATOL                      |            |            |            |
|                                |                               | 3                           | 0-2             | FNLETA                    |            |            |            |
|                                |                               | 4                           | 0-2             | OPTMAP                    |            |            |            |

Appendix 4 - NONMEM Control Records (FCON)"

|    |                              |   |                 |                                  |
|----|------------------------------|---|-----------------|----------------------------------|
|    |                              | 5 | 0-3             | ETADER                           |
|    |                              | 6 | ALPHA           | RANMETHOD                        |
| 7  | (X4,5I12,E12.5)              | 1 | 0-INTBIG        | MCETA                            |
|    |                              | 2 | 0-2             | NONINFETA                        |
|    |                              | 3 | INTSMALL-INTBIG | ISAMPEND (CHAIN)                 |
|    |                              | 4 | 0-1             | ETASTYPE                         |
|    |                              | 5 | 0-1             | AUTO                             |
|    |                              | 6 | 0.0-1000        | STDOBJ                           |
| 8  | (X4,I12,2E12.5,I12,I12,I6)   | 1 | 0-3             | NUMDER                           |
|    |                              | 2 | 0-INF           | PSCALE_MIN                       |
|    |                              | 3 | 0-INF           | PSCALE_MAX                       |
|    |                              | 4 | -1-INTBIG       | DFS                              |
|    |                              | 5 | 0-3             | SELECT                           |
|    |                              | 6 | 0-1             | NOCOV                            |
| 9  | (4X,I6,I6,I6,E12.5,E15.8,I6) | 1 | 0-1             | DERCONT                          |
|    |                              | 2 | -1-1            | NOSUB                            |
|    |                              | 3 | 0-2             | MAPCOV                           |
|    |                              | 4 | 0.0-1.0         | IACCEPTL                         |
|    |                              | 5 | -10.0-INF       | GRDQ                             |
|    |                              | 6 | 0-INTBIG        | ISAMPLE_M1B                      |
| 10 | (4X,4(I12),2(E15.8))         | 1 | -1-1            | MASSRESET                        |
|    |                              | 2 | 0-1             | BAYES_METHOD (0: BAYES, 1: NUTS) |
|    |                              | 3 | -1-INTBIG       | MADAPT                           |
|    |                              | 4 | 0-INTBIG        | IMADAPT (NOT USED)               |
|    |                              | 5 | 0.0001-INF      | KAPPA                            |
|    |                              | 6 | 0.0001-INF      | IKAPPA                           |
| 11 | (4X,6(E15.8))                | 1 | 0.0-INF         | NUTS_GAMMA                       |
|    |                              | 2 | 0.0-INF         | IGAMMA (NOT USED)                |
|    |                              | 3 | 0.0-1.0         | NUTS_DELTA                       |
|    |                              | 4 | 0.0-1.0         | IDELTA (NOT USED)                |
|    |                              | 5 | 0.0-INF         | OLKJDF                           |
|    |                              | 6 | 0.0-INF         | SLKJDF                           |
| 12 | (4X,4(E15.8))                | 1 | 0.0-INF         | TTDF                             |
|    |                              | 2 | -INF-INF        | OVARF                            |
|    |                              | 3 | -INF-INF        | SVARF                            |
|    |                              | 4 | -INF-INF        | TPU                              |
| 13 | (4X,A12,A12,I4,I4,I4,I4,I4)  | 1 | ALPHA           | NUTS_TYPE (NOT USED)             |
|    |                              | 2 | ALPHA           | NUTS_MASS                        |
|    |                              | 3 | 0-1             | NUTS_TRANSFORM                   |
|    |                              | 4 | 0-1             | INUTS_TRANSFORM (NOT USED)       |
|    |                              | 5 | 0-2             | NUTS_EPARAM                      |
|    |                              | 6 | 0-10            | WISHTYPE (NOT USED)              |
|    |                              | 7 | 0-1             | NUTS_OPARAM                      |
|    |                              | 8 | 0-1             | NUTS_SPARAM                      |
| 14 | (4X,I12,I12,I12,3(E15.8))    | 1 | 0-INTBIG        | NUTS_STEPITER                    |
|    |                              | 2 | 0-INTBIG        | NUTS_STEPINTER                   |
|    |                              | 3 | 0-1             | NUTS_TEST                        |
|    |                              | 4 | 0-INF           | NUTS_INIT                        |
|    |                              | 5 | -99-INF         | NUTS_BASE                        |

|    |                                 |            |                 |                                  |
|----|---------------------------------|------------|-----------------|----------------------------------|
| 15 | (4X,I12,I12,I12,E15.8,E15.8,I4) | 6          | 0-INF           | NUTS_TERM                        |
|    |                                 | 1          | 0-1             | KNUTHSUMOFF                      |
|    |                                 | 2          | 0-1             | LEVWT                            |
|    |                                 | 3          | -1-INTBIG       | NUTS_MAXDEPTH                    |
|    |                                 | 4          | 0.0-INF         | NUTS_CHOLBND (NOT USED)          |
|    |                                 | 5          | 0.0-INF         | NUTS_REG                         |
| 16 | (A4,6(I12),6(I4))               | 6          | 0-INTBIG        | SADDLE_RESET                     |
|    |                                 | 1          | 0-1             | SADDLE_HESS                      |
|    |                                 | 2          | 0-INTBIG        | THIN                             |
|    |                                 | 3          | 0-1             | ETASAMPLES                       |
|    |                                 | 4          | 0-1             | PHITYPE                          |
|    |                                 | 5          | 0-4             | LEVSWITCH                        |
|    |                                 | 6          | INTSMALL-INTBIG | TBLN (FOR CHAIN METHOD)          |
|    |                                 | 7          | 0-1             | BAYES_PHI_STORE                  |
|    |                                 | 8          | 0-1             | BIONLY                           |
|    |                                 | 9          | 0-1             | BOOTDATA                         |
|    |                                 | 10         | 0-1             | NOLEVCENTER (LEVCENTER=1=NOLEVC) |
|    |                                 | 11         | 0-1             | LEVOBJTYPE                       |
| 12 | 0-1                             | EVALSHRINK |                 |                                  |

**ADDITIONAL RECORDS FOR ESTIMATION (A4, 4X, A)**

| Record | Function  |
|--------|---|
| BFIL   | FILE (name be up to 256 characters)                                 |
| BDLM   | FORMAT/DELIM  |
| BMUM   | MUM (may go beyond 80 characters)                                   |
| BGRD   | GRD (may go beyond 80 characters)                                   |
| ORDR   | ORDER   |
| PFIL   | PARAFPRINT (I12:0-INTBIG),PARAFILE (name be up to 256 characters)   |
| FFIL   | FPARAFPRINT (I12:0-INTBIG),FPARAFILE (name be up to 256 characters) |

**ZERO record (ZERO) \* (A4, 4X, 18I4)**

| Field No. | Value | Function                             |
|-----------|-------|--------------------------------------|
| 1         | 0     | conditional estimate for eta(1)      |
|           | 1     | eta(1) is fixed to 0 (HYBRID method) |
| 2         | 0     | conditional estimate for eta(2)      |
|           | 1     | eta(2) is fixed to 0 (HYBRID method) |
|           | etc.  |                                      |

**GRID record (GRID) (A4, 4X, 9A8)**

| Field No. | Value | Function                           |
|-----------|-------|------------------------------------|
| 1         | nr    | as specified in GRID=(nr,ns,r0,r1) |
| 2         | ns    | as specified in GRID=(nr,ns,r0,r1) |
| 3         | r0    | as specified in GRID=(nr,ns,r0,r1) |
| 4         | r1    | as specified in GRID=(nr,ns,r0,r1) |

**NONPARAMETRIC record (NONP) (A4, 4X, 5I4, I12, I12, I6, I6, I2, I12)**

| Field No. | Value      | Function                                       |
|-----------|------------|--|
| 1         | 0 or blank | Nonparametric step implemented conditionally   |
|           | 1          | Nonparametric step implemented unconditionally |
| 2         | 0 or blank | use nonparametric estimate from input MSF      |
|           | 1          | recompute nonparametric estimate               |
| 3         | 0 or blank | obtain marginal cumulatives                    |
|           | 1          | compute conditional nonpar. etas (CNPE ETAS)   |
| 4         | 0 or blank | no model specification file is output          |
|           | 1          | a model specification file is output           |
| 5         | 0,1        | 1=BOOTSTRAP                                    |
| 6         | 0-3        | EXPAND(1,3),NPSUPPE(2,4)                       |
| 7         | 0-INTBIG   | NPSUPP(E) value                                |
| 8         | 1-INTBIG   | STRAT data column number                       |
| 9         | 1-INTBIG   | STRATF data column number                      |
| 10        | 0-1        | NPESTIM  |
| 11        | 0-INTBIG   | NPMAXITER                                      |

**ADDITIONAL RECORD FOR NONPARAMETRIC (A4, 4X, I12, A)**

| Record | Function   |
|--------|--|
| NFIL   | PARAFPRINT (0-INTBIG), PARAFILE (name be up to 256 characters) |

**COVARIANCE record (COVR) (A4, 4X, 18I4)**

| Field No. | Value      | Function  |
|-----------|------------|---|
| 1         | 0 or blank | Covariance Step conditionally implemented             |
|           | 1          | Covariance Step unconditionally implemented           |
|           | 2          | Covariance Step not implemented                       |
| 2         | 0 or blank | covariance matrix set to (R inverse) S (R inverse)    |
|           | 1          | covariance matrix set to R inverse                    |
|           | 2          | covariance matrix set to S inverse                    |
| 3         | 0 or blank | neither R nor S printed.                              |
|           | 1          | R matrix printed                                      |
|           | 2          | S matrix printed                                      |
|           | 3          | both R and S printed                                  |
| 4         | 0 or blank | eigenvalues not printed                               |
|           | 1          | eigenvalues printed.                                  |
| 5         | 0 or blank | default computation.                                  |
|           | 1          | Special computation with a recursive PRED subroutine. |
| 6         | 0 or blank | Print Covariance Step arrays in normal format.        |
|           | 1          | Print Covariance Step arrays in compressed format.    |
| 7         | 1          |   |
| 8         | 0 or blank |   |
| 9         | 0 or blank | Normal method of computation                          |
|           | 1          | Slower method of computation (SLOW)                   |

3 Fast analytical derivative method of computation (FOCE only)

**Additional COVARIANCE record (COVT) (A4, 4X, 6I4, I12, I6, I6, I12, I2, 4 (I6), I2, I2, I2, A10)**

| Field No. | Value    | Function                   |
|-----------|----------|----------------------------|
| 1         | -1,0,100 | SIGL default               |
|           | 1-15     | SIGL value                 |
| 2         | 1-15     | TOL                        |
| 3         | -1,0,100 | SIGLO default              |
|           | 1-15     | SIGLO value                |
| 4         | 1-15     | ATOL                       |
| 5         | 0-1      | I=NOFCOV                   |
| 6         | 0-1      | I=COVRESUME                |
| 7         | 0-INTBIG | SIRSAMPLE value            |
| 8         | 0-INTBIG | SIRNITER value             |
| 9         | 0-1      | SIRCENTER value            |
| 10        | 0-INTBIG | SIRSEED                    |
| 11        | 0-1      | CLOCKSEED                  |
| 12        | 0-INTBIG | PRECOND value              |
| 13        | 0-INTBIG | PFCOND value               |
| 14        | 0-2      | PRETYPE value              |
| 15        | 0-1      | FPOSDEF value              |
| 16        | 0-1      | 1:THBND=0, 0:THBND=1       |
| 17        | 0-1      | 1:SIRTHBND=0, 0:SIRTHBND=1 |
| 18        | 0-3      | POSDEF value               |
| 19        | ALPHA    | PRECONDS value             |

**Second line of COVT Record (COVT) (8X, I8, I4, I4, 6 (E12.5), A16)**

| Field No. | Value    | Function          |
|-----------|----------|-------------------|
| 1         | 0-INTBIG | SIRPRINT value    |
| 2         | 0-1      | CHOLROFF value    |
| 3         | 0-1      | KNUTHSUMOFF value |
| 4         | 0.0-INF  | SIRDF             |
| 5         | 0.0-1.0  | IACCEPT           |
| 6         | 0.0-1.0  | IACCEPTL          |
| 7         | 0.0-1.0  | SIR_CAPCORR       |
| 8         | 0.0-INF  | SIRMAXWT          |
| 9         | 0.0-INF  | SIRMINWT          |
| 10        | ALPHA    | RANMETHOD         |

**ADDITIONAL RECORDS FOR COVARIANCE (8X, I12, A)**

| Record | Function   |
|--------|--|
|        | SIRSAMPLES: COMMA SEPARATED LIST OF INTEGERS (A)<br>FORMAT,FILE (A30,A)            |
| CPAR   | PARAFPRINT (0-INTBIG), PARAFILE (name be up to 256 characters) (A4,4X,I12,A)       |
| SPAR   | SIRPARAFPRINT (0-INTBIG), SIRPARAFILE (name be up to 256 characters) (A4,4X,I12,A) |

**Initial TABLE record (TABL) (A4, 4X, 18I4)**

| Field No. | Value      | Function                               |
|-----------|------------|--|
| 1         | 0 or blank | Table Step conditionally implemented   |
|           | 1          | Table Step unconditionally implemented |
|           | 2          | Table Step not implemented             |

If the value is 2, the next field may be ignored, and there should not appear any individual TABLE records.

|   |      |                  |
|---|------|------------------|
| 2 | 1-10 | number of tables |
|---|------|------------------|

**ADDITIONAL RECORDS FOR TABLE (A4, 4X, I12, A)**

| Record | Function  |
|--------|---|
| PPAR   | PARAFPRINT (0-INTBIG),PARAFILE (name be up to 256 characters) |

**Individual TABLE record (TABL) (A4, 1X, 3A1, I4, 9 (I6, I2)**

| Field No. | Value  | Function   |
|-----------|--------|--|
| Pos. 1    | blank  | no option record.  |
|           | 1      | an option record follows.<br>(only if at least one item on the option rec. is non-blank) |
| 1         | 0-PDT  | number of selected data item types   |
| 2         | 1-9999 | index of 1st selected data item type   |
| 3         | 0-8    | sort code for data items of 1st selected type  |
|           | -1     | Exclude-by item marked by -1   |
| 4         | 1-9999 | index of 2nd selected data item type   |
| 5         | 0-8    | sort code for data items of 2nd selected type  |
|           | etc.   |  |

**Individual TABLE rec. contin. rec. ( )\*(A4, 1X, 3A1, I4, 9 (I6, I2)**

(as needed)

| Field No. | Value | Function                               |
|-----------|-------|--|
| 1         | 1-999 | index of 9th. selected data item type  |
| 2         | 0     |  |
| 3         | 1-999 | index of 10th. selected data item type |
| 4         | 0     |  |
|           | etc.  |  |

**Individual TABLE record option rec. ( ) (A4, 4X, 5I4, I12, I12, A12, I2, I2, I2, I2, I2, I2, 1X, A**

| Field No. | Value | Function  |
|-----------|-------|---|
| 1         | blank | Every data record appears in the table.                               |
|           | 1     | Only the first data rec. from each ind. rec. (FIRSTONLY)              |
|           | 2     | Only the last data rec. from each ind. rec. (LASTONLY)                |
|           | 3     | Only the first and last data rec. from each ind. rec. (FIRSTLASTONLY) |

|    |                 |  |
|----|-----------------|--|
| 2  | 1               | With TABLE file, no printed table (NOPRINT)  |
|    | 2               | With TABLE file, printed table appears in the NONMEM output.                         |
| 3  | 0               | default  |
|    | 1               | ONEHEADER  |
|    | 4               | NOTITLE  |
|    | 8               | NOLABEL  |
|    | 5               | ONEHEADER NOTITLE  |
|    | 9               | ONEHEADER NOLABEL  |
|    | 14              | NOHEADER (same as NOTITLE NOLABEL)   |
| 4  | blank           | The TABLE file is opened and is positioned at the start.                             |
|    | 1               | The TABLE file is positioned at the end (FORWARD)                                    |
| 5  | blank           | DV, PRED, RES, WRES appear automatically   |
|    | 1               | DV, PRED, RES, WRES do not appear unless listed (NOAPPEND)                           |
| 6  | INTSMALL-INTBIG | SEED   |
| 7  | 3-INTBIG        | ESAMPLE  |
| 8  | ALPHA           | RANMETHOD  |
| 9  | 0-1             | WRESCHOL   |
| 10 | -1-1            | NOSUB  |
| 11 | 0               | No SE to PRED item   |
|    | 1               | SE to PRED item  |
| 12 | 0-1             | NPDTYPE  |
| 13 | 0-1             | INTERPTYPE   |
| 14 | ALPHA           | FORMAT (May be up to 20 characters, so total line length may be up to 89 characters) |

**Additional TABLE records (A4, 4X, A)**

| Record | Function  |
|--------|---|
| FRML   | LFORMAT (record may be longer than 80 characters)               |
| FRMR   | RFORMAT (record may be longer than 80 characters)               |
| FETA   | FIXEDETAS number list (record may be longer than 80 characters) |

**Initial SCATTERPLOT record (SCAT) (A4, 4X, 18I4)**

| Field No. | Value      | Function                                     |
|-----------|------------|--|
| 1         | 0 or blank | Scatterplot Step conditionally implemented   |
|           | 1          | Scatterplot Step unconditionally implemented |
|           | 2          | Scatterplot Step not implemented             |

If the value is 2, the next field may be ignored, and there should not appear any individual SCATTERPLOT records.

|   |      |                    |
|---|------|--------------------|
| 2 | 1-20 | number of families |
|---|------|--------------------|

**Individual SCATTERPLOT record (SCAT) (A4, 4X, 9I8/8X, 9I8)**

| Field No. | Value | Function |
|-----------|-------|----------|
|-----------|-------|----------|

|   |            |  |
|---|------------|--|
| 1 | 1-23       | index of data items plotted on abscissa axis |
| 2 | 1-23       | index of data items plotted on ordinate axis |
| 3 | 0 or blank | a single scatterplot                         |
|   | 1          | a one-way partitioned scatterplot            |
|   | 2          | a two-way partitioned scatterplot            |

If the value of field 3 is 0 or blank, the next two fields should be ignored.

|   |      |                        |
|---|------|------------------------|
| 4 | 1-23 | index of 1st separator |
|---|------|------------------------|

If the value of field 3 is 1, the next field should be ignored.

|    |            |  |
|----|------------|--|
| 5  | 1-23       | index of 2nd separator                                   |
| 6  | 0 or blank | no unit slope line appears                               |
|    | 1          | unit slope line appears                                  |
| 7  | 0-99999999 | no. of the first data rec. for the scatter (FROM)        |
| 8  | 0-99999999 | no. of the last data rec. for the scatter (TO)           |
| 9  | 0 or blank | a line through zero on the ordinate axis if appropriate. |
|    | 1          | a line through zero on the ordinate axis. (ORD0)         |
|    | -1         | no line through zero on the ordinate axis.               |
| 10 | 0 or blank | a line through zero on the abscissa axis if appropriate. |
|    | 1          | a line through zero on the abscissa axis. (ABS0)         |
|    | -1         | no line through zero on the abscissa axis.               |
| 11 | 0 or blank | Every data record appears in the scatter.                |
|    | 1          | Only the first data rec. from each ind. rec. (FIRSTONLY) |
| 12 | 0 or blank | Every data record appears in the scatter                 |
|    | 1          | Only data records with MDV=0 (OBSONLY).                  |
| 12 | -1-1       | NOSUB  |

## INDEX

155  
# tag label output 155  
\$ERROR record 84, 86  
\$WARNING record 158  
& continuation character 158  
,STOP\_TIME reserved variable, ITASK\_ 157  
-2LL option of \$ESTIMATION record 153, 161  
 $\hat{\omega}$  41  
 $\hat{\sigma}$  41  
 $\hat{\theta}$  41  
 $\hat{y}$  41  
1.0E+06 141, 154  
100,1000 CMT data item 156  
100,1000 PCMT data item 156  
100,101 MDV data item 154  
2000 54

### - A -

$\alpha$ -level test 48  
A(i) reserved variable 157  
Abbreviated Code 158  
abbreviated code 5, 10  
\$ABBREVIATED record 149  
ABORT 150  
ABS 73  
ABS0 option of \$TABLE record 148  
Absorption lag parameter ALAG 136  
absorption rate KA 10  
absorption, first-order 8  
ACOS 73  
additional dose 74  
additional PK parameter 55, 72  
additive error model 27, 37, 41, 85, 90  
ADDL data item 136  
ADDL\_ACTUAL,ADDL\_TIME,ADDL\_TIMEDIFF  
reserved variable 157  
ADVAN 4, 71  
ADVAN1 13  
ADVAN2 9  
ADVAN57 134  
ADVAN68,13-14 134  
ADVAN9\_15 134  
advance 35, 71, 74  
AES subroutine 133  
\$AESINIT record 135  
\$AES record 135  
ALAGn 136  
All Options for \$COVARIANCE 169  
All Options for \$ESTIMATION 161  
AMT data item 56, 58  
ANALYSIS TYPE 141  
\$ANNEAL record 155  
ANRD reserved variable 157  
ANSI FORTRAN 4  
APPEND option of \$TABLE record 148  
ASIN 73  
assay 29  
assay, bias of 25  
ATAN 73  
ATOL option of \$COVARIANCE record 135, 169  
ATOL option of \$ESTIMATION record 135, 161

AUTO option of \$ESTIMATION record 161  
auto-correlation 143  
A\_0,A\_OFLG reserved variable 157  
A\_U,A\_UFLG reserved variable 157

### - B -

BASE\_STEP,EST\_STEP,COV\_STEP,TA-  
BLE\_STEP,SIML\_STEP,INE\_STEP,NONP\_STEP  
reserved variable 157  
basic PK parameter 55, 72  
BAYES\_PHI\_STORE option of \$ESTIMATION record  
161  
bias of assay 25  
bias of estimate 43  
\$BIND record 137  
bioavailability 59-62, 72, 79  
BIONLY option of \$ESTIMATION record 161  
BLANKOK option of \$DATA record 158  
BLOCK option of \$OMEGA record 140  
BLOCK option of \$SIGMA record 140  
BLOCK SAME(m) option of \$OMEGA record 142  
BLOCK SAME(m) option of \$SIGMA record 142  
bolus dose, instantaneous 59  
bolus dose, multiple 60  
bolus dose, zero-order 135-136  
BOOTDATA option of \$ESTIMATION record 161  
bootstrap 147, 154  
BOOTSTRAP option of \$NONPARAMETRIC record  
154  
BOOTSTRAP option of \$SIMULATION record 154  
BY option of \$TABLE record 148

### - C -

calendar date 66  
CALL data item 58, 74, 84, 138  
call to ERROR subroutine 58, 137  
call to PK subroutine 58, 137  
CALLFL reserved variable 135, 137  
calling protocol phrase 137-138  
CALPHA option of \$ESTIMATION record 161  
case insensitivity 158  
CCONTR subroutine 150  
CCV error model 27, 37, 41, 85, 90  
CENTERING option of \$ESTIMATION record 149,  
161  
central compartment 9, 71  
CHAIN option of \$CHAIN record 154  
CHAIN option of \$ESTIMATION record 154  
Changes to NONMEM Outputs 155  
CHECKOUT option of \$DATA record 148  
checkpoint-restart 143  
chi-square 48  
CHOLESKY option of \$OMEGA record 141  
CHOLESKY option of \$SIGMA record 141  
CHOLROFF option of \$COVARIANCE record 169  
CI 44, 130  
CINTERVAL option of \$ESTIMATION record 161  
CIPRED,CIRES,CIWRES reserved label of \$TA-  
BLE,\$SCATTER record 156

CIPREDI,CIRESI,CIWRESI reserved label of \$TABLE,\$SCATTER record 156  
 CITER/CNSAMP option of \$ESTIMATION record 161  
 CL, clearance 13, 24  
 clearance CL 13, 24  
 clock time 56, 65, 69  
 CLOCKSEED option of \$ESTIMATION record 161  
 CLOCKSEED option of \$SIMULATION record 147  
 CLOCKSEED option of \$TABLE record 148  
 CMT data item 57, 71  
 CNTID reserved variable 160  
 Code, Abbreviated 158  
 coefficient of variation 27  
 colon ":" in II data item 69  
 colon ":" in TIME data item 66  
 COM,COMACT reserved variable 158  
 command, operating system 5  
 COMPACT 157  
 compartment 9  
 compartment number 57, 71, 93  
 compartment, central 9, 71  
 compartment, default dose 9, 71-72  
 compartment, depot 9, 60, 72  
 compartment, dose 57, 59  
 compartment, equilibrium 134  
 compartment, output 25, 57, 60, 64, 72  
 compartment, prediction 57  
 compartment, zero-out a 72  
 COMPRESS option of \$COVARIANCE record 145, 169  
 COMRES,COMSAV option of \$ABBREVIATED record 158  
 concentration 23  
 concentration, plasma 8, 25, 30, 35  
 concentration, urine 25, 30, 35, 38, 64  
 concomitant data 55  
 conditional estimate 148  
 conditional estimation method 149  
 conditional estimation method, first-order 149  
 CONDITIONAL option of \$COVARIANCE record 144, 169  
 CONDITIONAL option of \$ESTIMATION record 161  
 CONDITIONAL option of \$SCATTERPLOT record 92  
 CONDITIONAL option of \$TABLE record 92  
 conditional statement 77  
 confidence interval 44-46, 130  
 console control characters 155  
 constant coefficient of variation (CCV) error model 27, 37, 41, 85, 90  
 constant infusion 62  
 CONSTRAIN option of \$ESTIMATION record 155, 161  
 CONSTRAINT subroutine 155  
 constraint, parameter 10, 87, 115  
 continuation line 158  
 CONTR subroutine 150  
 control language, NONMEM 5  
 \$CONTR record 151  
 correlation 36  
 correlation matrix of estimate 92, 103  
 Correlation matrix OMEGA,SIGMA output 155  
 correlation of parameter estimate 45  
 correlation of residual vs Y 118  
 CORRELATION option of \$OMEGA record 141  
 CORRELATION option of \$SIGMA record 141  
 CORRL2 reserved variable 143  
 COS 73  
 covariance 36, 89, 140  
 covariance matrix 36, 39, 103-104  
 covariance matrix of estimate 92  
 Covariance matrix OMEGA,SIGMA output 155  
 covariance matrix, full 140

COVARIANCE option of \$OMEGA record 141  
 COVARIANCE option of \$SIGMA record 141  
 covariance step 91-92, 103, 172  
 \$COVARIANCE record 10, 87, 91-92, 97, 103  
 CPRED,CRES,CWRES reserved label of \$TABLE,\$SCATTER record 156  
 CPREDI,CRESI,CWRESI reserved label of \$TABLE,\$SCATTER record 156  
 CRIT subroutine 150  
 csvalign utility 161  
 CTLO CTUP reserved variable 154  
 CTYPE option of \$ESTIMATION record 161

## - D -

DAT1,DAT2,DAT3 data item 67  
 data checkout 97, 148  
 data file name 52  
 data item 8, 29, 50  
 data item label 54  
 data item, dropping 55, 67, 70  
 data item, null 50  
 data item, steady-state 58  
 data items, maximum number of 51, 55  
 Data Preprocessor 158  
 Data Preprocessor 65  
 data record 50  
 data set 50  
 data set, deleting records from 50-51  
 data set, sequence of 50, 52  
 data set, size of 50  
 data, effect 133, 151  
 data, individual 8, 23, 69  
 data, population 55, 89  
 data, single-response population 23  
 \$DATA record 52, 65, 97, 145  
 DATE data item 66  
 date, calendar 66  
 day-time translation 65, 69  
 days 54, 67  
 ddexpand utility 161  
 DECLARE option of \$ABBREVIATED record 159  
 default dose compartment 9, 71-72  
 degrees of freedom 48, 142  
 deleting records from data set 50-51  
 DELIM option of \$TABLE record 147  
 dependent variable 8-9, 23  
 depot compartment 9, 60, 72  
 DERCONT option of \$ESTIMATION record 161  
 DERIV1 option of \$ABBREVIATED record 158  
 DERIV2 option of \$ABBREVIATED record 158  
 DES subroutine 133  
 \$DES record 135  
 DF option of \$ESTIMATION record 161  
 DFS option of \$ESTIMATION record 161  
 DIAG 159  
 diagonal elements of OMEGA 37  
 DIAGONAL option of \$OMEGA record 140  
 DIAGONAL option of \$SIGMA record 140  
 diagonal variance-covariance matrix 89, 140  
 dispersion factor 142  
 distribution of parameter estimate 44  
 do directive 161  
 doexpand utility 161  
 dose amount 58  
 dose compartment 57, 59  
 dose compartment, default 9, 71-72  
 dose event record 56, 58

dose, additional 74  
 dose, implied 60  
 dose, infusion 59  
 dose, instantaneous bolus 59  
 dose, lagged 74  
 dose, multiple 12  
 dose, multiple bolus 60  
 dose, steady-state 60  
 dose, zero-order bolus 135-136  
 dose-related data item 58  
 doses, multiple steady-state 63  
 DOSTIM reserved variable 136  
 DOWHILE(DATA) 139  
 DROP option of \$INPUT record 55, 67, 70, 97  
 dropping data item 55, 67, 70  
 drug level 61  
 duration of infusion 59  
 duration, modeled 136  
 DV data item 8, 55-56  
 dynamic memory allocation 155

**- E -**

EBV 155  
 EBVshrink output 155  
 ECWRES reserved label of \$TABLE,\$SCATTER record 156  
 effect data 133, 151  
 eigenvalue 134, 144  
 EIPRED,EIRES,EIWRES reserved label of \$TABLE,\$SCATTER record 156  
 elimination rate K 10, 24  
 ELS, extended least squares 42  
 EM 7  
 EM method 153  
 Emax model 133  
 Empirical Steady State 157  
 end of infusion 59  
 enddo directive 161  
 EONLY option of \$ESTIMATION record 161  
 Epectation-Maximation 7  
 EPRED,ERES,EWRES reserved label of \$TABLE,\$SCATTER record 156  
 $\epsilon$  32  
 EPS variable 84, 89  
 EPSshrink output 155  
 equilibrium compartment 134  
 ERR variable 25, 84, 89  
 error message, operating system 53  
 error message, PREDPP 175  
 error message, TRANSLATOR 175  
 error model 25, 84, 90  
 error model, additive 27, 37, 41, 85, 90  
 error model, CCV 27, 37, 41, 85, 90  
 error model, constant coefficient of variation (CCV) 27, 37, 41, 85, 90  
 error model, exponential 28, 37, 85  
 error model, log-normal 28, 37, 85  
 error model, power function 29, 42, 85  
 error model, proportional 27, 37  
 error model, statistical 23  
 error recovery option 150  
 error return code 150  
 ERROR subroutine 4-5, 55, 72, 133  
 ERROR subroutine, call to 58, 137  
 error variance 15, 26  
 error, estimation 43  
 error, interindividual 36

error, intraindividual 25, 36  
 error, MSE mean squared 43  
 \$ERROR record 5, 14, 55, 151  
 ESAMPLE option of \$TABLE record 148  
 estimate of ETA, individual 148  
 estimate of theta, initial 87  
 estimate of variance, initial 90, 144, 151  
 estimate, bias of 43  
 estimate, conditional 148  
 estimate, initial 10, 134  
 estimate, perturbed initial 88  
 estimation error 43  
 estimation method, first-order 148  
 estimation method, first-order conditional with interaction 149  
 estimation method, laplacian 149  
 estimation step 91, 102, 144, 154, 172  
 \$ESTIMATION record 10, 87, 91, 97, 154  
 $\eta$  25  
 ETA variable 14, 25, 84, 89  
 ETA(k:n) reserved label of \$TABLE record 156  
 ETA, individual estimate of 148  
 ETABAR output 155  
 ETABARCHECK option of \$ESTIMATION record 155, 161  
 ETADER option of \$ESTIMATION record 161  
 ETAn reserved label of \$TABLE record 156  
 ETAS option of \$NONPARAMETRIC record 153  
 ETAS(...) 156  
 ETASAMPLES option of \$ESTIMATION record 161  
 ETAshtink output 155  
 ETASTYP option of \$ESTIMATION record 155  
 ETASTYPE option of \$ESTIMATION record 161  
 ETASXI reserved variable 155  
 \$ETAS record 154  
 event record 56  
 event record, dose 56, 58  
 event record, observation 56, 84  
 event record, other 56-57, 74  
 event record, reset 57  
 event record, reset-dose 57  
 EVID data item 56, 65  
 EVID data item, generated 69  
 exception, floating-point 150  
 EXCLUDE\_BY 156  
 EXIT statement 150  
 EXP 73  
 EXPAND option of \$NONPARAMETRIC record 153  
 expectation feature 153  
 experiment, replication of 43  
 exponential error model 28, 37, 85  
 extended least squares ELS 42  
 external table file 147

**- F -**

F distribution 48  
 FAST option of \$COVARIANCE record 169  
 FAST option of \$ESTIMATION record 161  
 Features, NONMEM 153  
 FILE option of \$COVARIANCE record 169  
 FILE option of \$ESTIMATION record 161  
 FILE option of \$TABLE record 147  
 filename option of \$DATA record 52  
 final parameter estimate 91  
 finedata utility 160  
 FINISH record 52  
 first-order absorption 8

first-order conditional estimation method 149  
 first-order conditional with interaction estimation method 149  
 first-order estimation method 148  
 FIRSTLASTONLY option of \$TABLE record 148  
 FIRSTONLY option of \$TABLE record 148  
 fixed effects 23, 55  
 fixed effects parameter 23, 33  
 FIXED option of \$OMEGA record 89, 101, 141  
 FIXED option of \$SIGMA record 89, 101, 141  
 FIXED option of \$THETA record 88, 101  
 FIXEDETAS 156  
 flip-flop 176  
 floating-point exception 150  
 FNLETA option of \$ESTIMATION record 161  
 FO method 91  
 FOCE method 91  
 FORMAT option of \$COVARIANCE record 169  
 FORMAT option of \$TABLE record 147  
 format specification 50, 52, 65, 69-70  
 FORMAT/DELIM option of \$ESTIMATION record 161  
 \$FORMAT record 155  
 FORTRAN 6, 50  
 FORTRAN OPEN statement 52  
 FORTRAN READ statement 53  
 FORWARD option of \$TABLE record 147  
 FPARAFILE option of \$ESTIMATION record 155, 161  
 FPOSDEF option of \$COVARIANCE record 169  
 fraction, output 72, 79  
 FROM option of \$SCATTERPLOT record 105  
 FSUBS 6  
 FULL 157, 159  
 full covariance matrix 140  
 full model 47, 119  
 FUNCA reserved variable 159  
 function of parameters 43  
 F\_FLAG reserved variable 153

### - G -

GAMLN 73  
 general mixed effects model 39  
 generated EVID data item 69  
 generated ID data item 69  
 generated MDV data item 69  
 generated subroutine 6  
 GG array 99  
 Gn1 reserved label of \$TABLE record 156  
 goodness of fit 11, 47, 119  
 gradient 101, 172  
 GRD option of \$ESTIMATION record 161  
 GRDQ option of \$ESTIMATION record 161  
 GRID option of \$ESTIMATION record 153, 161

### - H -

half-life 43, 46  
 hierarchical file 51  
 HINIT\_, HMIN\_, HMAX\_ reserved variable 157  
 HMAX\_ reserved variable, HINIT\_, HMIN\_, 157  
 HMIN\_, HMAX\_ reserved variable, HINIT\_, 157  
 Hn1 reserved label of \$TABLE record 156  
 hours 54, 67  
 HYBRID option of \$ESTIMATION record 153, 161  
 hyperbolic model 34  
 hypotheses, joint 47

hypothesis test 19, 46, 106  
 hypothesis, null 46

### - I -

IACCEPT option of \$COVARIANCE record 169  
 IACCEPT option of \$ESTIMATION record 161  
 IACCEPTL option of \$COVARIANCE record 169  
 IACCEPTL option of \$ESTIMATION record 161  
 ICALL reserved variable 139, 159  
 ID data item 51, 55, 142, 173  
 ID data item, generated 69  
 identification number, patient 51  
 IFIRSTEM reserved variable 160  
 IGNORE option of \$DATA record 53  
 IGNORE option of \$INPUT record 97  
 II data item 56, 59, 69, 136  
 II data item, colon ":" in 69  
 II option of \$DATA record 158  
 II/24 54  
 IIDX reserved variable 160  
 IKAPPA option of \$ESTIMATION record 161  
 ill-formed data file 158  
 implied dose 60  
 INCLUDE record 94  
 index plot 108, 117  
 indicator variable 29, 35, 77, 81, 85-86  
 individual data 8, 23, 69  
 individual estimate of ETA 148  
 individual parameter estimate 148  
 individual record 55  
 INDR1, INDR2 reserved variable 160  
 infinite infusion 62  
 INFINITY 87, 97  
 INFN subroutine 133, 139  
 \$INFN record 139  
 informative form, informative record name 142  
 infusion dose 59  
 infusion, constant 62  
 infusion, duration of 59  
 infusion, end of 59  
 infusion, infinite 62  
 infusion, multiple 61  
 infusion, rate of 58  
 Initial condition 135  
 initial estimate 10, 134  
 initial estimate of theta 87  
 initial estimate of variance 90, 144, 151  
 initial estimate step 88, 91, 144  
 initial estimate, perturbed 88  
 initial parameter estimate 144  
 initialization/finalization 139  
 \$INPUT record 54, 59, 97  
 installation of NONMEM 2, 4  
 instantaneous bolus dose 59  
 INT 73  
 INTER file 143  
 INTERACTION method 91  
 INTERACTION option of \$ESTIMATION record 149, 161  
 interactive control 155  
 interdose interval 59, 69, 136  
 interindividual error 36  
 interindividual variability 36  
 INTERPTYPE 156  
 interrupt 150  
 intraindividual error 25, 36  
 intraindividual variability 25, 36

inverse covariance matrix of estimate 92  
 IPRD,IRS,CIWRS reserved label of \$TABLE,\$SCATTER record 156  
 IPROB reserved variable 145  
 IREP reserved variable 146  
 ISAMPEND option of \$ESTIMATION record 161  
 ISAMPLE option of \$ESTIMATION record 161  
 ISAMPLE\_M1 option of \$ESTIMATION record 161  
 ISAMPLE\_M1A option of \$ESTIMATION record 161  
 ISAMPLE\_M1B option of \$ESTIMATION record 161  
 ISAMPLE\_M2 option of \$ESTIMATION record 161  
 ISAMPLE\_M3 option of \$ESTIMATION record 161  
 ISCALE\_MAX option of \$ESTIMATION record 161  
 ISCALE\_MIN option of \$ESTIMATION record 161  
 ISFINL reserved variable 157  
 ISSMOD reserved variable 134, 157  
 ITASK\_ \_STOP\_TIME reserved variable 157  
 iteration 101, 172  
 ITS method 153  
 I\_SS 134-135, 157

### - J -

joint hypotheses 47

### - K -

K, elimination rate 10, 24  
 KA, absorption rate 10  
 KAPPA option of \$ESTIMATION record 161  
 KNUTHSUMOFF option of \$COVARIANCE record 169  
 KNUTHSUMOFF option of \$ESTIMATION record 161

### - L -

L1 data item 142  
 L2 data item 142, 151, 173  
 label substitution 159  
 labels, reserved 54  
 lagged dose 74  
 LAPLACE option of \$ESTIMATION record 161  
 laplacian estimation method 149  
 LAPLACIAN option of \$ESTIMATION record 149  
 LAST20 option of \$DATA record 54  
 LASTONLY option of \$TABLE record 148  
 lblr utility 161  
 SLDFOLD record 155  
 least squares criterion 41  
 least squares ELS, extended 42  
 least squares OLS, ordinary 41  
 least squares WLS, weighted 41  
 LEVCENTER option of \$ESTIMATION record 161  
 SLEVEL record 154  
 LEVOBJTYPE option of \$ESTIMATION record 161  
 LEVWT option of \$ESTIMATION record 161  
 LFORMAT option of \$TABLE record 147  
 LIKE option of \$ESTIMATION record 153, 161  
 likelihood ratio test 48, 132  
 linear model 33  
 linear system 63  
 link editing 5  
 LIREC reserved variable 160  
 load module 5

log likelihood 48, 120  
 LOG,LOG10 73  
 log-normal error model 28, 37, 85  
 Loops 159  
 lower case 158  
 lower triangular elements of OMEGA 37  
 lpcc utility 161  
 LRECL option of \$DATA record 53

### - M -

MADAPT option of \$ESTIMATION record 161  
 MAPCOV option of \$ESTIMATION record 161  
 MAPINTER option of \$ESTIMATION record 161  
 MAPITER option of \$ESTIMATION record 161  
 MARGINALS option of \$NONPARAMETRIC record 153  
 mass balance 72  
 MASSRESET option of \$ESTIMATION record 161  
 MATRIX option of \$COVARIANCE record 144, 169  
 MAX 73  
 MAXEVAL option of \$ESTIMATION record 92, 161, 172  
 maximum number of data items 51, 55  
 maximum number of observation records 56  
 MCETA option of \$ESTIMATION record 161  
 MDV data item 55, 140  
 MDV data item 100,101 154  
 MDV data item, generated 69  
 MDV1,2,3 reserved variable 154  
 MDVRES reserved variable 156  
 mean squared error, MSE 43  
 METHOD option of \$ESTIMATION record 91, 149, 161  
 Michaelis-Menten model 34, 71  
 microconstant 72  
 MIN 73  
 minimal model 113  
 minimum value of objective function 10, 48, 91, 102  
 MISDAT option of \$DATA record 158  
 MIX subroutine 133, 149-150  
 mixed effects model 26, 31  
 mixed effects model, general 39  
 MIXEST reserved variable 150  
 MIXNUM reserved variable 150  
 MIXP reserved variable 150  
 MIXPT reserved variable 150  
 mixture model 149-150  
 \$MIX record 149  
 MNEXT reserved variable 137  
 MNOW reserved variable 137  
 MOD 73  
 model building 106  
 model misspecification 103  
 model specification file 92, 143-144  
 MODEL subroutine 133  
 model, Emax 133  
 model, full 47, 119  
 model, general mixed effects 39  
 model, linear 33  
 model, Michaelis-Menten 34, 71  
 model, minimal 113  
 model, mixed effects 26, 31  
 model, mixture 149-150  
 model, multiplicative 34, 80  
 model, one-compartment 8, 13, 23  
 model, parameter 32  
 model, pharmacodynamic 133, 140, 151

model, pharmacokinetic 2, 71, 134  
 model, population 32  
 model, random effects 127  
 model, reduced 47, 119  
 model, statistical 126-127  
 model, structural 23, 36, 98, 113  
 model, user-defined 134  
 modeled duration 136  
 modeled rate 135  
 \$MODEL record 134  
 monitoring of search 91  
 monte-carlo 148  
 monte-carlo method 153, 156  
 MPAST reserved variable 137  
 MRG\_ data item 153  
 MSE mean squared error 43  
 MSEC,MFIRST reserved variable 160  
 \$MSFI record 92, 143  
 MSFO option of \$ESTIMATION record 143, 161, 172  
 MSFO option of \$NONPARAMETRIC record 153  
 MTDIFF reserved variable 137  
 MTIME 136  
 MU modeling 154  
 multiple \$ESTIMATION records 154  
 multiple bolus dose 60  
 multiple dose 12  
 multiple infusion 61  
 multiple steady-state doses 63  
 multiplicative model 34, 80  
 multivariate observation 142  
 MUM option of \$ESTIMATION record 161  
 MU\_reserved variables 154  
 MXSTEP reserved variable 135

- N -

N output 155  
 NBURN option of \$ESTIMATION record 161  
 neff utility 161  
 neffi utility 161  
 negative objective function 42  
 nested if 74  
 nested parentheses 74  
 NEW option of \$MSFI record 143  
 NEW option of \$SIMULATION record 147  
 NEWIND reserved variable 160  
 NINDR reserved variable 160  
 NIPRED,NIRES,NIWRES reserved label of \$TABLE,\$SCATTER record 156  
 NIREC,NDREC reserved variable 160  
 NITER/NSAMPLE option of \$ESTIMATION record 161  
 NM-TRAN defined 2  
 nmfe 5  
 nmfe75 5  
 nmfe75 utility 160  
 nmtemplate utility 160  
 NM\_STEP reserved variable 157  
 NOABORT 150  
 NOABORT option of \$ESTIMATION record 161  
 NOABORTFIRST 150  
 NOABORTFIRST option of \$THETA record 150  
 NOAPPEND option of \$TABLE record 148  
 NOCHECKMU option of \$ABBREVIATED record 154  
 NOCOV option of \$ESTIMATION record 145, 161  
 NOFASTDER option of \$ABBREVIATED record 158  
 NOFCOV option of \$COVARIANCE record 145, 169  
 NOFDATACS option of \$DATA record 158

NOFORWARD option of \$TABLE record 147  
 NOHABORT 150  
 NOHABORT option of \$ESTIMATION record 161  
 NOHABORT option of \$THETA record 150  
 NOHEADER option of \$TABLE record 147  
 NOLABEL option of \$ESTIMATION record 161  
 NOLABEL option of \$TABLE record 147  
 NOMSFTEST option of \$MSFI record 143  
 Non continuous 153  
 NONINFETA option of \$ESTIMATION record 161  
 NONMEM 1  
 NONMEM control language 5  
 NONMEM Features 153  
 NONMEM Outputs, Changes to 155  
 nonmem\_general\_reserved 7  
 nonmem\_reserved 159  
 nonmem\_reserved\_general 154, 160  
 \$NONPARAMETRIC record 153  
 NOOMEGABOUNDTEST option of \$ESTIMATION record 161  
 NOPREDICTION option of \$SIMULATION record 147  
 NOPRINT option of \$TABLE record 147  
 NOPRIOR option of \$ESTIMATION record 151, 161  
 NOREPLACE option of \$MSFI record 143  
 NOREPLACE option of \$SIMULATION record 147, 154  
 NOREWIND 52  
 NORMAL option of \$SIMULATION record 147  
 NOSIGMABOUNDTEST option of \$ESTIMATION record 161  
 NOSLOW option of \$COVARIANCE record 169  
 NOSUB option of \$ESTIMATION record 161  
 NOSUB option\_of \$ESTIMATION record 159  
 NOSUB option\_of \$SCATTER record 159  
 NOSUB option\_of \$TABLE record 159  
 NOSUPRESET option of \$SIMULATION record 147  
 NOTHETABOUNDTEST option of \$ESTIMATION record 161  
 NOTITLE option of \$ESTIMATION record 161  
 NOTITLE option of \$TABLE record 147  
 NPDE,NPD reserved label of \$TABLE,\$SCATTER record 156  
 NPDTYPE 156  
 NPESTIM option of \$SIMULATION record 154  
 NPMAXITER option of \$SIMULATION record 154  
 NPOPETAS option of \$MSFI record 143  
 NPRED,NRES,NWRES reserved label of \$TABLE,\$SCATTER record 156  
 NPROB reserved variable 145  
 NPSUPP,NPSUPPE option of \$NONPARAMETRIC record 153  
 NRD reserved variable 157  
 NREP reserved variable 146  
 NSIG option of \$ESTIMATION record 161  
 NSPOP reserved variable 150  
 null data item 50  
 null hypothesis 46  
 NULL option of \$DATA record 53  
 null value 46  
 null value of parameter 129-130  
 number of significant digits 98  
 NUMBERPOINTS option of \$THETA record 144  
 NUMBER option of \$ESTIMATION record 155, 161  
 NUMERICAL option of \$ESTIMATION record 161  
 NUTS\_BASE option of \$ESTIMATION record 161  
 NUTS\_DELTA option of \$ESTIMATION record 161  
 NUTS\_EPARAM option of \$ESTIMATION record 161  
 NUTS\_GAMMA option of \$ESTIMATION record 161  
 NUTS\_INIT option of \$ESTIMATION record 161  
 NUTS\_MASS option of \$ESTIMATION record 161  
 NUTS\_MAXDEPTH option of \$ESTIMATION record 161

NUTS\_OPARAM option of \$ESTIMATION record 161  
NUTS\_REG option of \$ESTIMATION record 161  
NUTS\_SPARAM option of \$ESTIMATION record 161  
NUTS\_STEPINTER option of \$ESTIMATION record 161  
NUTS\_STEPITER option of \$ESTIMATION record 161  
NUTS\_TERM option of \$ESTIMATION record 161  
NUTS\_TEST option of \$ESTIMATION record 161  
NUTS\_TRANSFORM option of \$ESTIMATION record 161  
NWPRI subroutine 142, 151

- O -

OACCEPT option of \$ESTIMATION record 161  
objective function 42, 91, 120  
objective function, minimum value of 10, 48, 91, 102  
OBJI reserved label of \$TABLE record 156  
observation event record 56, 84  
observation records, maximum number of 56  
observed value 4, 55-56, 90  
OBSONLY option of \$TABLE record 148  
Odd type data 153  
OLKJDF option of \$ESTIMATION record 161  
OLNTWOPI option of \$ESTIMATION record 161  
OLS, ordinary least squares 41  
OMEGA 10, 26, 36  
Ω 36, 88  
OMEGA reserved variable 160  
OMEGA, diagonal elements of 37  
OMEGA, lower triangular elements of 37  
OMEGABOUNDTTEST option of \$ESTIMATION record 161  
\$OMEGAPD record 142  
\$OMEGAP record 142  
\$OMEGA record 10, 14, 88-89, 97, 140  
OMITTED option of \$COVARIANCE record 169  
OMITTED option of \$ESTIMATION record 161  
\$OMIT record 153  
on/off status 57, 65, 78  
one-compartment model 8, 13, 23  
ONEHEADER option of \$TABLE record 147  
ONEHEADERALL option of \$TABLE record 147  
ONEHEADERPERFILE option of \$TABLE record 147  
ONLYREAD option of \$MSFI record 143  
ONLYSIMULATION option of \$SIMULATION record 146  
operating system command 5  
operating system error message 53  
OPTMAP option of \$ESTIMATION record 161  
ORD0 option of \$SCATTERPLOT record 93, 148  
ORDER option of \$ESTIMATION record 155, 161  
ordinary least squares OLS 41  
OSAMPLE\_M1 option of \$ESTIMATION record 161  
OSAMPLE\_M2 option of \$ESTIMATION record 161  
OSAMPLE\_M3 option of \$ESTIMATION record 161  
other event record 56-57, 74  
OTHER option of \$SUBROUTINE record 151  
outlier 109  
output compartment 25, 57, 60, 64, 72  
output fraction 72, 79  
output-type 57, 65, 72, 138  
Outputs, Changes to NONMEM 155  
OVARF option of \$ESTIMATION record 161

- P -

P reserved variable 150  
P VAL output 155  
p-value 132  
PACCEPT option of \$ESTIMATION record 161  
PARAFILE option of \$COVARIANCE record 155, 169  
PARAFILE option of \$ESTIMATION record 155, 161  
PARAFILE option of \$SIMULATION record 147, 154-155  
PARAFILE option of \$TABLE record 155  
PARAFPRINT option of \$COVARIANCE record 169  
PARAFPRINT option of \$ESTIMATION record 161  
parallel computing 155  
parameter ALAG, Absorption lag 136  
parameter constraint 10, 87, 115  
parameter estimate 41  
parameter estimate, correlation of 45  
parameter estimate, distribution of 44  
parameter estimate, final 91  
parameter estimate, individual 148  
parameter estimate, initial 144  
parameter estimate, precision of 43, 92, 129, 131  
parameter model 32  
parameter, additional PK 55, 72  
parameter, basic PK 55, 72  
parameter, fixed effects 23, 33  
parameter, null value of 129-130  
parameter, PK 10, 71  
parameter, random effects 26, 127  
parameter, scale 10, 24, 71, 77  
parameter, time varying 35  
parameterization 24, 43, 46, 72, 76  
parameters, function of 43  
PARAMETRIC option of \$SIMULATION record 147  
partial derivative 6  
partitioned scatterplot 93, 105  
PASS subroutine 139  
PASSRC reserved variable 139  
patient identification number 51  
PCMT data item 57, 71  
PD in \$SIZES 155  
PD in \$SIZES 51  
PD in SIZES 51  
PDT in \$SIZES 147, 155  
perturbed initial estimate 88  
PFCOND option of \$COVARIANCE record 169  
pharmacodynamic model 133, 140, 151  
pharmacokinetic model 2, 71, 134  
phenobarbital example 12, 24, 89-90, 106, 133, 152  
PHI 73  
φ 23  
\$PHIS record 154  
PHITYPE option of \$ESTIMATION record 161  
PK parameter 10, 71  
PK parameter, additional 55, 72  
PK parameter, basic 55, 72  
PK subroutine 4-5, 55, 72, 133  
PK subroutine, call to 58, 137  
\$PK record 5, 10, 55, 71  
plasma concentration 8, 25, 30, 35  
plot, index 108, 117  
population data 55, 89  
population data, single-response 23  
population model 32  
positive definite 141  
POSTHOC option of \$ESTIMATION record 148, 161  
power function error model 29, 42, 85  
PRDERR 150  
PRDFL reserved variable 154  
precision of parameter estimate 43, 92, 129, 131  
PRECOND option of \$COVARIANCE record 169  
PRECONDS option of \$COVARIANCE record 169

PRED error recovery option 150  
 PRED error return code 150  
 PRED subroutine 1, 71, 98, 133, 139  
 PRED subroutine, recursive 35, 144  
 PRED, predicted value 11, 92  
 PREDI.RESI,WRESI reserved label of \$TABLE,\$SCATTER record 156  
 predicted value 4, 56  
 predicted value PRED 11, 92  
 prediction compartment 57  
 PREDICTION option of \$ESTIMATION record 161  
 PREDICTION option of \$SIMULATION record 147  
 PREDPP 1, 71, 156  
 PREDPP error message 175  
 PREDPP library 4  
 PRED\_RES\_WRESI reserved variable 160  
 PRED\_IGNORE\_DATA,PRED\_IGNORE\_DATA\_FLAG 97, 153  
 \$PRED record 6, 98  
 Preprocessor, Data 158  
 PRETYPE option of \$COVARIANCE record 169  
 PRINT option of \$COVARIANCE record 144, 169  
 PRINT option of \$ESTIMATION record 92, 161, 173  
 PRINT option of \$TABLE record 147  
 prior 142  
 PRIOR subroutine 151  
 PRIORC option of \$ESTIMATION record 161  
 priorget utility 161  
 \$PRIOR record 151  
 \$PROBLEM record 8, 97, 145  
 proportional error model 27, 37  
 PR\_CT reserved variable 154  
 PR\_Y reserved variable 154  
 PSAMPLE\_M1 option of \$ESTIMATION record 161  
 PSAMPLE\_M2 option of \$ESTIMATION record 161  
 PSAMPLE\_M3 option of \$ESTIMATION record 161  
 PSCALE\_MAX option of \$ESTIMATION record 161  
 PSCALE\_MIN option of \$ESTIMATION record 161

## - R -

$R^{-1}$  covariance matrix 144  
 random effects 26, 32, 80  
 random effects model 127  
 random effects parameter 26, 127  
 RANDOM subroutine 146, 153  
 random variable 6, 73, 81, 84  
 random variable 81  
 RANMETHOD option of \$COVARIANCE record 169  
 RANMETHOD option of \$ESTIMATION record 161  
 RANMETHOD option of \$SIMULATION record 147  
 RANMETHOD option of \$TABLE record 148  
 RATE data item 56, 58  
 rate of infusion 58  
 rate, modeled 135  
 raw data average feature 153  
 raw output file 155  
 RAW\_data item 153  
 RECOMPUTE option of \$NONPARAMETRIC record 153  
 record length 53  
 RECORDS option of \$DATA record 52, 158  
 recovery option, error 150  
 recursive PRED subroutine 35, 144  
 reduced model 47, 119  
 relative time 56, 66  
 RELATIVEINF output 155  
 REPEAT option of \$ESTIMATION record 144, 161

REPEAT1 option of \$ESTIMATION record 153, 161  
 REPEAT2 option of \$ESTIMATION record 153, 161  
 repeated values xn 142  
 Repetition feature 154  
 REPL,REPL\_NOFDATACSV 153  
 REPLACE option of \$ABBREVIATED record 159  
 REPLACE option of \$SIMULATION record 147, 154  
 replication of experiment 43  
 REQUESTFIRST option of \$SIMULATION record 147  
 REQUESTSECOND option of \$SIMULATION record 147  
 RES, residual 16, 92, 116  
 RESCALE option of \$MSFI record 144  
 reserved labels 54  
 reserved variable 7  
 reset event record 57  
 reset-dose event record 57  
 residual error 25, 32  
 residual RES 16, 92, 116  
 residual vs Y, correlation of 118  
 RESUME option of \$COVARIANCE record 145, 169  
 return code, error 150  
 REWIND 52  
 REWIND option of \$SIMULATION record 146  
 RFORMAT option of \$TABLE record 147  
 root.agh output file 156  
 root.fgh output file 156  
 root.xxx output file 155  
 RPTI,RPTO,RPTON reserved variable 154  
 RPT\_data item 154

## - S -

$S^{-1}$  covariance matrix 144  
 S1IT,S2IT reserved variable 145  
 S1NIT,S2NIT reserved variable 145  
 S1NUM,S2NUM reserved variable 145  
 SADDLE\_HESS option of \$ESTIMATION record 161  
 SADDLE\_RESET option of \$ESTIMATION record 161  
 SAME option of \$SIGMA record 141  
 saturation model 34, 80  
 scale parameter 10, 24, 71, 77  
 SCALE(d) option of \$OMEGA record 142  
 SCALE(d) option of \$SIGMA record 142  
 scatterplot 11, 51, 57, 59, 92-93  
 scatterplot step 104  
 scatterplot, partitioned 93, 105  
 \$SCATTERPLOT record 87, 92-93, 97  
 SD in SIZES 54  
 SD option of \$OMEGA record 141  
 SD option of \$SIGMA record 141  
 SE (standard error) 44  
 SE output 155  
 SEED option of \$ESTIMATION record 161  
 SEED option of \$TABLE record 148  
 SEOMEG reserved variable 160  
 sequence of data set 50, 52  
 SESIGM reserved variable 160  
 SETHET reserved variable 160  
 SETHETR reserved variable 160  
 SIGDIGITS option of \$ESTIMATION record 91  
 SIGL option of \$COVARIANCE record 145, 169  
 SIGL option of \$ESTIMATION record 161  
 SIGLO option of \$COVARIANCE record 145, 169  
 SIGLO option of \$ESTIMATION record 161  
 SIGMA 15, 32  
 $\Sigma$  32, 88  
 SIGMA reserved variable 160

SIGMABOUNDTEST option of \$ESTIMATION record 161  
 \$SIGMAPD record 142  
 \$SIGMAP record 142  
 \$SIGMA record 14, 87-89, 97, 140  
 significant digits, number of 98  
 SIMEPS subroutine 146  
 SIMETA subroutine 146  
 simulation step 100, 145  
 \$SIMULATION record 145  
 SIN 73  
 single-response population data 23  
 SIRCENTER option of \$COVARIANCE record 169  
 SIRDF option of \$COVARIANCE record 169  
 SIRNITER option of \$COVARIANCE record 169  
 SIRPRINT option of \$COVARIANCE record 169  
 SIRSAMPLE option of \$COVARIANCE record 169  
 SIRTHBND option of \$COVARIANCE record 169  
 size of data set 50  
 \$SIZES record 155  
 SKIP\_ reserved variable 145  
 SLKJDF option of \$ESTIMATION record 161  
 SLOW option of \$COVARIANCE record 145, 169  
 SLOW option of \$ESTIMATION record 161  
 SORT option of \$ESTIMATION record 153, 161  
 SOURCE\_EPS option of \$SIMULATION record 147  
 SPECIAL option of \$COVARIANCE record 144, 169  
 SQRT 73  
 SS data item 56, 58  
 standard deviation 27, 90, 117  
 standard error 8, 10, 44-45, 103, 130, 144  
 standard error of estimate 92  
 standard error vs. standard deviation 44  
 STANDARD option of \$OMEGA record 141  
 STANDARD option of \$SIGMA record 141  
 statistical error model 23  
 statistical model 126-127  
 STDOBJ option of \$ESTIMATION record 161  
 steady-state 136  
 steady-state data item 58  
 steady-state dose 60  
 steady-state doses, multiple 63  
 steady-state level 61-62, 64  
 STIELTJES option of \$ESTIMATION record 153, 161  
 STRAT,STRATF option of \$SIMULATION record 147, 154  
 structural model 23, 36, 98, 113  
 SUBPROBLEM option of \$SIMULATION record 145  
 subroutine, generated 6  
 subroutine, user-supplied 6  
 subroutine, user-written 150  
 \$SUBROUTINES record 150  
 \$SUBROUTINE record 135  
 \$SUBROUTINE record 71, 73, 98  
 sum of squares 11, 41  
 summary utility 161  
 superposition 63  
 superproblem 145  
 \$SUPER record 145  
 SUPRESET option of \$SIMULATION record 147  
 SVARF option of \$ESTIMATION record 161  
 symbolic label substitution 159  
 synonym 54  
 system, linear 63

**- T -**

table 57, 59, 92

table file, external 147  
 table step 104  
 table\_compare utility 160  
 table\_quant utility 160  
 table\_resample utility 160  
 table\_to\_xml utility 161  
 \$TABLE record 87, 92-93, 97  
 tabs in data file 158  
 tag label # output 155  
 TAN 73  
 TBLN option of \$ESTIMATION record 161  
 TEMPLT reserved variable 150, 153  
 THBND option of \$COVARIANCE record 169  
 theophylline example 8  
 THETA 10, 73  
 theta, initial estimate of 87  
 THETABOUNDTEST option of \$ESTIMATION record 161  
 THETAFR reserved variable 160  
 \$THETAI record 154  
 \$THETAP record 154  
 \$THETAR record 154  
 \$THETA record 10, 87, 97  
 THIN option of \$ESTIMATION record 161  
 TIME data item 56  
 TIME data item, colon ":" in 66  
 TIME option of \$DATA record 158  
 time varying parameter 35  
 time, relative 56, 66  
 TIME/24 54, 67  
 TNPRI subroutine 151  
 to NONMEM Outputs, Changes 155  
 TO option of \$SCATTERPLOT record 105  
 TOL option of \$COVARIANCE record 135, 169  
 TOL option of \$ESTIMATION record 135  
 TOL option of \$SUBROUTINE record 135  
 TOL subroutine 133  
 \$TOL record 135  
 TPU option of \$ESTIMATION record 161  
 TRANS 4, 24, 72  
 TRANS1 73  
 transgeneration 139, 159  
 TRANSLATE option of \$DATA record 54, 67, 158  
 translation 24, 72, 99  
 TRANSLATOR error message 175  
 TRANSLATOR warning message 5  
 TRUE option of \$SIMULATION record 147  
 true-value variable 81  
 TSTATE reserved variable 157  
 TTDF option of \$ESTIMATION record 161  
 TTDF option of \$SIMULATION record 147  
 typical value 36, 80, 90

**- U -**

UNCONDITIONAL option of \$COVARIANCE record 144, 169  
 UNCONDITIONAL option of \$SCATTERPLOT record 92  
 UNCONDITIONAL option of \$TABLE record 92  
 UNCONSTRAINED ETAS 141, 154  
 unexplained variability 120, 127  
 UNIFORM option of \$SIMULATION record 147  
 UNIT option of \$SCATTERPLOT record 93  
 unit slope line 11, 93  
 units 24, 77  
 upper case 158  
 urine collection 30, 64

urine concentration 25, 30, 35, 38, 64  
urine volume 25, 30, 64  
user-defined model 134  
user-supplied subroutine 6  
user-written subroutine 150  
USMETA subroutine 150

**- V -**

V, volume of distribution 8, 24-25  
value, null 46  
value, observed 4, 55-56, 90  
value, predicted 4, 56  
value, typical 36, 80, 90  
VALUES option of \$OMEGA record 142  
VALUES option of \$SIGMA record 142  
VARCALC 156  
variability, interindividual 36  
variability, intraindividual 25, 36  
variability, unexplained 120, 127  
variable, dependent 8-9, 23  
variable, indicator 29, 35, 77, 81, 85-86  
variable, random 6, 73, 81, 84  
variance 10, 36  
VARIANCE option of \$OMEGA record 141  
VARIANCE option of \$SIGMA record 141  
variance-covariance matrix 42  
variance-covariance matrix, diagonal 89, 140  
VECTRA reserved variable 159  
VERSION option of \$MSFI record 143  
volume of distribution V 8, 24-25

**- W -**

warning message, TRANSLATOR 5  
weighted least squares WLS 41  
weighted residual 92  
weighted residual WRES 92, 116, 118  
WIDE option of \$DATA record 53  
WLS, weighted least squares 41  
WRES, weighted residual 92, 116, 118  
WRESCHOL option of \$TABLE record 148

**- X -**

LNTWOPI 161  
xml\_compare utility 161  
XVID1-5 data item 156

**- Y -**

y 23  
year 2000 54  
YLO YUP reserved variable 154

**- Z -**

ZERO option of \$ESTIMATION record 153, 161  
zero-order bolus dose 135-136  
zero-out a compartment 72